

- ALL GATE MATERIAL MUST BE GALVANIZED AFTER FABRICATION.
- ALL 40 DIA. PIPE MUST BE STD. SCHEDULE 40 NEW BUTT WELD PIPE.
- GATE POST TO EXTEND A MIN. OF 1000 INTO FOUNDATION SLEEVE PIPE.
- PIN IS WELDED TO GATE WITH A 300 LONG GALV. CHAIN. 4.
- DIRECTIONAL SIGN TO BE MIN. 1.5 MM TK ALUMINUM OR GALVANIZED METAL RIVETTED TO GATE AT EACH CORNER ON EACH SIDE OF GATE.
- ALL WELDING AND GALVANIZING DRIPS AND SPLATTERS TO BE REMOVED 6.
- 7. 40MM O.D STEEL HANDRAIL ARE TO BE CONTINUOUS PIPE.
- ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE NOTED.
- THE LOCATION OF THE GATE IS TO BE APPROVED BY A COMMUNITY SERVICES REPRESENTATIVE.
- 10. FOR ASPHALT REFER TO C.S. DETAIL 02510-1.
- 11. PADLOCK TO BE PROVIDED BY THE COMMUNITY SERVICES DEPARTMENT.



SCALE: N.T.S.

DATE: FEBRUARY 9, 2005 DRAWN BY: P & H, D NUMBER: 02870-2