
PART I - GENERAL

- 1.1 Related Work .1 Rough Grading : Section 02211
- 1.2 Scope of Work .1 The contractor is to supply all necessary labour and materials for this work as shown on the drawings and as specified herein.
- .2 Supply and install granular material in accordance with Standard Detail #02511-1 and approved working drawings.
- .3 Coordinate work in this section with work in all other sections.
- 1.3 Guarantee .1 The contractor shall guarantee all material and workmanship for a period of two years from the date of Preliminary Acceptance by the City.

PART II - PRODUCTS

- 2.1 Materials .1 All material shall be free from clay lumps, cementation, organic material, frozen material and other deleterious material, meeting all OPSS Standards 1001, 1004 and 1010.
- .2 Base material shall be Granular 'A' as per OPSS Standard 1010.05.02
- .3 Sub-base material shall be Granular 'B' as per OPSS Standard 1010.05.03
- .4 Water for compaction to be clean and potable.

PART III - EXECUTION

- 3.1 Excavating .1 Strip all topsoil and sod to a depth and to a width as indicated on the drawings.
- .2 Ensure edges and bottom of excavation are in a smooth, even line and adjacent grass areas are not contaminated with excavated sod and topsoil.
- .3 Subgrade shall be compacted to 98% Standard Proctor Density.

- .4 Remove all soft areas and replace with approved material compacted to 98% Standard Proctor Density.
- 3.2 Granular
- .1 Place granular material in accordance with Standard Detail #02511-1 and compact to 98% Standard Proctor Maximum Dry Density.
- .2 Rake and compact the granular surface free from ridges or hollows.
- 3.3 Testing and Quality Control
- .1 Inspection and compaction tests of subbase and granular material will be carried out by an independent testing laboratory. Costs of tests will be paid for by the contractor. Subbase tests shall be submitted to the City for approval prior to the installation of the granular material.
- 3.4 Maintenance
- .1 The contractor shall maintain all work to the desired grade and thickness for a period of two years from the date of Preliminary Acceptance by the City.

END OF SECTION 02512