

Noise Impact Study

**1225 Dundas Street East,
Mississauga, Ontario
SW22159.00**

Prepared For

Daniel Orellana, B.U.R.PL

**Dundix Realty Holdings c/o SmartCentres REIT
3200 Highway 7**

Vaughan, ON L4K 5Z5

Tel: +1 905.760.6200

dorellana@smartcentres.com

Prepared By

Robert Fuller, P.Eng.

Thornton Tomasetti

23-366 Revus Avenue

Mississauga, Ontario L5G 4S5

Tel: +1 647.769.7161

RFuller@ThorntonTomasetti.com

www.ThorntonTomasetti.com

Reviewed By

Stephen McCann, P.Eng.

Associate

June 28, 2022

Table of Contents

Table of Contents	i
List of Tables	ii
List of Figures	ii
1.0 Introduction	1
2.0 Site and Surrounding Area	1
2.1 Project Location	1
2.2 Zoning & Official Plan	1
2.3 Planned Development	1
2.4 Site Inspection	2
2.1 Topography	2
3.0 Ministry of the Environment Conservation and Parks	2
4.0 Land Use Planning Authority	2
4.1 Region of Peel	2
4.2 City of Mississauga	2
5.0 Transportation Noise Assessment	3
5.1 Critical Transportation Noise Receptors	3
5.2 Transportation Noise Sources	4
5.2.1 Road Noise Sources	4
5.2.2 Rail Noise Sources	5
5.2.3 Aircraft Noise Sources	5
5.3 Transportation Sound Level Limits	5
5.3.1 Outdoor Living Areas	5
5.3.2 Indoor Living Areas	5
5.4 Transportation Sound Level Predictions	6
5.4.1 Road Traffic	6
5.5 Transportation Noise Control Recommendations	7
5.5.1 Outdoor Living Areas – Barriers	7
5.5.2 Indoor Living Areas - Ventilation	8
5.5.3 Indoor Living Areas - Building Components	8
5.5.4 Example Constructions	9
5.5.5 Warning Clauses	10
6.0 Stationary Noise Assessment	10
6.1 Critical Stationary Noise Receptors	10
6.1.1 Project Receptors	11
6.1.2 Surrounding Receptors	11
6.2 Stationary Noise Sources	12
6.2.1 Project Sources	12
6.2.2 Surrounding Sources	13
6.3 Project Area Classification	13

6.3.1 Class 1 Area Exclusionary Sound Level Limits	13
6.4 Stationary Sound Level Predictions	14
6.4.1 Stationary Noise Impacts on the Project.....	14
6.4.2 Project Stationary Noise Impacts on the Surrounding Area.....	15
6.5 Stationary Noise Mitigation Recommendations	15
6.5.1 Mitigation for Project Receptors	15
6.5.2 Mitigation for Surrounding Receptors	15
7.0 Concluding Comments	16
Disclaimer	16

Appendix A : Figures

Appendix B : Traffic Data

Appendix C : Transportation Noise Predictions

Appendix D : Manufacturer Specifications

Appendix E : CadnaA Calculation Output

List of Tables

Table 1: Construction Elevations – Transportation Receptors	3
Table 2: Points of Reception – Transportation Noise	3
Table 3: Traffic Data Summary.....	4
Table 4: Traffic Data Summary.....	4
Table 5: MECP Outdoor Sound Level Limit & Mitigation for OLAs – Combined Road & Rail Traffic.....	5
Table 6: MECP POW Sound Level Limit: Ventilation & Warning Clauses – Combined Road & Rail Traffic.....	5
Table 7: MECP Indoor Sound Level Limit & Construction Requirements – Road & Rail Traffic.....	6
Table 8: Calculated Sound Levels due to Road Sources.....	7
Table 9: Transportation Noise Control Measures Summary	7
Table 10: OLA Barrier Specifications	8
Table 11: Building Envelope Requirements	9
Table 12: Project Points of Reception – Stationary Noise.....	11
Table 13: Surrounding Points of Reception – Stationary Noise	11
Table 14: Project Stationary Noise Sources.....	12
Table 15: Surrounding Stationary Noise Sources.....	13
Table 16: Class 1 Exclusionary Sound Level Limits – Steady Noise.....	14
Table 17: Predicted Stationary Noise Source Impacts to the Project	14
Table 18: Predicted Stationary Noise Source Impacts To The Surrounding Area.....	15

List of Figures

Figure 1: Project Location & Surroundings	17
Figure 2: Zoning Map	17
Figure 3: Project Site Plan	17
Figure 4: Transportation Noise PORs & Sources	17
Figure 5: Stationary Noise PORs & Sources	17
Figure 6: Recommended Mitigation Measures	17

1.0 Introduction

At the request of Dundix Realty Holdings c/o SmartCentres REIT (Client), Thornton Tomasetti (TT) presents this Noise Impact Study (NIS) regarding the planned development located at 1225 Dundas Street East, Mississauga Ontario (the Project).

The purpose of this study is to assess the noise impact on the Project from surrounding noise sources and the noise impact of the Project on surrounding noise sensitive areas. This report is intended to support the Zoning By-Law Amendment (ZBA) and Site Plan Approval (SPA) application for the Project as a feasibility study.

Where applicable, this report will provide noise control recommendations to meet the requirements of the applicable Land Use Planning Authority (LUPA), and noise criteria developed by the Ontario Ministry of the Environment, Conservation and Parks (MECP).

Where predicted sound impacts are lower than applicable action thresholds identified, the project should be designed to meet the Ontario Building Code (OBC) as a minimum standard.

2.0 Site and Surrounding Area

2.1 Project Location

The Project is located on the north corner of the intersection of Dundas Street East and Arena Road, approximately 400m southwest of Dixie Road.

The Project is bordered on the north and west by residential land uses. The Project is bordered on the east and south by commercial land uses. The broader neighborhood includes residential land uses northwest of Dundas Street East, and commercial land uses southeast of Dundas Street East.

An illustration of the project location and surrounding area is provided in Figure 1.

2.2 Zoning & Official Plan

The Project site is zoned as C3 “General Commercial” under the City of Mississauga Zoning By-Law No. 0225-2007, and designated as “Mixed Use” under the City of Mississauga’s Official Plan. Surrounding areas are zoned for residential, commercial and employment uses.

A zoning map is presented in Figure 2.

2.3 Planned Development

The Project will consist of a 12 storey residential building plus 34 townhomes. The Project is expected to include two standby power generators and centralized heating, ventilation and air conditioning (HVAC) equipment. The Project will have a maximum height of approximately 41m.

The proposed new site plan is provided in Figure 3.

2.4 Site Inspection

TT personnel attended the Project site on June 21, 2022 in order to inspect the acoustical environment in the area of the Project. The ambient sound environment was observed to be dominated by traffic noise from the adjacent Dundas Street East.

Transportation noise from adjacent roadways is discussed in Section 5.0 of this report.

No individual stationary noise sources were distinguishable from the Project site, but an inspection of publicly accessible areas of the surrounding neighborhood did identify potentially significant stationary noise sources (roof top HVAC units). Stationary noise sources are discussed in Section 6.0 of this report.

2.1 Topography

Based on the observed and/or reported conditions on and around the Project site, the local topography is expected to be approximately flat.

3.0 Ministry of the Environment Conservation and Parks

The MECP's *Environmental Noise Guideline – Stationary and Transportation Sources – Approval and Planning* (NPC-300) provides province wide assessment standards and criteria for evaluating noise impacts from transportation sources such as roads, railways and aircraft, as well as stationary sources such as mechanical equipment, and industrial facilities. In preparing this NIS report, TT has referred to *Part A Background and Part C Land Use Planning* of NPC-300.

This NIS report has been prepared to support land use planning decisions, and is not intended to support an application for an Environmental Compliance Approval (ECA) in accordance with *Part B Stationary Sources* of NPC-300, and Section 9 of the Environmental Protection Act.

4.0 Land Use Planning Authority

In addition to the MECP's standards and criteria, some LUPAs impose additional requirements on applications for development approval. The LUPAs for this Project are the Region of Peel and the City of Mississauga.

4.1 Region of Peel

Peel Region defers to the MECP and municipalities in regard to noise by-laws and regulations.

4.2 City of Mississauga

The City of Mississauga's Noise Study Terms of Reference generally align with the requirements of NPC-300, with the following exceptions:

- The impact of noise from the proposed development on itself should also be considered.
- Road traffic data must be obtained from the City when analyzing transportation noise from City roads.

5.0 Transportation Noise Assessment

5.1 Critical Transportation Noise Receptors

NPC-300 defines a point of reception for the assessment of transportation noise sources as either the Plane of Window (POW) of a noise sensitive indoor space or an Outdoor Living Area (OLA) representing an area of a noise sensitive land use intended for quiet enjoyment of the outdoor environment.

The POW receptor(s) most likely to be affected by transportation noise are those representing the residential suites of the Project that have maximum exposure to Dundas Street East. Specifically, POW receptors were assessed for the northeast, southeast and southwest facades of the planned structures, at the highest elevation with windows.

Based on provided site plans of the Project, TT has assessed a total of 3 potential OLAs, including the Level 10 Roof Terrace, and ground level gardens located on the northeast and southwest corners of the townhomes. Individual suites will have balconies, and there will be other terraces, however because these are less than 4m in depth they have not been considered as OLAs.

The elevation of each level of the Project is illustrated in Figure 3 and summarized in Table 1.

Table 1: Construction Elevations – Transportation Receptors

Floor Level	Elevation (m)	Floor-to-Floor Height (m)	Midpoint Height (m)
Street Level (Dundas)	120.0	-	-
Townhouse 3 rd Floor	127.9	3.25	9.5
Tower 10 th Floor	151.2	3.25	-
Tower 12 th Floor	157.4	4.10	39.5

The locations of the critical receptors for transportation noise are summarized in Table 2 and shown in Figure 4. POW elevations were taken to be the midpoint height of the highest floor with windows, and OLA elevations were taken to be 1.5m above the applicable floor level.

Table 2: Points of Reception – Transportation Noise

Receptor ID	Receptor Description	Receptor Location
POW1	Tower, northeast façade	North tower centre, 39.5m above ground
POW2	Tower, southeast façade	South tower centre, 39.5m above ground
POW3	Tower, southwest façade	South tower centre, 39.5m above ground
POW4	Townhome, northeast corner	Corner, 9.5m above ground
POW5	Townhome, southwest corner	Corner, 9.5m above ground
OLA1	Tower, 10 th floor terrace	Terrace centre, 32.7m above ground
OLA2	Townhome, northeast garden	3m from façade, 1.5m above ground
OLA3	Townhome, southwest garden	3m from façade, 1.5m above ground

5.2 Transportation Noise Sources

5.2.1 Road Noise Sources

Dundas Street East (adjacent to the southeast), and Arena Road (adjacent to the southwest) represent the most significant road noise sources for the Project. Traffic data was obtained from a draft Transportation Impact Study prepared for the Project by CGH Transportation, dated June 2022. This data is presented in Appendix B.

The highest hourly volumes of cars, trucks and busses recorded in the TMC data were identified and converted to AADT values by adding the AM and PM peak hour volumes together and multiplying by 5. AADT estimates are summarized in Table 3.

Table 3: Traffic Data Summary

Street	Section	Time Period	Cars		Trucks & Buses		Total
			Year	Volume	Year	Volume	
Dundas Street East	East of Arena Road	AM Peak	2022	1,903	2022	105	24,610
		PM Peak	2022	2,838	2022	76	
		Daily	2022	23,705	2022	905	
Arena Road	North of Dundas Street East	AM Peak	2022	77	2022	3	955
		PM Peak	2022	110	2022	1	
		Daily	2022	935	2022	20	

The total Annual Average Daily Traffic (AADT) was projected forward to 2035 (10 years after expected completion) using a growth rate of 2% per year from the noted year of measurement.

Medium and heavy truck percentages were estimated based on the volume of trucks and buses as a % of total traffic, assuming that 25% of the combined truck & bus volume would be considered “heavy trucks”, and 75% of the combined volume would be considered “medium trucks”.

Posted speed limits on Dundas Street East and Arena Road are 60 and 40 km/hr respectively. Road grades were assumed to be 0% in the area under review. The day/night split was assumed to be 90%/10% on Dundas Street East and 70%/30% on Arena Road.

Because Dundas Street East is six lanes, it was considered to be two separate roads, each of which was assigned half of the AADT.

The traffic data used in the sound level calculations is summarized in Table 4.

Table 4: Traffic Data Summary

Parameter	Dundas Street East (Westbound)	Dundas Street East (Eastbound)	Arena Road
AADT	12,305 (2022)	12,305 (2022)	955 (2022)
% Annual Growth	2%	2%	2%
Years of Annual Growth	13	13	13
% Medium Trucks	3%	3%	2%
% Heavy Trucks	1%	1%	1%

Parameter	Dundas Street East (Westbound)	Dundas Street East (Eastbound)	Arena Road
% Day (16h) / Night (8h)	90% / 10%	90% / 10%	70% / 30%
Speed Limit	60 km/hr	60 km/hr	40 km/hr
Gradient	0%	0%	0%

5.2.2 Rail Noise Sources

No rail noise sources located within 400m of the Project have been identified.

5.2.3 Aircraft Noise Sources

No airports located in the vicinity of the project have been identified.

5.3 Transportation Sound Level Limits

5.3.1 Outdoor Living Areas

Impacts to OLAs from combined road and rail traffic are assessed against a 16-hour daytime (07:00 – 23:00) equivalent sound pressure level (L_{eq}) reported in dBA. The MECP outdoor sound level limits and the sliding scale of required noise reduction measures for road and rail noise at OLAs are listed in Table 5. Note that whistle noise is not included in the assessment of rail noise at an OLA.

Table 5: MECP Outdoor Sound Level Limit & Mitigation for OLAs – Combined Road & Rail Traffic

Category	Sound Level $L_{eq,16hr}$ (dBA)	Mitigation Measures	NPC-300 Warning Clause Required
Outdoor Limit	55	None	None
OLA Mitigation Threshold	56 - 60	Optional	Type A unless sound level brought below 55 dBA
OLA Mitigation Threshold	>60	Required to achieve sound level below 60 dBA	Type B unless sound level brought below 55 dBA

5.3.2 Indoor Living Areas

Impacts to POWs from combined road and rail (if applicable) traffic are assessed against a 16-hour daytime (07:00 – 23:00) and 8-hour nighttime (23:00 – 07:00) equivalent sound pressure level (L_{eq}) reported in dBA. The combined impact is used to determine the requirement for ventilation and warning clauses. The MECP POW sound level limits and the sliding scale of required noise reduction measures for combined road and rail noise at POWs are listed in Table 6. Note that whistle noise is not included in the assessment of rail noise for this purpose.

Table 6: MECP POW Sound Level Limit: Ventilation & Warning Clauses – Combined Road & Rail Traffic

Category	Daytime $L_{eq,16hr}$ (dBA)	Nighttime $L_{eq,8hr}$ (dBA)	Mitigation Measures	NPC-300 Warning Clause Required
POW Limit	55	50	None	None
POW Mitigation Threshold Living & Bedrooms	56 - 65	51 – 60	Include forced air heating and provision for central air conditioning	Type C

Category	Daytime L _{eq,16hr} (dBA)	Nighttime L _{eq,8hr} (dBA)	Mitigation Measures	NPC-300 Warning Clause Required
POW Mitigation Threshold Living & Bedrooms	>65	>60	Include central air conditioning	Type D

Impacts to indoor noise levels from road and rail (if applicable) traffic are assessed against a 16-hour daytime (07:00 – 23:00) and 8-hour nighttime (23:00 – 07:00) equivalent sound pressure level (L_{eq}) reported in dBA at the POW receptor. The requirements for building construction to address transportation noise impacts to indoor sound levels are determined independently for road and rail noise, with the resulting requirements then being combined logarithmically. The MECP indoor sound level limits and the required noise reduction measures for road and rail noise at POWs are listed in Table 7. Note that whistle noise is included in the assessment of rail noise for this purpose.

Table 7: MECP Indoor Sound Level Limit & Construction Requirements – Road & Rail Traffic

Category	Daytime L _{eq,16hr} (dBA)	Nighttime L _{eq,8hr} (dBA)	Total L _{eq,24hr} (dBA)	Mitigation Measures
Road Indoor Limit Living Rooms / Bedrooms	45 / 45	45 / 40	-	Not Applicable
Road POW Mitigation Threshold Living & Bedrooms	>65	>60	-	Design building components to achieve indoor sound level limit
Rail Indoor Limit Living Rooms / Bedrooms	40 / 40	40 / 35	-	Not Applicable
Rail POW Mitigation Threshold Living & Bedrooms	>60	>55	-	Design building components to achieve indoor sound level limit
Rail POW Mitigation Threshold Bedrooms	-	-	>60	Minimum of brick veneer or masonry equivalent construction from foundation to rafters in first row of dwellings if within 100m of tracks

5.4 Transportation Sound Level Predictions

5.4.1 Road Traffic

Calculations of road traffic sound levels were performed using STAMSON 5.04, the software implementation of the MECP ORNAMENT model, which was developed and published by the MECP for transportation noise prediction. Only daytime sound levels are considered for outdoor amenity areas. The calculated sound levels at the receptors are presented in Table 8.

Table 8: Calculated Sound Levels due to Road Sources

POR ID	Predicted Transportation Sound Levels (dBA)	
	Daytime (07:00–23:00) $L_{eq,16hr}$	Nighttime (23:00–07:00) $L_{eq,8hr}$
POW1	61	54
POW2	67	61
POW3	61	55
POW4	54	47
POW5	59	54
OLA1	51	-
OLA2	54	-
OLA3	59	-

The STAMSON calculation outputs for the traffic noise predictions are attached in Appendix C.

5.5 Transportation Noise Control Recommendations

Noise control recommendations for the identified critical receptors and the corresponding noise sensitive land uses that they represent in the proposed redevelopment are summarized in Table 9 and discussed in the subsequent sections.

Table 9: Transportation Noise Control Measures Summary

POR ID	Noise Barrier	Ventilation	Building Components	Warning Clause
POW1	N/A	Forced-Air Heating	Meet OBC Requirements	Type C
POW2	N/A	Central Air Conditioning	Designed to achieve indoor sound level criteria	Type D
POW3	N/A	Forced-Air Heating	Meet OBC Requirements	Type C
POW4	N/A	None	Meet OBC Requirements	Type C
POW5	N/A	Forced-Air Heating	Meet OBC Requirements	Type C
OLA1	No	N/A	N/A	None
OLA2	No	N/A	N/A	None
OLA3	Optional	N/A	N/A	Type A*

*Unless mitigation (barrier) is installed to reduce the sound level to 55 dBA or lower.

5.5.1 Outdoor Living Areas – Barriers

Sound levels at the OLA associated with the 10th floor terrace and north townhouses are expected to be equal to or lower than 55 dBA, and no additional noise mitigation is required for these OLAs.

Sound levels at the OLAs associated with the rear yard of the south townhouses are expected to be greater than 55 dBA and equal to or lower than 60 dBA, and therefore it may be desirable to implement a noise barrier in order to reduce the sound level to 55 dBA or less at this OLA. NPC-300 requires either the implementation of such a barrier, or the inclusion of a Type A warning clause in applicable land title and/or development agreement documents. If noise mitigation for the OLAs is implemented such that the sound levels in the OLAs is expected to be 55 dBA or lower, no warning clause is required.

Proposed noise barrier heights for OLAs are summarized in Table 10 and illustrated in Figure 6.

Table 10: OLA Barrier Specifications

Receptor ID	Mitigation Level	Predicted Sound Level $L_{eq}(16h, day)$ dBA
OLA3	Unmitigated	59
	Barrier Option 1: South of Townhouses 1.5m height above ground	55

Noise barriers, if constructed, should have a minimum surface density (face weight) of 20 kg/m². Barriers should be structurally sound, appropriately designed to withstand wind and snow load, and constructed without cracks or surface gaps. Any gaps under the barrier that are necessary for drainage purposes should be minimized and localized, so that the acoustical performance of the barrier is maintained. To improve the visual characteristics of the barrier, transparent elements may be included, if they meet the above conditions.

5.5.2 Indoor Living Areas - Ventilation

Sensitive receptors along the southeast façades of the main tower are expected to face POW sound levels above 65 dBA during the 16-hour day (07:00 – 23:00) and/or 60 dBA during the 8-hour night (23:00 – 07:00) due to road noise, therefore central air conditioning will be required for these units.

Sensitive receptors along the northeast and southwest façades of the main tower and the southeast and southwest façades of the townhouses are expected to face POW sound levels between 55 dBA and 65 dBA during the 16-hour day (07:00 – 23:00) and/or 50 dBA and 60 dBA during the 8-hour night (23:00 – 07:00) due to road, therefore forced air heating with the provision for central air conditioning is the minimum requirement for these units.

Sensitive receptors along the other façades of the Project are expected to face POW sound levels below 55 dBA during the 16-hour day (07:00 – 23:00) and/or 50 dBA during the 8-hour night (23:00 – 07:00) due to road noise, therefore no specific ventilation requirements apply for the purposes of addressing transportation noise.

TT understands that the Project plan includes forced air heating and central air conditioning for the entirety of the Project, therefore the above noted requirements are expected to be met.

5.5.3 Indoor Living Areas - Building Components

Sensitive receptors along the southeast façades of the Project are expected to face POW sound levels above 65 dBA during the 16-hour day (07:00 – 23:00) and/or 60 dBA during the 8-hour night (23:00 – 07:00) due to road noise, therefore building components on these façades must be designed to achieve the indoor sound level limit.

Sensitive receptors along the other façades of the Project are not expected to face POW sound levels above 65 dBA during the 16-hour day (07:00 – 23:00) and/or 60 dBA during the 8-hour night (23:00 – 07:00) due to road noise, therefore building components on these façades need only be designed to meet the requirements of OBC.

As the building design is at an early stage, the construction of the building envelope is not yet confirmed.

Table 11 shows TT's estimation of the maximum exterior wall, fixed window, and operable window component areas as a percentage of the floor area of a typical room and the minimum recommended STC requirement of each component. If a component with a higher STC rating than the noted requirement is used, then the maximum allowable area of that component may increase.

Table 11: Building Envelope Requirements

Component	Maximum Component Area as Percentage of Floor Area	STC Required
Sensitive Spaces Along the Southeast Facades of the Project		
Solid Exterior	100%	36
Fixed Glazing	50%	32
Operable Glazing	50%	32

Note that these building components are required only for exterior walls of sensitive spaces, such as bedrooms and living rooms. The remaining façades of the Project must meet minimum OBC requirements for the glazing and exterior wall constructions.

5.5.4 Example Constructions

Unless otherwise specified, all building components must meet the minimum STC requirements set out in OBC. Examples of building components that meet the identified STC requirements above are as follows.

Exterior wall

For exterior walls, the following construction(s) are recommended in order to meet the identified STC requirements:

- Southeast façade, solid exterior (STC 36):
 - 12.7mm gypsum board
 - vapour barrier
 - 38 x 89 mm studs
 - 50 mm (or thicker) mineral wool or glass fibre batts
 - sheathing
 - wood siding or metal siding and fibre backer board

Glazing

For operable windows, the following glazing constructions are recommended in order to meet the identified STC requirements:

- Southeast façade, operable window (STC 32): 3mm glass, 20mm airspace, 3mm glass

For fixed windows, the following glazing constructions are recommended in order to meet the identified STC requirements:

- Southeast façade, inoperable window (STC 32): 3mm glass, 6mm airspace, 3mm glass

These provided glazing constructions are noted for reference only – STC of installed components should be verified with the glazing manufacturer. Any glazing constructions with equivalent or greater STC values will be acceptable.

5.5.5 Warning Clauses

The **Type A** warning clause is required to be included in the development agreements for the Project if one or more representative OLA receptors is predicted to be exposed to transportation sound pressure levels greater than 55 dBA and less than or equal to 60 dBA, and mitigations to reduce the sound level to 55 dBA or less are not provided. The Type A warning clause is as follows:

“Purchasers/tenants are advised that sound levels due to increasing road traffic may occasionally interfere with some activities of the dwelling occupants as the sound levels exceed the sound level limits of the Municipality and the Ministry of the Environment, Conservation and Parks.”

The **Type C** warning clause is required to be included in the development agreements for specific dwelling units if one or more representative POW receptors is predicted to be exposed to transportation sound pressure levels greater than 55 dBA and less than or equal to 65 dBA during the 16-hour day (07:00 – 23:00) or greater than 50 dBA and less than or equal to 60 dBA during the 8-hour night (23:00 – 07:00), and the Project includes forced air heating with the provision for installation of central air conditioning in the future. The Type C warning clause is as follows:

“This dwelling unit has been designed with the provision for adding central air conditioning at the occupant’s discretion. Installation of central air conditioning by the occupant in low and medium density developments will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the sound level limits of the Municipality and the Ministry of the Environment, Conservation and Parks.”

The **Type D** warning clause is required to be included in the development agreements for specific dwelling units if one or more representative POW receptors is predicted to be exposed to transportation sound pressure levels greater than 65 dBA during the 16-hour day (07:00 – 23:00) or 60 dBA during the 8-hour night (23:00 – 07:00), and the Project includes central air conditioning. The Type D warning clause is as follows:

“This dwelling unit has been supplied with a central air conditioning system which will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the sound level limits of the Municipality and the Ministry of the Environment, Conservation and Parks.”

6.0 Stationary Noise Assessment

6.1 Critical Stationary Noise Receptors

NPC-300 defines a point of reception for the assessment of stationary noise sources as any location on a noise sensitive land use where noise from a stationary source is received. This typically includes both

points of reception on building façades, representing the plane-of-window of noise sensitive spaces (POR) and outdoor points of reception representing areas such as balconies, gardens, patios, and terraces (OPOR). These locations may be the same or different from the POW and OLA receptors identified as part of a transportation noise assessment.

6.1.1 Project Receptors

The project point of reception (PPOR) and project outdoor point of reception (POPOR) receptor(s) on the Project most likely to be affected by stationary noise sources are those representing the residential suites that have maximum exposure to stationary noise sources associated with the surrounding properties in each direction, and the project itself.

Based on provided site plans of the Project, TT understands that the 10th floor terrace will represent the most impacted POPOR at the Project. Individual suites and lower floors will have balconies and terraces, however because these are less than 4m in depth they have not been considered as POPORs.

The locations of the critical receptors on the Project for stationary noise are summarized in Table 12 and shown in Figure 5. PPORs were assessed using a grid of receptors across the full facade, and POPORs were assessed at the most impacted point within 30m of a building façade, 1.5m above ground/floor level.

Table 12: Project Points of Reception – Stationary Noise

Receptor ID	Receptor Description	Receptor Location
PPOR1	North tower	Building evaluation of full façades
PPOR2	Central & lower towers	Building evaluation of full façades
PPOR3	South tower	Building evaluation of full façades
PPOR4	Northeast townhouses	Building evaluation of full façades
PPOR5	Southwest townhouses	Building evaluation of full façades
POPOR1	10 th floor terrace	SE area, 32.7m above ground

6.1.2 Surrounding Receptors

The surrounding point of reception (SPOR) and surrounding outdoor point of reception (SOPOR) receptor(s) most likely to be affected by stationary noise from the Project include those associated with residential areas to the north and west of the Project. Areas south and east of the project are commercial properties and therefore not considered to be noise sensitive.

The locations of the critical receptors in the surrounding area for stationary noise from the Project are summarized in Table 13, and shown in Figure 5. SPORs and SOPORs were assessed at the most impacted points associated with each cardinal direction.

Table 13: Surrounding Points of Reception – Stationary Noise

Receptor ID	Receptor Description	Receptor Location
SPOR1	Townhouses southwest of Project	3 rd floor (7.5m), northeast façade centre, 1168 Arena Road

Receptor ID	Receptor Description	Receptor Location
SPOR2	Townhouses northwest of Project	3 rd floor (7.5m), southeast façade centre, 3070 Queen Frederica Drive
SPOR3	Residential tower northeast of Project	6 th floor (16m), southwest façade centre, 3020 Queen Frederica Drive
SOPOR1	Townhouses southwest of Project	Rear yard of 1168 Arena Road, 1.5m above ground
SOPOR2	Townhouses northwest of Project	Rear yard of 3070 Queen Frederica Drive, 1.5m above ground
SOPOR3	Residential tower northeast of Project	Rear yard of 3020 Queen Frederica Drive, 1.5m above ground

6.2 Stationary Noise Sources

NPC-300 defines a stationary source of noise as one or more sources of sound that are normally operated within a given property. Stationary sources typically include mechanical equipment such as Heating, Ventilation and Air Conditioning (HVAC) equipment, standby power generators with routine testing, and heavy vehicle traffic (truck idling, driving, and loading).

Certain sources of noise, such as residential air conditioners, passenger automobile traffic in parking lots, or temporary noise such as that related to construction are not considered to be stationary sources in NPC-300 and are not assessed in this report.

6.2.1 Project Sources

Due to the early stage of planning for the Project, detailed information regarding stationary noise sources at the project is not currently available. Source sound power levels identified in this report are estimated and provided for preliminary planning purposes only, this information will need to be confirmed in a future revision to this report and may rise or fall. Table 14 and Figure 5 provide a summary of the assumed Project stationary source data.

Table 14: Project Stationary Noise Sources

Source ID	Source Description	Source Location	Source Sound Power	Source Type	Notes & Assumptions
			dBA		
PHVAC1	Roof Top HVAC	North Tower Roof	90*	Steady	60 min/hr (07:00 – 23:00) 30 min/hr (23:00 – 07:00)
PHVAC2	Roof Top HVAC	South Tower Roof	90*	Steady	60 min/hr (07:00 – 23:00) 30 min/hr (23:00 – 07:00)
PGEN1	Standby generator	North Tower Roof	102*	Emergency	Daytime only

*Sound power level assumed.

6.2.2 Surrounding Sources

Based on a review of satellite imagery, and field inspection, exterior HVAC equipment has been identified in the area surrounding the project. Table 15 and Figure 5 provide a summary of the assumed surrounding stationary source data. Because TT was unable to inspect equipment installed on surrounding properties, the following assumptions have been made:

- Equipment with no visible fans was assumed to be heating only, and/or located in an acoustical enclosure, therefore noise impacts from this equipment are assumed to be negligible;
- “Small” HVAC equipment (1-2 visible fans) was assumed to have a sound power level of approximately 78-82 dBA (based on Carrier model 48HCA05 and 48HCD08)

Table 15: Surrounding Stationary Noise Sources

Source ID	Source Description	Source Location	Source Sound Power	Source Type	Notes & Assumptions
			dBA		
SHVAC01 – SHVAC38	“Small” HVAC units	Surrounding roof tops	78 - 82	Steady	60 min/hr (07:00 – 23:00) 30 min/hr (23:00 – 07:00)

6.3 Project Area Classification

NPC-300 defines the applicable sound pressure level limit at a given receptor as the higher of a set exclusionary sound level limit based on the area classification of that receptor, or the actual background sound level at the location of the receptor, whichever is higher. For the purposes of this report, the defined exclusionary limits were used for the purposes of assessing compliance.

The Project is considered to be located in a Class 1 area as defined in NPC-300, based on the surrounding area features and its distance from major roads.

6.3.1 Class 1 Area Exclusionary Sound Level Limits

NPC-300 defines a Class 1 area as having an acoustical environment typical of a major population centre, where the background sound level is dominated by the activities of people, usually road traffic, often referred to as “urban hum” during both day and night.

Table 16 provides a summary of the applicable exclusionary sound level limits for steady noise sources impacting receptors in a Class 1 area. Steady stationary noise sources are assessed against a 1 hour equivalent sound pressure level (L_{eq}) expressed in A-weighted decibels (dBA). Routine testing of emergency equipment, if applicable, is assessed separately from other stationary noise sources, and is compared to sound level limits that are 5 dBA higher than would otherwise apply.

Table 16: Class 1 Exclusionary Sound Level Limits – Steady Noise

Time Period	Normal Operations Steady Noise ($L_{eq,1hr}$, dBA)		Emergency Equipment Testing Steady Noise ($L_{eq,1hr}$, dBA)	
	POR	OPOR	POR	OPOR
Daytime (07:00 – 19:00)	50	50	55	55
Evening (19:00 – 23:00)	50	50	55	55
Nighttime (23:00 – 07:00)	45	-	50	-

6.4 Stationary Sound Level Predictions

Sound levels at the PORs due to the nearby stationary sources were calculated using the software CadnaA in accordance with the methods described in ISO 9613-2. The CadnaA calculation outputs are presented in Appendix D.

6.4.1 Stationary Noise Impacts on the Project

In modelling the impact of stationary noise sources to receptors located on the Project, TT has considered only the identified stationary sources associated with the surrounding area. The impact of stationary noise sources located on the project itself was not considered, as NPC-300 does not consider properties to be sensitive to their own noise sources.

Table 17 provides a summary of the modelling results for stationary noise impacts to the Project, and Appendix D contains the full modelling output and illustrations.

Table 17: Predicted Stationary Noise Source Impacts to the Project

POR ID	Time Period	Steady Sound Level $L_{eq,1hr}$ (dBA)	Steady Sound Level Limit $L_{eq,1hr}$ (dBA)	Compliance
PPOR1	Daytime	44	50	Yes
	Evening	44	50	Yes
	Nighttime	41	45	Yes
PPOR2	Daytime	48	50	Yes
	Evening	48	50	Yes
	Nighttime	45	45	Yes
PPOR3	Daytime	47	50	Yes
	Evening	47	50	Yes
	Nighttime	44	45	Yes
POPOR1	Daytime	43	50	Yes
	Evening	43	50	Yes

Noise due to stationary noise sources is predicted to meet the applicable sound level limits at all modeled receptors on the Project.

6.4.2 Project Stationary Noise Impacts on the Surrounding Area

In modelling the impact of stationary noise sources from the Project onto the surrounding area, TT has considered only the identified stationary sources associated with the project. The noise impact of existing stationary noise sources located in the surrounding area was not considered.

Table 18 provides a summary of the modelling results for stationary noise impacts to the surrounding area, and Appendix D contains the full modelling output and illustrations.

Table 18: Predicted Stationary Noise Source Impacts To The Surrounding Area

POR ID	Time Period	Steady Sound Level L _{eq,1hr} (dBA)	Steady Sound Level Limit L _{eq,1hr} (dBA)	Compliance
SPOR1	Daytime	43	50	Yes
	Evening	43	50	Yes
	Nighttime	40	45	Yes
SPOR2	Daytime	36	50	Yes
	Evening	36	50	Yes
	Nighttime	33	45	Yes
SPOR3	Daytime	44	50	Yes
	Evening	44	50	Yes
	Nighttime	41	45	Yes
SOPOR1	Daytime	42	50	Yes
	Evening	42	50	Yes
SOPOR2	Daytime	34	50	Yes
	Evening	34	50	Yes
SOPOR3	Daytime	36	50	Yes
	Evening	36	50	Yes

Noise due to stationary noise sources is predicted to meet the applicable sound level limits at all modeled receptors in the surrounding area.

6.5 Stationary Noise Mitigation Recommendations

6.5.1 Mitigation for Project Receptors

No predicted exceedances of the applicable stationary sound level limits at the Project receptors have been identified; therefore, no specific mitigation is recommended at this time. Constructing the Project to meet OBC and the identified requirements for mitigation of transportation noise is expected to be sufficient to address potential impacts from minor stationary noise sources in the vicinity of the Project.

6.5.2 Mitigation for Surrounding Receptors

No predicted exceedances of the applicable stationary sound level limits at the surrounding receptors have been identified; therefore, no specific mitigation is recommended at this time.

7.0 Concluding Comments

Noise impacts associated with the proposed development at 1225 Dundas Street East, Mississauga are expected to be able to meet all applicable MECP noise limits with the inclusion of noise control measures and warning clauses as presented in Section 5.5 of this report for transportation noise sources and Section 6.5 of this report for stationary noise sources. The proposed development should therefore be approved.

As the design of the redevelopment proceeds, and mechanical equipment is selected, acoustical modelling of the impacts of this equipment should be confirmed in order to evaluate compliance with applicable MECP limits at surrounding sensitive receptors, and confirm that impacts to the Project itself will be acceptable.

Please do not hesitate to contact us if there are any questions.

Yours Truly,

Thornton Tomasetti

A handwritten signature in black ink, reading "Robert Fuller", is positioned above a horizontal line.

Robert Fuller, P.Eng.
Project Engineer

Reviewed by:

Stephen McCann, P.Eng.
Associate

Disclaimer

Achieving the required noise control requirements relies on correct incorporation of noise control recommendations into Architectural and Mechanical drawings and specifications, as well as correct installation during construction. On Request, TT will conduct drawing reviews and onsite reviews of noise control measures and provide observations as appropriate; however, notwithstanding the foregoing, it is expressly understood and agreed that TT shall not have control or charge of, and shall not be responsible for the acts or omissions, including but not limited to means, methods, techniques, sequences and procedures, of the Design Professionals and/or Contractors performing design and/or construction on the Project. Accordingly, TT shall not be held responsible for the failure of any party to properly incorporate the noise control measures stated in this report.

Appendix A: Figures

Figure 1: Project Location & Surroundings


Figure 2: Zoning Map

Figure 3: Project Site Plan

Figure 4: Transportation Noise PORs & Sources

Figure 5: Stationary Noise PORs & Sources

Figure 6: Recommended Mitigation Measures



Thornton Tomasetti
366 Revus Avenue, Unit 23
Mississauga, ON Canada L5G 4S5
Tel: 905.271.7888 Fax: 905.271.1846
www.thorntontomasetti.com

True North

TT PROJECT CODE

SW22159

DRAWN BY: RF

REVIEWED BY:

REVISION		
#	DATE	DESCRIPTION
0	2021/12/02	FOR INFORMATION ONLY, NOT FOR CONSTRUCTION
1	2021/MM/DD	FOR INFORMATION ONLY, NOT FOR CONSTRUCTION

PROJECT NAME

1225 DUNDAS STREET EAST
MISSISSAUGA

DRAWING NAME

FIGURE 1:
SITE LOCATION
& SURROUNDINGS

SCALE	DATE
ON DRAWING	2022/06/20
Project SK. No	SHEET
	1 OF 1



Legend

- Road Names**

Zoning Labels

Zoning Shapes

 - A Agricultural (By-law 5500)
 - AP Lester B. Pearson International
 - B Buffer, Berm, Fence
 - C1 Convenience Commercial
 - C2 Neighbourhood Commercial
 - C3 General Commercial
 - C4 Mainstreet Commercial
 - C5 Motor Vehicle Commercial
 - CC1 Core Commercial
 - CC2, CC4 Mixed Use
 - CC3 Mixed Use - Transition Area
 - CCO Office
 - CCOS Open Space
 - D Existing Use
 - E1 Employment in Nodes
 - E2 Employment
 - E3 Industrial
 - G1 Natural Hazards
 - G2 Natural Features
 - I Hospital and University / College
 - O Office
 - OS1 Community Park
 - OS2 City Park

Notes

© 2021 Queen's Printer for Ontario and its licensors. May not be reproduced without permission.
Aerial Imagery provided by Teranet Inc. and Nearmap US, Inc.
Aerial Imagery provided by First Base Solutions Inc.
Parcel Data © Teranet Inc.

1: 9,028



458.6	0	229.31	458.6	Meters
-------	---	--------	-------	--------

WGS_1984_Web_Mercator_Auxiliary_Sphere
© 2021 The City of Mississauga 6-20-2022

This map is a user generated static output from an Internet mapping site and is for reference only. Data layers that appear on this map may or may not be accurate, current, or otherwise reliable.


THIS IS NOT A PLAN OF SURVEY

This drawing, as an instrument of service, is provided by and is the property of Turner Fleischer Architects Inc. The contractor must verify and accept responsibility for all dimensions and conditions on site and must notify Turner Fleischer Architects Inc. of any variations from the supplied information. This drawing is not to be scaled. The architect is not responsible for the accuracy of survey, structural, mechanical, electrical, etc., information shown on this drawing. Refer to the appropriate drawings for details. The contractor must verify all dimensions and conditions on site, applicable codes and requirements of authorities having jurisdiction. The contractor working from drawings not specifically marked "For Construction" must assume full responsibility and bear costs for any corrections or damages resulting from his work.



	PRIMARY RESIDENTIAL ENTRANCE
	SECONDARY RESIDENTIAL ENTRANCE
	RETAIL ENTRANCE
	EXIT
	FIRE HYDRANT
	SIAMESE CONNECTION
	CONVEX MIRROR
	TRANSFORMER WITH CLEARANCES
	FIRE ROUTE SIGN
	SPOT ELEVATION
	GAS/HYDRO METER

1	Date 1	Draft Concept Plan	
N	DATE	DESCRIPTION	BY



PROJECT


**PROPOSED RESIDENTIAL MIX-USE
DEVELOPMENT**

1225 Dundas Street E, Mississauga, ON


DRAWING


SITE PLAN / ROOF PLAN

PROJECT NO. 22.117P01	
PROJECT DATE	
DRAWN BY Author	
CHECKED BY Checker	
SCALE As indicated	




DRAWING NO.	REV.
SPA006	1





Thornton Tomasetti

366 Rebus Avenue, Unit 23
Mississauga, ON Canada L5G 4S5
Tel: 905.271.7888 Fax: 905.271.1846
www.thorntontomasetti.com



TT PROJECT CODE

SW22159

DRAWN BY:

RF

REVIEWED BY:

REVISION

#	DATE	DESCRIPTION
0	2021/12/02	FOR INFORMATION ONLY, NOT FOR CONSTRUCTION
1	2021/MM/DD	FOR INFORMATION ONLY, NOT FOR CONSTRUCTION

PROJECT NAME

1225 DUNDAS
STREET EAST
MISSISSAUGA

DRAWING NAME


FIGURE 4:
TRANSPORTATION NOISE
PORs & SOURCES

SCALE
ON DRAWING

DATE
2022/06/20

Project SK. No

SHEET
1 OF 1



TT PROJECT CODE

SW22159

DRAWN BY:

RF

REVIEWED BY:

REVISION

#	DATE	DESCRIPTION
0	2021/12/02	FOR INFORMATION ONLY, NOT FOR CONSTRUCTION
1	2021/MM/DD	FOR INFORMATION ONLY, NOT FOR CONSTRUCTION

PROJECT NAME

1225 DUNDAS
STREET EAST
MISSISSAUGA

DRAWING NAME


FIGURE 5:
STATIONARY NOISE
PORs & SOURCES

SCALE ON DRAWING

DATE 2022/06/20

Project SK. No

SHEET 1 OF 1



Thornton Tomasetti
366 Revus Avenue, Unit 23
Mississauga, ON Canada L5G 4S5
Tel: 905.271.7888 Fax: 905.271.1846
www.thorntontomasetti.com

True North

TT PROJECT CODE

SW22159

DRAWN BY: RF

REVIEWED BY:

REVISION		DESCRIPTION
#	DATE	
0	2021/12/02	FOR INFORMATION ONLY, NOT FOR CONSTRUCTION
1	2021/MM/DD	FOR INFORMATION ONLY, NOT FOR CONSTRUCTION

PROJECT NAME

1225 DUNDAS STREET EAST
MISSISSAUGA

DRAWING NAME

FIGURE 6:
RECOMMENDED
MITIGATION MEASURES

SCALE ON DRAWING	DATE 2022/06/20
Project SK. No	SHEET 1 OF 1

Appendix B: Traffic Data

Peak Hour Diagram

Specified Period

From: 07:00:00

To: 09:00:00

One Hour Peak

From: 08:00:00

To: 09:00:00

Intersection: Dundas St E & Arena Rd - Commercial Access

Site Code: 2219300003

Count Date: Jun 07, 2022

Weather conditions: Clear

**** Signalized Intersection ****

Major Road: Dundas St E runs E/W

North Approach

	Out	In	Total
	51	26	77
	0	0	0
	1	2	3
	0	0	0
Totals	52	28	80

Arena Rd

	0	0	0	0
	0	0	1	0
	0	0	0	0
	36	3	12	0
Totals	36	3	13	0






East Approach

	Out	In	Total
	725	1178	1903
	39	43	82
	13	10	23
	0	0	0
Totals	777	1231	2008

Dundas St E

					Totals
	0	0	0	0	0
	0	2	0	17	19
	0	9	39	1116	1164
	0	0	0	17	17

Peds: 9

Peds: 4



Peds: 6

Peds: 9

Dundas St E

Totals				
	0	0	0	0
	8	8	0	0
	725	675	37	13
	44	42	2	0

West Approach

	Out	In	Total
	1150	718	1868
	39	37	76
	11	13	24
	0	0	0
Totals	1200	768	1968

				
Totals	7	1	54	0
	7	1	50	0
	0	0	4	0
	0	0	0	0
	0	0	0	0

Commercial Access

South Approach

	Out	In	Total
	58	62	120
	4	2	6
	0	0	0
	0	0	0
Totals	62	64	126

 - Cars

 - Trucks

 - Buses

 - Bicycles

Comments

Peak Hour Diagram

Specified Period

From: 16:00:00

To: 18:00:00

One Hour Peak

From: 16:30:00

To: 17:30:00

Intersection: Dundas St E & Arena Rd - Commercial Access

Site Code: 2219300003

Count Date: Jun 07, 2022

Weather conditions: Clear

**** Signalized Intersection ****

Major Road: Dundas St E runs E/W

North Approach

	Out	In	Total
	43	67	110
	0	1	1
	0	0	0
	0	0	0
Totals	43	68	111

Arena Rd

	0	0	0	0
	0	0	0	0
	0	0	0	0
	26	2	15	0
Totals	26	2	15	0

East Approach

	Out	In	Total
	1593	1245	2838
	27	24	51
	13	12	25
	0	0	0
Totals	1633	1281	2914

Dundas St E

					Totals
	0	0	0	0	0
	0	0	1	36	37
	0	12	24	1120	1156
	0	0	1	18	19

Peds: 11



Peds: 15

Peds: 11

Peds: 24

Dundas St E

Totals				
	0	0	0	0
	20	20	0	0
	1525	1486	26	13
	88	87	1	0

West Approach

	Out	In	Total
	1174	1532	2706
	26	27	53
	12	13	25
	0	0	0
Totals	1212	1572	2784

	21	11	110	0
	20	11	110	0
	1	0	0	0
	0	0	0	0
	0	0	0	0

Commercial Access

South Approach

	Out	In	Total
	141	107	248
	1	2	3
	0	0	0
	0	0	0
Totals	142	109	251

- Cars

- Trucks

- Buses

- Bicycles

Comments

Appendix C: Transportation Noise Predictions

STAMSON 5.0 NORMAL REPORT Date: 27-06-2022 16:07:08
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: olal.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: DSEE (day/night)

```
-----
Car traffic volume   : 13753/1528   veh/TimePeriod  *
Medium truck volume :    430/48    veh/TimePeriod  *
Heavy truck volume  :    143/16    veh/TimePeriod  *
Posted speed limit   :     60 km/h
Road gradient        :      0 %
Road pavement       :      1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth         : 2.00
Number of Years of Growth           : 13.00
Medium Truck % of Total Volume      : 3.00
Heavy Truck % of Total Volume       : 1.00
Day (16 hrs) % of Total Volume      : 90.00
```

Data for Segment # 1: DSEE (day/night)

```
-----
Angle1   Angle2      : -90.00 deg   90.00 deg
Wood depth      :      0      (No woods.)
No of house rows :      0 / 0
Surface         :      2      (Reflective ground surface)
Receiver source distance : 45.00 / 45.00 m
Receiver height  : 32.70 / 32.70 m
Topography      :      2      (Flat/gentle slope; with barrier)
Barrier angle1   : -90.00 deg   Angle2 : 90.00 deg
Barrier height   : 31.20 m
Barrier receiver distance : 9.00 / 9.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle  : 0.00
```

Road data, segment # 2: DSEW (day/night)

```
-----
Car traffic volume   : 13753/1528   veh/TimePeriod  *
Medium truck volume :    430/48    veh/TimePeriod  *
Heavy truck volume  :    143/16    veh/TimePeriod  *
Posted speed limit   :     60 km/h
Road gradient        :      0 %
Road pavement       :      1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT):	12305
Percentage of Annual Growth	: 2.00
Number of Years of Growth	: 13.00
Medium Truck % of Total Volume	: 3.00
Heavy Truck % of Total Volume	: 1.00
Day (16 hrs) % of Total Volume	: 90.00

Data for Segment # 2: DSEW (day/night)

Angle1	Angle2	: -90.00 deg	90.00 deg
Wood depth	:	0	(No woods.)
No of house rows	:	0 / 0	
Surface	:	2	(Reflective ground surface)
Receiver source distance	:	30.00 / 30.00 m	
Receiver height	:	32.70 / 32.70 m	
Topography	:	2	(Flat/gentle slope; with barrier)
Barrier angle1	:	-90.00 deg	Angle2 : 90.00 deg
Barrier height	:	31.20 m	
Barrier receiver distance	:	9.00 / 9.00 m	
Source elevation	:	0.00 m	
Receiver elevation	:	0.00 m	
Barrier elevation	:	0.00 m	
Reference angle	:	0.00	

Road data, segment # 3: AR (day/night)

Car traffic volume	:	839/359	veh/TimePeriod *
Medium truck volume	:	17/7	veh/TimePeriod *
Heavy truck volume	:	9/4	veh/TimePeriod *
Posted speed limit	:	40 km/h	
Road gradient	:	0 %	
Road pavement	:	1	(Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT):	955
Percentage of Annual Growth	: 2.00
Number of Years of Growth	: 13.00
Medium Truck % of Total Volume	: 2.00
Heavy Truck % of Total Volume	: 1.00
Day (16 hrs) % of Total Volume	: 70.00

Data for Segment # 3: AR (day/night)

Angle1	Angle2	: -29.00 deg	51.00 deg
Wood depth	:	0	(No woods.)
No of house rows	:	0 / 0	
Surface	:	2	(Reflective ground surface)
Receiver source distance	:	73.00 / 73.00 m	
Receiver height	:	32.70 / 32.70 m	
Topography	:	2	(Flat/gentle slope; with barrier)
Barrier angle1	:	-18.00 deg	Angle2 : 51.00 deg

Barrier height : 41.50 m
 Barrier receiver distance : 33.00 / 33.00 m
 Source elevation : 0.00 m
 Receiver elevation : 0.00 m
 Barrier elevation : 0.00 m
 Reference angle : 0.00

Results segment # 1: DSEE (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	32.70	26.36	26.36

ROAD (0.00 + 47.95 + 0.00) = 47.95 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	90	0.00	66.53	0.00	-4.77	0.00	0.00	0.00	-13.82

SubLeq
 47.95

Segment Leq : 47.95 dBA

Results segment # 2: DSEW (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	32.70	23.19	23.19

ROAD (0.00 + 47.36 + 0.00) = 47.36 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	90	0.00	66.53	0.00	-3.01	0.00	0.00	0.00	-16.16

SubLeq
 47.36

Segment Leq : 47.36 dBA

Results segment # 3: AR (day)

Source height = 1.01 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.01	32.70	18.37	18.37

ROAD (31.05 + 19.03 + 0.00) = 31.32 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-29	-18	0.00	50.07	0.00	-6.87	-12.14	0.00	0.00	0.00

SubLeq
31.05
19.03

Segment Leq : 31.32 dBA

Total Leq All Segments: 50.73 dBA

Results segment # 1: DSEE (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	32.70	26.36	26.36

ROAD (0.00 + 41.43 + 0.00) = 41.43 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	90	0.00	60.01	0.00	-4.77	0.00	0.00	0.00	-13.81

SubLeq
41.43

Segment Leq : 41.43 dBA

Results segment # 2: DSEW (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	32.70	23.19	23.19

ROAD (0.00 + 40.84 + 0.00) = 40.84 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	90	0.00	60.01	0.00	-3.01	0.00	0.00	0.00	-16.16

SubLeq

Segment Leq : 40.84 dBA

Results segment # 3: AR (night)

Source height = 1.02 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.02	32.70	18.38	18.38

ROAD (30.42 + 18.40 + 0.00) = 30.69 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-29	-18	0.00	49.43	0.00	-6.87	-12.14	0.00	0.00	0.00

SubLeq

18.40

Segment Leq : 30.69 dBA

Total Leq All Segments: 44.35 dBA

TOTAL Leq FROM ALL SOURCES (DAY) : 50.73
(NIGHT) : 44.35

STAMSON 5.0 NORMAL REPORT Date: 27-06-2022 16:08:53
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: Ola2.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: DSEE1 (day/night)

```
-----
Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth : 2.00
Number of Years of Growth : 13.00
Medium Truck % of Total Volume : 3.00
Heavy Truck % of Total Volume : 1.00
Day (16 hrs) % of Total Volume : 90.00
```

Data for Segment # 1: DSEE1 (day/night)

```
-----
Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 104.00 / 104.00 m
Receiver height : 1.50 / 1.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : -24.00 deg
Barrier height : 17.80 m
Barrier receiver distance : 60.00 / 60.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00
```

Road data, segment # 2: DSEE2 (day/night)

```
-----
Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 12305
```

```

Percentage of Annual Growth      :    2.00
Number of Years of Growth       :   13.00
Medium Truck % of Total Volume  :    3.00
Heavy Truck % of Total Volume   :    1.00
Day (16 hrs) % of Total Volume  :   90.00

```

Data for Segment # 2: DSEE2 (day/night)

```

-----
Angle1   Angle2      :   0.00 deg   90.00 deg
Wood depth      :           0      (No woods.)
No of house rows :           0 / 0
Surface         :           2      (Reflective ground surface)
Receiver source distance : 104.00 / 104.00 m
Receiver height  :    1.50 / 1.50 m
Topography      :           2      (Flat/gentle slope; with barrier)
Barrier angle1   :    8.00 deg   Angle2 : 90.00 deg
Barrier height   :   22.05 m
Barrier receiver distance : 72.00 / 72.00 m
Source elevation :    0.00 m
Receiver elevation :    0.00 m
Barrier elevation :    0.00 m
Reference angle  :    0.00

```

Road data, segment # 3: DSEW1 (day/night)

```

-----
Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient      : 0 %
Road pavement      : 1 (Typical asphalt or concrete)

```

* Refers to calculated road volumes based on the following input:

```

24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth      :    2.00
Number of Years of Growth       :   13.00
Medium Truck % of Total Volume  :    3.00
Heavy Truck % of Total Volume   :    1.00
Day (16 hrs) % of Total Volume  :   90.00

```

Data for Segment # 3: DSEW1 (day/night)

```

-----
Angle1   Angle2      :  -90.00 deg   0.00 deg
Wood depth      :           0      (No woods.)
No of house rows :           0 / 0
Surface         :           2      (Reflective ground surface)
Receiver source distance : 89.00 / 89.00 m
Receiver height  :    1.50 / 1.50 m
Topography      :           2      (Flat/gentle slope; with barrier)
Barrier angle1   :  -90.00 deg   Angle2 : -24.00 deg
Barrier height   :   17.80 m
Barrier receiver distance : 60.00 / 60.00 m
Source elevation :    0.00 m

```

Receiver elevation : 0.00 m
 Barrier elevation : 0.00 m
 Reference angle : 0.00

Road data, segment # 4: DSEW2 (day/night)

 Car traffic volume : 13753/1528 veh/TimePeriod *
 Medium truck volume : 430/48 veh/TimePeriod *
 Heavy truck volume : 143/16 veh/TimePeriod *
 Posted speed limit : 60 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12305
 Percentage of Annual Growth : 2.00
 Number of Years of Growth : 13.00
 Medium Truck % of Total Volume : 3.00
 Heavy Truck % of Total Volume : 1.00
 Day (16 hrs) % of Total Volume : 90.00

Data for Segment # 4: DSEW2 (day/night)

 Angle1 Angle2 : 0.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 89.00 / 89.00 m
 Receiver height : 1.50 / 1.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 8.00 deg Angle2 : 90.00 deg
 Barrier height : 22.05 m
 Barrier receiver distance : 72.00 / 72.00 m
 Source elevation : 0.00 m
 Receiver elevation : 0.00 m
 Barrier elevation : 0.00 m
 Reference angle : 0.00

Road data, segment # 5: AR1 (day/night)

 Car traffic volume : 839/359 veh/TimePeriod *
 Medium truck volume : 17/7 veh/TimePeriod *
 Heavy truck volume : 9/4 veh/TimePeriod *
 Posted speed limit : 40 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 955
 Percentage of Annual Growth : 2.00
 Number of Years of Growth : 13.00
 Medium Truck % of Total Volume : 2.00

Heavy Truck % of Total Volume : 1.00
 Day (16 hrs) % of Total Volume : 70.00

Data for Segment # 5: AR1 (day/night)

 Angle1 Angle2 : -36.00 deg 0.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 136.00 / 136.00 m
 Receiver height : 1.50 / 1.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -36.00 deg Angle2 : -9.00 deg
 Barrier height : 22.05 m
 Barrier receiver distance : 122.00 / 122.00 m
 Source elevation : 0.00 m
 Receiver elevation : 0.00 m
 Barrier elevation : 0.00 m
 Reference angle : 0.00

Road data, segment # 6: AR2 (day/night)

 Car traffic volume : 839/359 veh/TimePeriod *
 Medium truck volume : 17/7 veh/TimePeriod *
 Heavy truck volume : 9/4 veh/TimePeriod *
 Posted speed limit : 40 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT) : 955
 Percentage of Annual Growth : 2.00
 Number of Years of Growth : 13.00
 Medium Truck % of Total Volume : 2.00
 Heavy Truck % of Total Volume : 1.00
 Day (16 hrs) % of Total Volume : 70.00

Data for Segment # 6: AR2 (day/night)

 Angle1 Angle2 : 0.00 deg 11.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 136.00 / 136.00 m
 Receiver height : 1.50 / 1.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 0.00 deg Angle2 : 11.00 deg
 Barrier height : 11.15 m
 Barrier receiver distance : 122.00 / 122.00 m
 Source elevation : 0.00 m
 Receiver elevation : 0.00 m
 Barrier elevation : 0.00 m
 Reference angle : 0.00

Results segment # 1: DSEE1 (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	1.50	1.21	1.21

ROAD (0.00 + 36.36 + 49.37) = 49.59 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	-24	0.00	66.53	0.00	-8.41	-4.36	0.00	0.00	-17.40

SubLeq
36.36

-24	0	0.00	66.53	0.00	-8.41	-8.75	0.00	0.00	0.00
-----	---	------	-------	------	-------	-------	------	------	------

49.37

Segment Leq : 49.59 dBA

Results segment # 2: DSEE2 (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	1.50	1.15	1.15

ROAD (44.60 + 36.10 + 0.00) = 45.18 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
0	8	0.00	66.53	0.00	-8.41	-13.52	0.00	0.00	0.00

44.60

8	90	0.00	66.53	0.00	-8.41	-3.41	0.00	0.00	-18.61
---	----	------	-------	------	-------	-------	------	------	--------

36.10

Segment Leq : 45.18 dBA

Results segment # 3: DSEW1 (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	1.50	1.16	1.16

ROAD (0.00 + 36.60 + 50.05) = 50.24 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	-24	0.00	66.53	0.00	-7.73	-4.36	0.00	0.00	-17.84

SubLeq
36.60

-24	0	0.00	66.53	0.00	-7.73	-8.75	0.00	0.00	0.00
-----	---	------	-------	------	-------	-------	------	------	------

50.05

Segment Leq : 50.24 dBA

Results segment # 4: DSEW2 (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	1.50	1.10	1.10

ROAD (45.28 + 36.42 + 0.00) = 45.81 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
0	8	0.00	66.53	0.00	-7.73	-13.52	0.00	0.00	0.00

SubLeq
45.28

8	90	0.00	66.53	0.00	-7.73	-3.41	0.00	0.00	-18.97
---	----	------	-------	------	-------	-------	------	------	--------

36.42

--

Segment Leq : 45.81 dBA

Results segment # 5: AR1 (day)

Source height = 1.01 m

Barrier height for grazing incidence

Source Height	! Receiver (m) !	Barrier Height	! Receiver (m) !	Barrier Height	! Receiver (m) !	Elevation of Barrier Top
1.01	!	1.50	!	1.06	!	1.06

ROAD (0.00 + 12.25 + 27.48) = 27.61 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-36	-9	0.00	50.07	0.00	-9.57	-8.24	0.00	0.00	-20.00
12.25									

-9	0	0.00	50.07	0.00	-9.57	-13.01	0.00	0.00	0.00
27.48									

--

Segment Leq : 27.61 dBA

Results segment # 6: AR2 (day)

Source height = 1.01 m

Barrier height for grazing incidence

Source Height	! Receiver (m) !	Barrier Height	! Receiver (m) !	Barrier Height	! Receiver (m) !	Elevation of Barrier Top
1.01	!	1.50	!	1.06	!	1.06

ROAD (0.00 + 8.35 + 0.00) = 8.35 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

0	11	0.00	50.07	0.00	-9.57	-12.14	0.00	0.00	-20.00
8.35									

--

Segment Leq : 8.35 dBA

Total Leq All Segments: 54.29 dBA

Results segment # 1: DSEE1 (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.00	!	1.50	!
		1.21	!
			1.21

ROAD (0.00 + 29.84 + 42.85) = 43.07 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

--	--	--	--	--	--	--	--	--	--
-90	-24	0.00	60.01	0.00	-8.41	-4.36	0.00	0.00	-17.40
29.84									

--	--	--	--	--	--	--	--	--	--
-24	0	0.00	60.01	0.00	-8.41	-8.75	0.00	0.00	0.00
42.85									

Segment Leq : 43.07 dBA

Results segment # 2: DSEE2 (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.00	!	1.50	!
		1.15	!
			1.15

ROAD (38.08 + 29.58 + 0.00) = 38.66 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

--	--	--	--	--	--	--	--	--	--
0	8	0.00	60.01	0.00	-8.41	-13.52	0.00	0.00	0.00
38.08									

8 90 0.00 60.01 0.00 -8.41 -3.41 0.00 0.00 -18.61
29.58

Segment Leq : 38.66 dBA

Results segment # 3: DSEW1 (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	1.50	1.16	1.16

ROAD (0.00 + 30.08 + 43.53) = 43.72 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	-24	0.00	60.01	0.00	-7.73	-4.36	0.00	0.00	-17.84

30.08

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-24	0	0.00	60.01	0.00	-7.73	-8.75	0.00	0.00	0.00

Segment Leq : 43.72 dBA

Results segment # 4: DSEW2 (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	1.50	1.10	1.10

ROAD (38.76 + 29.90 + 0.00) = 39.29 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
0	8	0.00	60.01	0.00	-7.73	-13.52	0.00	0.00	0.00

38.76

```

-----
--
      8      90      0.00  60.01      0.00  -7.73  -3.41      0.00      0.00 -18.97
29.90
-----
--

```

Segment Leq : 39.29 dBA

Results segment # 5: AR1 (night)

Source height = 1.02 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
      1.02 !      1.50 !      1.07 !      1.07

```

ROAD (0.00 + 11.62 + 26.85) = 26.98 dBA

```

Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj
SubLeq

```

```

-----
--
    -36     -9     0.00  49.43      0.00  -9.57  -8.24      0.00      0.00 -20.00
11.62
-----
--
     -9      0     0.00  49.43      0.00  -9.57 -13.01      0.00      0.00   0.00
26.85
-----
--

```

Segment Leq : 26.98 dBA

Results segment # 6: AR2 (night)

Source height = 1.02 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
      1.02 !      1.50 !      1.07 !      1.07

```

ROAD (0.00 + 7.72 + 0.00) = 7.72 dBA

```

Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj
SubLeq

```

--

0	11	0.00	49.43	0.00	-9.57	-12.14	0.00	0.00	-20.00
7.72									

--

Segment Leq : 7.72 dBA

Total Leq All Segments: 47.79 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 54.29
(NIGHT): 47.79

STAMSON 5.0 NORMAL REPORT Date: 27-06-2022 16:09:49
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: ola3.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: DSEE (day/night)

Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth : 2.00
Number of Years of Growth : 13.00
Medium Truck % of Total Volume : 3.00
Heavy Truck % of Total Volume : 1.00
Day (16 hrs) % of Total Volume : 90.00

Data for Segment # 1: DSEE (day/night)

Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 104.00 / 104.00 m
Receiver height : 1.50 / 1.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 0.00 deg
Barrier height : 22.05 m
Barrier receiver distance : 72.00 / 72.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00

Road data, segment # 2: DSEW (day/night)

Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12305

```

Percentage of Annual Growth      :    2.00
Number of Years of Growth       :   13.00
Medium Truck % of Total Volume  :    3.00
Heavy Truck % of Total Volume   :    1.00
Day (16 hrs) % of Total Volume  :   90.00

```

Data for Segment # 2: DSEW (day/night)

```

-----
Angle1   Angle2      : -90.00 deg   90.00 deg
Wood depth      :      0      (No woods.)
No of house rows :      0 / 0
Surface         :      2      (Reflective ground surface)
Receiver source distance : 89.00 / 89.00 m
Receiver height  :    1.50 / 1.50 m
Topography      :      2      (Flat/gentle slope; with barrier)
Barrier angle1   : -90.00 deg   Angle2 : 0.00 deg
Barrier height   :   22.05 m
Barrier receiver distance : 72.00 / 72.00 m
Source elevation :    0.00 m
Receiver elevation :    0.00 m
Barrier elevation :    0.00 m
Reference angle  :    0.00

```

Road data, segment # 3: AR (day/night)

```

-----
Car traffic volume :   839/359   veh/TimePeriod *
Medium truck volume :    17/7    veh/TimePeriod *
Heavy truck volume :     9/4     veh/TimePeriod *
Posted speed limit :    40 km/h
Road gradient      :     0 %
Road pavement      :     1 (Typical asphalt or concrete)

```

* Refers to calculated road volumes based on the following input:

```

24 hr Traffic Volume (AADT or SADT) :    955
Percentage of Annual Growth          :    2.00
Number of Years of Growth           :   13.00
Medium Truck % of Total Volume       :    2.00
Heavy Truck % of Total Volume        :    1.00
Day (16 hrs) % of Total Volume       :   70.00

```

Data for Segment # 3: AR (day/night)

```

-----
Angle1   Angle2      : -79.00 deg   57.00 deg
Wood depth      :      0      (No woods.)
No of house rows :      0 / 0
Surface         :      2      (Reflective ground surface)
Receiver source distance : 19.00 / 19.00 m
Receiver height  :    1.50 / 1.50 m
Topography      :      2      (Flat/gentle slope; with barrier)
Barrier angle1   :   33.00 deg   Angle2 : 57.00 deg
Barrier height   :   11.15 m
Barrier receiver distance : 5.00 / 5.00 m
Source elevation :    0.00 m

```

Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00

Results segment # 1: DSEE (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	1.50	1.15	1.15

ROAD (0.00 + 36.40 + 55.11) = 55.17 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	0	0.00	66.53	0.00	-8.41	-3.01	0.00	0.00	-18.72

SubLeq
36.40

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
0	90	0.00	66.53	0.00	-8.41	-3.01	0.00	0.00	0.00

SubLeq
55.11

Segment Leq : 55.17 dBA

Results segment # 2: DSEW (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	1.50	1.10	1.10

ROAD (0.00 + 36.74 + 55.79) = 55.84 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	0	0.00	66.53	0.00	-7.73	-3.01	0.00	0.00	-19.05

SubLeq
36.74

SubLeq

0 90 0.00 66.53 0.00 -7.73 -3.01 0.00 0.00 0.00
55.79

Segment Leq : 55.84 dBA

Results segment # 3: AR (day)

Source height = 1.01 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.01	1.50	1.37	1.37

ROAD (46.98 + 20.29 + 0.00) = 46.99 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-79	33	0.00	50.07	0.00	-1.03	-2.06	0.00	0.00	0.00

46.98

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
33	57	0.00	50.07	0.00	-1.03	-8.75	0.00	0.00	-20.00

Segment Leq : 46.99 dBA

Total Leq All Segments: 58.82 dBA

Results segment # 1: DSEE (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	1.50	1.15	1.15

ROAD (0.00 + 29.88 + 48.59) = 48.65 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj

```

-90      0      0.00  60.01      0.00  -8.41  -3.01      0.00      0.00 -18.72
29.88

```

```

--
      0      90      0.00  60.01      0.00  -8.41  -3.01      0.00      0.00      0.00
48.59

```

Segment Leq : 48.65 dBA

Results segment # 2: DSEW (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	1.50	1.10	1.10

ROAD (0.00 + 30.22 + 49.27) = 49.32 dBA

```

Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj
SubLeq

```

```

--
-90      0      0.00  60.01      0.00  -7.73  -3.01      0.00      0.00 -19.05
30.22

```

```

--
      0      90      0.00  60.01      0.00  -7.73  -3.01      0.00      0.00      0.00
49.27

```

Segment Leq : 49.32 dBA

Results segment # 3: AR (night)

Source height = 1.02 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.02	1.50	1.37	1.37

ROAD (46.35 + 19.66 + 0.00) = 46.36 dBA

```

Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj
SubLeq

```

--									
	-79	33	0.00	49.43	0.00	-1.03	-2.06	0.00	0.00
46.35									

--									
	33	57	0.00	49.43	0.00	-1.03	-8.75	0.00	0.00
19.66									

--									

Segment Leq : 46.36 dBA

Total Leq All Segments: 53.05 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 58.82
(NIGHT): 53.05

STAMSON 5.0 NORMAL REPORT Date: 27-06-2022 16:11:42
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: ola3b1.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: DSEE1 (day/night)

```
-----
Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth : 2.00
Number of Years of Growth : 13.00
Medium Truck % of Total Volume : 3.00
Heavy Truck % of Total Volume : 1.00
Day (16 hrs) % of Total Volume : 90.00
```

Data for Segment # 1: DSEE1 (day/night)

```
-----
Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 104.00 / 104.00 m
Receiver height : 1.50 / 1.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 0.00 deg
Barrier height : 22.05 m
Barrier receiver distance : 72.00 / 72.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00
```

Road data, segment # 2: DSEW1 (day/night)

```
-----
Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 12305
```

```

Percentage of Annual Growth      :    2.00
Number of Years of Growth       :   13.00
Medium Truck % of Total Volume  :    3.00
Heavy Truck % of Total Volume   :    1.00
Day (16 hrs) % of Total Volume  :   90.00

```

Data for Segment # 2: DSEW1 (day/night)

```

-----
Angle1   Angle2      : -90.00 deg   0.00 deg
Wood depth      :      0      (No woods.)
No of house rows :      0 / 0
Surface         :      2      (Reflective ground surface)
Receiver source distance : 89.00 / 89.00 m
Receiver height  :    1.50 / 1.50 m
Topography      :      2      (Flat/gentle slope; with barrier)
Barrier angle1   : -90.00 deg   Angle2 : 0.00 deg
Barrier height   :   22.05 m
Barrier receiver distance : 72.00 / 72.00 m
Source elevation :    0.00 m
Receiver elevation :    0.00 m
Barrier elevation :    0.00 m
Reference angle  :    0.00

```

Road data, segment # 3: AR (day/night)

```

-----
Car traffic volume :   839/359   veh/TimePeriod *
Medium truck volume :    17/7    veh/TimePeriod *
Heavy truck volume :     9/4     veh/TimePeriod *
Posted speed limit :    40 km/h
Road gradient      :     0 %
Road pavement      :     1 (Typical asphalt or concrete)

```

* Refers to calculated road volumes based on the following input:

```

24 hr Traffic Volume (AADT or SADT) :    955
Percentage of Annual Growth          :    2.00
Number of Years of Growth            :   13.00
Medium Truck % of Total Volume       :    2.00
Heavy Truck % of Total Volume        :    1.00
Day (16 hrs) % of Total Volume       :   70.00

```

Data for Segment # 3: AR (day/night)

```

-----
Angle1   Angle2      : -79.00 deg   57.00 deg
Wood depth      :      0      (No woods.)
No of house rows :      0 / 0
Surface         :      2      (Reflective ground surface)
Receiver source distance : 19.00 / 19.00 m
Receiver height  :    1.50 / 1.50 m
Topography      :      2      (Flat/gentle slope; with barrier)
Barrier angle1   :   33.00 deg   Angle2 : 57.00 deg
Barrier height   :   11.15 m
Barrier receiver distance : 5.00 / 5.00 m
Source elevation :    0.00 m

```

Receiver elevation : 0.00 m
 Barrier elevation : 0.00 m
 Reference angle : 0.00

Road data, segment # 4: DSEE2 (day/night)

 Car traffic volume : 13753/1528 veh/TimePeriod *
 Medium truck volume : 430/48 veh/TimePeriod *
 Heavy truck volume : 143/16 veh/TimePeriod *
 Posted speed limit : 60 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12305
 Percentage of Annual Growth : 2.00
 Number of Years of Growth : 13.00
 Medium Truck % of Total Volume : 3.00
 Heavy Truck % of Total Volume : 1.00
 Day (16 hrs) % of Total Volume : 90.00

Data for Segment # 4: DSEE2 (day/night)

 Angle1 Angle2 : 0.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 104.00 / 104.00 m
 Receiver height : 1.50 / 4.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 0.00 deg Angle2 : 90.00 deg
 Barrier height : 1.50 m
 Barrier receiver distance : 6.00 / 6.00 m
 Source elevation : 0.00 m
 Receiver elevation : 0.00 m
 Barrier elevation : 0.00 m
 Reference angle : 0.00

Road data, segment # 5: DSEW2 (day/night)

 Car traffic volume : 13753/1528 veh/TimePeriod *
 Medium truck volume : 430/48 veh/TimePeriod *
 Heavy truck volume : 143/16 veh/TimePeriod *
 Posted speed limit : 60 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12305
 Percentage of Annual Growth : 2.00
 Number of Years of Growth : 13.00
 Medium Truck % of Total Volume : 3.00

Heavy Truck % of Total Volume : 1.00
Day (16 hrs) % of Total Volume : 90.00

Data for Segment # 5: DSEW2 (day/night)

Angle1 Angle2 : 0.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 89.00 / 89.00 m
Receiver height : 1.50 / 4.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 0.00 deg Angle2 : 90.00 deg
Barrier height : 1.50 m
Barrier receiver distance : 6.00 / 6.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00

Results segment # 1: DSEE1 (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source ! Receiver ! Barrier ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
1.00 ! 1.50 ! 1.15 ! 1.15

ROAD (0.00 + 36.40 + 0.00) = 36.40 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

--
-90 0 0.00 66.53 0.00 -8.41 -3.01 0.00 0.00 -18.72
36.40

--

Segment Leq : 36.40 dBA

Results segment # 2: DSEW1 (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source ! Receiver ! Barrier ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----

1.00 ! 1.50 ! 1.10 ! 1.10

ROAD (0.00 + 36.74 + 0.00) = 36.74 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-90	0	0.00	66.53	0.00	-7.73	-3.01	0.00	0.00	-19.05
36.74									

Segment Leq : 36.74 dBA

Results segment # 3: AR (day)

Source height = 1.01 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.01 !	1.50 !	1.37 !	1.37

ROAD (46.98 + 20.29 + 0.00) = 46.99 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-79	33	0.00	50.07	0.00	-1.03	-2.06	0.00	0.00	0.00
46.98									

33	57	0.00	50.07	0.00	-1.03	-8.75	0.00	0.00	-20.00
20.29									

Segment Leq : 46.99 dBA

Results segment # 4: DSEE2 (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00 !	1.50 !	1.47 !	1.47

ROAD (0.00 + 50.11 + 0.00) = 50.11 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

0	90	0.00	66.53	0.00	-8.41	-3.01	0.00	0.00	-5.00
50.11									

Segment Leq : 50.11 dBA

Results segment # 5: DSEW2 (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	1.50	1.47	1.47

ROAD (0.00 + 50.79 + 0.00) = 50.79 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

0	90	0.00	66.53	0.00	-7.73	-3.01	0.00	0.00	-5.00
50.79									

Segment Leq : 50.79 dBA

Total Leq All Segments: 54.50 dBA

Results segment # 1: DSEE1 (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	1.50	1.15	1.15

ROAD (0.00 + 29.88 + 0.00) = 29.88 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

```

-----
--
-90      0      0.00  60.01   0.00  -8.41  -3.01   0.00   0.00 -18.72
29.88
-----
--

```

Segment Leq : 29.88 dBA

Results segment # 2: DSEW1 (night)

Source height = 1.00 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
          1.00 !          1.50 !          1.10 !          1.10

```

ROAD (0.00 + 30.22 + 0.00) = 30.22 dBA

```

Angle1 Angle2  Alpha RefLeq  P.Adj  D.Adj  F.Adj  W.Adj  H.Adj  B.Adj
SubLeq

```

```

-----
--
-90      0      0.00  60.01   0.00  -7.73  -3.01   0.00   0.00 -19.05
30.22
-----
--

```

Segment Leq : 30.22 dBA

Results segment # 3: AR (night)

Source height = 1.02 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
          1.02 !          1.50 !          1.37 !          1.37

```

ROAD (46.35 + 19.66 + 0.00) = 46.36 dBA

```

Angle1 Angle2  Alpha RefLeq  P.Adj  D.Adj  F.Adj  W.Adj  H.Adj  B.Adj
SubLeq

```

```

-----
--
-79      33      0.00  49.43   0.00  -1.03  -2.06   0.00   0.00   0.00
46.35
-----
--

```

33 57 0.00 49.43 0.00 -1.03 -8.75 0.00 0.00 -20.00
19.66

--

Segment Leq : 46.36 dBA

Results segment # 4: DSEE2 (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	4.50	4.30	4.30

ROAD (0.00 + 48.59 + 0.00) = 48.59 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

--

0	90	0.00	60.01	0.00	-8.41	-3.01	0.00	0.00	-0.13
48.47*									
0	90	0.00	60.01	0.00	-8.41	-3.01	0.00	0.00	0.00
48.59									

--

* Bright Zone !

Segment Leq : 48.59 dBA

Results segment # 5: DSEW2 (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	4.50	4.26	4.26

ROAD (0.00 + 49.27 + 0.00) = 49.27 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

--

0	90	0.00	60.01	0.00	-7.73	-3.01	0.00	0.00	-0.13
49.14*									

0	90	0.00	60.01	0.00	-7.73	-3.01	0.00	0.00	0.00
---	----	------	-------	------	-------	-------	------	------	------

49.27

--

* Bright Zone !

Segment Leq : 49.27 dBA

Total Leq All Segments: 53.06 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 54.50
(NIGHT): 53.06

STAMSON 5.0 NORMAL REPORT Date: 27-06-2022 15:58:29
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: pow1.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: DSEE (day/night)

```
-----
Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth : 2.00
Number of Years of Growth : 13.00
Medium Truck % of Total Volume : 3.00
Heavy Truck % of Total Volume : 1.00
Day (16 hrs) % of Total Volume : 90.00
```

Data for Segment # 1: DSEE (day/night)

```
-----
Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 63.00 / 63.00 m
Receiver height : 39.50 / 39.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00
```

Road data, segment # 2: DSEW (day/night)

```
-----
Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth : 2.00
Number of Years of Growth : 13.00
Medium Truck % of Total Volume : 3.00
Heavy Truck % of Total Volume : 1.00
Day (16 hrs) % of Total Volume : 90.00
```

Data for Segment # 2: DSEW (day/night)

```

-----
Angle1   Angle2       : -90.00 deg   0.00 deg
Wood depth      :      0      (No woods.)
No of house rows :      0 / 0
Surface         :      2      (Reflective ground surface)
Receiver source distance : 48.00 / 48.00 m
Receiver height  : 39.50 / 39.50 m
Topography      :      1      (Flat/gentle slope; no barrier)
Reference angle  :      0.00
  
```

Results segment # 1: DSEE (day)

Source height = 1.00 m

ROAD (0.00 + 57.29 + 0.00) = 57.29 dBA

```

Angle1 Angle2  Alpha RefLeq  P.Adj  D.Adj  F.Adj  W.Adj  H.Adj  B.Adj
SubLeq
  
```

```

-----
--
-90      0    0.00  66.53    0.00  -6.23  -3.01    0.00    0.00    0.00
57.29
  
```

Segment Leq : 57.29 dBA

Results segment # 2: DSEW (day)

Source height = 1.00 m

ROAD (0.00 + 58.47 + 0.00) = 58.47 dBA

```

Angle1 Angle2  Alpha RefLeq  P.Adj  D.Adj  F.Adj  W.Adj  H.Adj  B.Adj
SubLeq
  
```

```

-----
--
-90      0    0.00  66.53    0.00  -5.05  -3.01    0.00    0.00    0.00
58.47
  
```

Segment Leq : 58.47 dBA

Total Leq All Segments: 60.93 dBA

Results segment # 1: DSEE (night)

Source height = 1.00 m

ROAD (0.00 + 50.77 + 0.00) = 50.77 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

```

-----
--
-90      0      0.00  60.01   0.00  -6.23  -3.01   0.00   0.00   0.00
50.77
-----
--

```

Segment Leq : 50.77 dBA

Results segment # 2: DSEW (night)

Source height = 1.00 m

ROAD (0.00 + 51.95 + 0.00) = 51.95 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

```

-----
--
-90      0      0.00  60.01   0.00  -5.05  -3.01   0.00   0.00   0.00
51.95
-----
--

```

Segment Leq : 51.95 dBA

Total Leq All Segments: 54.41 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 60.93
(NIGHT): 54.41

STAMSON 5.0 NORMAL REPORT Date: 27-06-2022 16:02:20
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: pow2.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: DSEE (day/night)

```
-----
Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth : 2.00
Number of Years of Growth : 13.00
Medium Truck % of Total Volume : 3.00
Heavy Truck % of Total Volume : 1.00
Day (16 hrs) % of Total Volume : 90.00
```

Data for Segment # 1: DSEE (day/night)

```
-----
Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 35.00 / 35.00 m
Receiver height : 39.50 / 39.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00
```

Road data, segment # 2: DSEW (day/night)

```
-----
Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth : 2.00
Number of Years of Growth : 13.00
Medium Truck % of Total Volume : 3.00
Heavy Truck % of Total Volume : 1.00
Day (16 hrs) % of Total Volume : 90.00
```

Data for Segment # 2: DSEW (day/night)

```

-----
Angle1   Angle2       : -90.00 deg   90.00 deg
Wood depth      :          0       (No woods.)
No of house rows :          0 / 0
Surface         :          2       (Reflective ground surface)
Receiver source distance : 20.00 / 20.00 m
Receiver height  : 39.50 / 39.50 m
Topography      :          1       (Flat/gentle slope; no barrier)
Reference angle  :          0.00

```

Road data, segment # 3: AR (day/night)

```

-----
Car traffic volume : 839/359 veh/TimePeriod *
Medium truck volume : 17/7 veh/TimePeriod *
Heavy truck volume : 9/4 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient      : 0 %
Road pavement      : 1 (Typical asphalt or concrete)

```

* Refers to calculated road volumes based on the following input:

```

24 hr Traffic Volume (AADT or SADT): 955
Percentage of Annual Growth      : 2.00
Number of Years of Growth        : 13.00
Medium Truck % of Total Volume   : 2.00
Heavy Truck % of Total Volume    : 1.00
Day (16 hrs) % of Total Volume   : 70.00

```

Data for Segment # 3: AR (day/night)

```

-----
Angle1   Angle2       : -42.00 deg   0.00 deg
Wood depth      :          0       (No woods.)
No of house rows :          0 / 0
Surface         :          2       (Reflective ground surface)
Receiver source distance : 33.00 / 33.00 m
Receiver height  : 39.50 / 39.50 m
Topography      :          1       (Flat/gentle slope; no barrier)
Reference angle  :          0.00

```

Results segment # 1: DSEE (day)

Source height = 1.00 m

ROAD (0.00 + 62.85 + 0.00) = 62.85 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-90	90	0.00	66.53	0.00	-3.68	0.00	0.00	0.00	0.00
62.85									

Segment Leq : 62.85 dBA

Results segment # 2: DSEW (day)

Source height = 1.00 m

ROAD (0.00 + 65.28 + 0.00) = 65.28 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-90	90	0.00	66.53	0.00	-1.25	0.00	0.00	0.00	0.00
65.28									

Segment Leq : 65.28 dBA

Results segment # 3: AR (day)

Source height = 1.01 m

ROAD (0.00 + 40.32 + 0.00) = 40.32 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-42	0	0.00	50.07	0.00	-3.42	-6.32	0.00	0.00	0.00
40.32									

Segment Leq : 40.32 dBA

Total Leq All Segments: 67.25 dBA

Results segment # 1: DSEE (night)

Source height = 1.00 m

ROAD (0.00 + 56.33 + 0.00) = 56.33 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-90	90	0.00	60.01	0.00	-3.68	0.00	0.00	0.00	0.00
56.33									

Segment Leq : 56.33 dBA

Results segment # 2: DSEW (night)

Source height = 1.00 m

ROAD (0.00 + 58.76 + 0.00) = 58.76 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-90	90	0.00	60.01	0.00	-1.25	0.00	0.00	0.00	0.00
58.76									

Segment Leq : 58.76 dBA

Results segment # 3: AR (night)

Source height = 1.02 m

ROAD (0.00 + 39.69 + 0.00) = 39.69 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-42	0	0.00	49.43	0.00	-3.42	-6.32	0.00	0.00	0.00
39.69									

Segment Leq : 39.69 dBA

Total Leq All Segments: 60.76 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 67.25
(NIGHT): 60.76

STAMSON 5.0 NORMAL REPORT Date: 27-06-2022 16:03:24
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: pow3.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: DSEE (day/night)

Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth : 2.00
Number of Years of Growth : 13.00
Medium Truck % of Total Volume : 3.00
Heavy Truck % of Total Volume : 1.00
Day (16 hrs) % of Total Volume : 90.00

Data for Segment # 1: DSEE (day/night)

Angle1 Angle2 : 0.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 64.00 / 64.00 m
Receiver height : 39.50 / 39.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

Road data, segment # 2: DSEW (day/night)

Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth : 2.00
Number of Years of Growth : 13.00
Medium Truck % of Total Volume : 3.00
Heavy Truck % of Total Volume : 1.00
Day (16 hrs) % of Total Volume : 90.00

Data for Segment # 2: DSEW (day/night)

```

-----
Angle1   Angle2       :   0.00 deg   90.00 deg
Wood depth      :           0       (No woods.)
No of house rows :           0 / 0
Surface         :           2       (Reflective ground surface)
Receiver source distance : 49.00 / 49.00 m
Receiver height  : 39.50 / 39.50 m
Topography      :           1       (Flat/gentle slope; no barrier)
Reference angle  :           0.00
  
```

Road data, segment # 3: AR (day/night)

```

-----
Car traffic volume :   839/359   veh/TimePeriod *
Medium truck volume :    17/7    veh/TimePeriod *
Heavy truck volume  :     9/4    veh/TimePeriod *
Posted speed limit  :    40 km/h
Road gradient       :     0 %
Road pavement       :     1 (Typical asphalt or concrete)
  
```

* Refers to calculated road volumes based on the following input:

```

24 hr Traffic Volume (AADT or SADT):    955
Percentage of Annual Growth         :    2.00
Number of Years of Growth           :   13.00
Medium Truck % of Total Volume      :    2.00
Heavy Truck % of Total Volume       :    1.00
Day (16 hrs) % of Total Volume      :   70.00
  
```

Data for Segment # 3: AR (day/night)

```

-----
Angle1   Angle2       : -70.00 deg   73.00 deg
Wood depth      :           0       (No woods.)
No of house rows :           0 / 0
Surface         :           2       (Reflective ground surface)
Receiver source distance : 21.00 / 21.00 m
Receiver height  : 39.50 / 39.50 m
Topography      :           1       (Flat/gentle slope; no barrier)
Reference angle  :           0.00
  
```

Results segment # 1: DSEE (day)

Source height = 1.00 m

ROAD (0.00 + 57.22 + 0.00) = 57.22 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

0	90	0.00	66.53	0.00	-6.30	-3.01	0.00	0.00	0.00
57.22									

Segment Leq : 57.22 dBA

Results segment # 2: DSEW (day)

Source height = 1.00 m

ROAD (0.00 + 58.38 + 0.00) = 58.38 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

0	90	0.00	66.53	0.00	-5.14	-3.01	0.00	0.00	0.00
58.38									

Segment Leq : 58.38 dBA

Results segment # 3: AR (day)

Source height = 1.01 m

ROAD (0.00 + 47.60 + 0.00) = 47.60 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-70	73	0.00	50.07	0.00	-1.46	-1.00	0.00	0.00	0.00
47.60									

Segment Leq : 47.60 dBA

Total Leq All Segments: 61.05 dBA

Results segment # 1: DSEE (night)

Source height = 1.00 m

ROAD (0.00 + 50.70 + 0.00) = 50.70 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

0	90	0.00	60.01	0.00	-6.30	-3.01	0.00	0.00	0.00
50.70									

Segment Leq : 50.70 dBA

Results segment # 2: DSEW (night)

Source height = 1.00 m

ROAD (0.00 + 51.86 + 0.00) = 51.86 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

0	90	0.00	60.01	0.00	-5.14	-3.01	0.00	0.00	0.00
51.86									

Segment Leq : 51.86 dBA

Results segment # 3: AR (night)

Source height = 1.02 m

ROAD (0.00 + 46.97 + 0.00) = 46.97 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-70	73	0.00	49.43	0.00	-1.46	-1.00	0.00	0.00	0.00
46.97									

Segment Leq : 46.97 dBA

Total Leq All Segments: 55.06 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 61.05
(NIGHT): 55.06

STAMSON 5.0 NORMAL REPORT Date: 27-06-2022 16:05:06
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: pow4.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: DSEE1 (day/night)

```
-----
Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth : 2.00
Number of Years of Growth : 13.00
Medium Truck % of Total Volume : 3.00
Heavy Truck % of Total Volume : 1.00
Day (16 hrs) % of Total Volume : 90.00
```

Data for Segment # 1: DSEE1 (day/night)

```
-----
Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 107.00 / 107.00 m
Receiver height : 9.50 / 9.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : -21.00 deg
Barrier height : 17.80 m
Barrier receiver distance : 62.00 / 62.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00
```

Road data, segment # 2: DSEE2 (day/night)

```
-----
Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 12305
```

```

Percentage of Annual Growth      :    2.00
Number of Years of Growth       :   13.00
Medium Truck % of Total Volume  :    3.00
Heavy Truck % of Total Volume   :    1.00
Day (16 hrs) % of Total Volume  :   90.00

```

Data for Segment # 2: DSEE2 (day/night)

```

-----
Angle1   Angle2      :   0.00 deg   90.00 deg
Wood depth      :           0      (No woods.)
No of house rows :           0 / 0
Surface         :           2      (Reflective ground surface)
Receiver source distance : 107.00 / 107.00 m
Receiver height  :    9.50 / 9.50 m
Topography      :           2      (Flat/gentle slope; with barrier)
Barrier angle1   :    9.00 deg   Angle2 : 90.00 deg
Barrier height   :   22.05 m
Barrier receiver distance : 75.00 / 75.00 m
Source elevation :    0.00 m
Receiver elevation :    0.00 m
Barrier elevation :    0.00 m
Reference angle  :    0.00

```

Road data, segment # 3: DSEW1 (day/night)

```

-----
Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient      : 0 %
Road pavement      : 1 (Typical asphalt or concrete)

```

* Refers to calculated road volumes based on the following input:

```

24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth      :    2.00
Number of Years of Growth       :   13.00
Medium Truck % of Total Volume  :    3.00
Heavy Truck % of Total Volume   :    1.00
Day (16 hrs) % of Total Volume  :   90.00

```

Data for Segment # 3: DSEW1 (day/night)

```

-----
Angle1   Angle2      :  -90.00 deg   0.00 deg
Wood depth      :           0      (No woods.)
No of house rows :           0 / 0
Surface         :           2      (Reflective ground surface)
Receiver source distance : 92.00 / 92.00 m
Receiver height  :    9.50 / 9.50 m
Topography      :           2      (Flat/gentle slope; with barrier)
Barrier angle1   :  -90.00 deg   Angle2 : -21.00 deg
Barrier height   :   17.80 m
Barrier receiver distance : 62.00 / 62.00 m
Source elevation :    0.00 m

```

Receiver elevation : 0.00 m
 Barrier elevation : 0.00 m
 Reference angle : 0.00

Road data, segment # 4: DSEW2 (day/night)

 Car traffic volume : 13753/1528 veh/TimePeriod *
 Medium truck volume : 430/48 veh/TimePeriod *
 Heavy truck volume : 143/16 veh/TimePeriod *
 Posted speed limit : 60 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12305
 Percentage of Annual Growth : 2.00
 Number of Years of Growth : 13.00
 Medium Truck % of Total Volume : 3.00
 Heavy Truck % of Total Volume : 1.00
 Day (16 hrs) % of Total Volume : 90.00

Data for Segment # 4: DSEW2 (day/night)

 Angle1 Angle2 : 0.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 92.00 / 92.00 m
 Receiver height : 9.50 / 9.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 9.00 deg Angle2 : 90.00 deg
 Barrier height : 22.05 m
 Barrier receiver distance : 75.00 / 75.00 m
 Source elevation : 0.00 m
 Receiver elevation : 0.00 m
 Barrier elevation : 0.00 m
 Reference angle : 0.00

Road data, segment # 5: AR1 (day/night)

 Car traffic volume : 839/359 veh/TimePeriod *
 Medium truck volume : 17/7 veh/TimePeriod *
 Heavy truck volume : 9/4 veh/TimePeriod *
 Posted speed limit : 40 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 955
 Percentage of Annual Growth : 2.00
 Number of Years of Growth : 13.00
 Medium Truck % of Total Volume : 2.00

```

Heavy Truck % of Total Volume      :    1.00
Day (16 hrs) % of Total Volume     :   70.00

```

Data for Segment # 5: AR1 (day/night)

```

-----
Angle1  Angle2      : -37.00 deg   0.00 deg
Wood depth          :          0      (No woods.)
No of house rows    :          0 / 0
Surface            :          2      (Reflective ground surface)
Receiver source distance : 139.00 / 139.00 m
Receiver height     :    9.50 / 9.50 m
Topography          :          2      (Flat/gentle slope; with barrier)
Barrier angle1      : -37.00 deg   Angle2 : -10.00 deg
Barrier height      :   22.05 m
Barrier receiver distance : 125.00 / 125.00 m
Source elevation    :    0.00 m
Receiver elevation   :    0.00 m
Barrier elevation    :    0.00 m
Reference angle     :    0.00

```

Road data, segment # 6: AR2 (day/night)

```

-----
Car traffic volume :    839/359   veh/TimePeriod *
Medium truck volume :    17/7    veh/TimePeriod *
Heavy truck volume :     9/4     veh/TimePeriod *
Posted speed limit :    40 km/h
Road gradient      :     0 %
Road pavement      :     1 (Typical asphalt or concrete)

```

* Refers to calculated road volumes based on the following input:

```

24 hr Traffic Volume (AADT or SADT) :    955
Percentage of Annual Growth          :     2.00
Number of Years of Growth            :    13.00
Medium Truck % of Total Volume       :     2.00
Heavy Truck % of Total Volume        :     1.00
Day (16 hrs) % of Total Volume       :    70.00

```

Data for Segment # 6: AR2 (day/night)

```

-----
Angle1  Angle2      :    0.00 deg   10.00 deg
Wood depth          :          0      (No woods.)
No of house rows    :          0 / 0
Surface            :          2      (Reflective ground surface)
Receiver source distance : 139.00 / 139.00 m
Receiver height     :    9.50 / 9.50 m
Topography          :          2      (Flat/gentle slope; with barrier)
Barrier angle1      :    0.00 deg   Angle2 : 10.00 deg
Barrier height      :   11.15 m
Barrier receiver distance : 125.00 / 125.00 m
Source elevation    :    0.00 m
Receiver elevation   :    0.00 m
Barrier elevation    :    0.00 m
Reference angle     :    0.00

```

Results segment # 1: DSEE1 (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	9.50	4.57	4.57

ROAD (0.00 + 37.41 + 48.67) = 48.98 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-90	-21	0.00	66.53	0.00	-8.53	-4.16	0.00	0.00	-16.43
37.41									

-21	0	0.00	66.53	0.00	-8.53	-9.33	0.00	0.00	0.00
48.67									

Segment Leq : 48.98 dBA

Results segment # 2: DSEE2 (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	9.50	3.54	3.54

ROAD (44.99 + 36.30 + 0.00) = 45.54 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

0	9	0.00	66.53	0.00	-8.53	-13.01	0.00	0.00	0.00
44.99									

9	90	0.00	66.53	0.00	-8.53	-3.47	0.00	0.00	-18.24
36.30									

Segment Leq : 45.54 dBA

Results segment # 3: DSEW1 (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	9.50	3.77	3.77

ROAD (0.00 + 37.30 + 49.33) = 49.59 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	-21	0.00	66.53	0.00	-7.88	-4.16	0.00	0.00	-17.19
37.30									
-21	0	0.00	66.53	0.00	-7.88	-9.33	0.00	0.00	0.00
49.33									

Segment Leq : 49.59 dBA

Results segment # 4: DSEW2 (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	9.50	2.57	2.57

ROAD (45.65 + 36.42 + 0.00) = 46.14 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
0	9	0.00	66.53	0.00	-7.88	-13.01	0.00	0.00	0.00
45.65									
9	90	0.00	66.53	0.00	-7.88	-3.47	0.00	0.00	-18.77
36.42									

--

Segment Leq : 46.14 dBA

Results segment # 5: AR1 (day)

Source height = 1.01 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.01 !	9.50 !	1.87 !	1.87

ROAD (0.00 + 12.16 + 27.84) = 27.96 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-37	-10	0.00	50.07	0.00	-9.67	-8.24	0.00	0.00	-20.00
12.16									

-10	0	0.00	50.07	0.00	-9.67	-12.55	0.00	0.00	0.00
27.84									

--

Segment Leq : 27.96 dBA

Results segment # 6: AR2 (day)

Source height = 1.01 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.01 !	9.50 !	1.87 !	1.87

ROAD (0.00 + 7.84 + 0.00) = 7.84 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

0	10	0.00	50.07	0.00	-9.67	-12.55	0.00	0.00	-20.00
7.84									

--

Segment Leq : 7.84 dBA

Total Leq All Segments: 53.94 dBA

Results segment # 1: DSEE1 (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	9.50	4.58	4.58

ROAD (0.00 + 30.89 + 42.15) = 42.46 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-90	-21	0.00	60.01	0.00	-8.53	-4.16	0.00	0.00	-16.43
30.89									

-21	0	0.00	60.01	0.00	-8.53	-9.33	0.00	0.00	0.00
42.15									

Segment Leq : 42.46 dBA

Results segment # 2: DSEE2 (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	9.50	3.54	3.54

ROAD (38.47 + 29.78 + 0.00) = 39.02 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

0	9	0.00	60.01	0.00	-8.53	-13.01	0.00	0.00	0.00
38.47									

9 90 0.00 60.01 0.00 -8.53 -3.47 0.00 0.00 -18.24
29.78

Segment Leq : 39.02 dBA

Results segment # 3: DSEW1 (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	9.50	3.77	3.77

ROAD (0.00 + 30.78 + 42.81) = 43.07 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	-21	0.00	60.01	0.00	-7.88	-4.16	0.00	0.00	-17.19

30.78

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-21	0	0.00	60.01	0.00	-7.88	-9.33	0.00	0.00	0.00

Segment Leq : 43.07 dBA

Results segment # 4: DSEW2 (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	9.50	2.57	2.57

ROAD (39.13 + 29.90 + 0.00) = 39.62 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	-21	0.00	60.01	0.00	-7.88	-4.16	0.00	0.00	-17.19

0 9 0.00 60.01 0.00 -7.88 -13.01 0.00 0.00 0.00
39.13

--
9 90 0.00 60.01 0.00 -7.88 -3.47 0.00 0.00 -18.77
29.90

Segment Leq : 39.62 dBA

Results segment # 5: AR1 (night)

Source height = 1.02 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.02	9.50	1.87	1.87

ROAD (0.00 + 11.52 + 27.21) = 27.33 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-37	-10	0.00	49.43	0.00	-9.67	-8.24	0.00	0.00	-20.00

11.52

-10	0	0.00	49.43	0.00	-9.67	-12.55	0.00	0.00	0.00
-----	---	------	-------	------	-------	--------	------	------	------

Segment Leq : 27.33 dBA

Results segment # 6: AR2 (night)

Source height = 1.02 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.02	9.50	1.87	1.87

ROAD (0.00 + 7.21 + 0.00) = 7.21 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj

```

-----
--
    0      10    0.00  49.43    0.00  -9.67 -12.55    0.00    0.00 -20.00
7.21
-----
--

```

Segment Leq : 7.21 dBA

Total Leq All Segments: 47.45 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 53.94
 (NIGHT): 47.45

STAMSON 5.0 NORMAL REPORT Date: 27-06-2022 16:06:08
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: pow5.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: DSEE (day/night)

Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12305
Percentage of Annual Growth : 2.00
Number of Years of Growth : 13.00
Medium Truck % of Total Volume : 3.00
Heavy Truck % of Total Volume : 1.00
Day (16 hrs) % of Total Volume : 90.00

Data for Segment # 1: DSEE (day/night)

Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 107.00 / 107.00 m
Receiver height : 9.50 / 9.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 0.00 deg
Barrier height : 22.05 m
Barrier receiver distance : 75.00 / 75.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00

Road data, segment # 2: DSEW (day/night)

Car traffic volume : 13753/1528 veh/TimePeriod *
Medium truck volume : 430/48 veh/TimePeriod *
Heavy truck volume : 143/16 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 12305

```

Percentage of Annual Growth      :    2.00
Number of Years of Growth       :   13.00
Medium Truck % of Total Volume  :    3.00
Heavy Truck % of Total Volume   :    1.00
Day (16 hrs) % of Total Volume  :   90.00

```

Data for Segment # 2: DSEW (day/night)

```

-----
Angle1   Angle2      : -90.00 deg   90.00 deg
Wood depth      :      0      (No woods.)
No of house rows :      0 / 0
Surface        :      2      (Reflective ground surface)
Receiver source distance :  92.00 / 92.00 m
Receiver height :    9.50 / 9.50 m
Topography     :      2      (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg   Angle2 : 0.00 deg
Barrier height :   22.05 m
Barrier receiver distance :  75.00 / 75.00 m
Source elevation :    0.00 m
Receiver elevation :    0.00 m
Barrier elevation :    0.00 m
Reference angle :    0.00

```

Road data, segment # 3: AR (day/night)

```

-----
Car traffic volume :   839/359   veh/TimePeriod *
Medium truck volume :    17/7    veh/TimePeriod *
Heavy truck volume :     9/4     veh/TimePeriod *
Posted speed limit :    40 km/h
Road gradient      :     0 %
Road pavement     :     1 (Typical asphalt or concrete)

```

* Refers to calculated road volumes based on the following input:

```

24 hr Traffic Volume (AADT or SADT) :    955
Percentage of Annual Growth      :    2.00
Number of Years of Growth       :   13.00
Medium Truck % of Total Volume  :    2.00
Heavy Truck % of Total Volume   :    1.00
Day (16 hrs) % of Total Volume  :   70.00

```

Data for Segment # 3: AR (day/night)

```

-----
Angle1   Angle2      : -82.00 deg   61.00 deg
Wood depth      :      0      (No woods.)
No of house rows :      0 / 0
Surface        :      2      (Reflective ground surface)
Receiver source distance :  15.00 / 15.00 m
Receiver height :    9.50 / 9.50 m
Topography     :      1      (Flat/gentle slope; no barrier)
Reference angle :    0.00

```

Results segment # 1: DSEE (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	9.50	3.54	3.54

ROAD (0.00 + 36.61 + 54.99) = 55.05 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	0	0.00	66.53	0.00	-8.53	-3.01	0.00	0.00	-18.38
36.61									
0	90	0.00	66.53	0.00	-8.53	-3.01	0.00	0.00	0.00
54.99									

SubLeq

Segment Leq : 55.05 dBA

Results segment # 2: DSEW (day)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	9.50	2.57	2.57

ROAD (0.00 + 36.77 + 55.65) = 55.70 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
-90	0	0.00	66.53	0.00	-7.88	-3.01	0.00	0.00	-18.88
36.77									
0	90	0.00	66.53	0.00	-7.88	-3.01	0.00	0.00	0.00
55.65									

SubLeq

Segment Leq : 55.70 dBA

Results segment # 3: AR (day)

Source height = 1.01 m

ROAD (0.00 + 49.07 + 0.00) = 49.07 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-82	61	0.00	50.07	0.00	0.00	-1.00	0.00	0.00	0.00
49.07									

Segment Leq : 49.07 dBA

Total Leq All Segments: 58.88 dBA

Results segment # 1: DSEE (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.00	9.50	3.54	3.54

ROAD (0.00 + 30.09 + 48.47) = 48.53 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

-90	0	0.00	60.01	0.00	-8.53	-3.01	0.00	0.00	-18.38
30.09									

0	90	0.00	60.01	0.00	-8.53	-3.01	0.00	0.00	0.00
48.47									

Segment Leq : 48.53 dBA

Results segment # 2: DSEW (night)

Source height = 1.00 m

Barrier height for grazing incidence

Source	!	Receiver	!	Barrier	!	Elevation of
Height (m)	!	Height (m)	!	Height (m)	!	Barrier Top (m)
-----	+	-----	+	-----	+	-----
1.00	!	9.50	!	2.57	!	2.57

ROAD (0.00 + 30.25 + 49.13) = 49.18 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

--									
-90	0	0.00	60.01	0.00	-7.88	-3.01	0.00	0.00	-18.88
30.25									

--									
0	90	0.00	60.01	0.00	-7.88	-3.01	0.00	0.00	0.00
49.13									

--									

Segment Leq : 49.18 dBA

Results segment # 3: AR (night)

Source height = 1.02 m

ROAD (0.00 + 48.43 + 0.00) = 48.43 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj
SubLeq									

--									
-82	61	0.00	49.43	0.00	0.00	-1.00	0.00	0.00	0.00
48.43									

--									

Segment Leq : 48.43 dBA

Total Leq All Segments: 53.50 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 58.88

(NIGHT): 53.50

Appendix D: Manufacturer Specifications



Product Data

WeatherMaster®

Gas Heat/Electric Cooling
Packaged Rooftop Units

3 to 12.5 Nominal Tons



48HC Sizes 04 to 14
Packaged Rooftop Units with Gas Heat and Optional
EnergyX® Energy Recovery Ventilator

Capacity ratings (cont)



Typical one-fan RTU

SOUND RATINGS TABLE

48HC UNIT	COOLING STAGES	OUTDOOR SOUND (dB) AT 60 HZ								
		A-WEIGHTED	63	125	250	500	1000	2000	4000	8000
A04	1	76	78.2	78.0	74.2	73.3	70.6	66.0	62.4	56.9
A05	1	78	84.7	83.6	77.1	74.6	72.3	68.3	64.7	60.9
A06	1	77	87.5	82.5	76.1	73.6	71.3	67.1	64.1	60.0
A07	1	82	90.1	82.6	81.0	79.4	77.0	73.0	70.4	66.7
D07	2	82	90.1	82.6	81.0	79.4	77.0	73.0	70.4	66.7
D08	2	82	90.6	84.3	80.2	79.3	77.1	72.2	67.4	63.7
D09	2	82	88.6	85.0	81.6	79.5	77.4	74.1	71.0	66.3
D11	2	87	85.9	87.9	85.6	84.4	82.8	78.5	74.9	72.5
D12	2	87	85.9	87.9	85.6	84.4	82.8	78.5	74.9	72.5
D14	2	83	89.3	86.0	82.9	80.7	78.5	73.6	69.6	64.5

LEGEND

dB — Decibel

NOTES:

1. Outdoor sound data is measured in accordance with AHRI.
2. Measurements are expressed in terms of sound power. Do not compare these values to sound pressure values because sound pressure depends on specific environmental factors which normally do not match individual applications. Sound power values are independent of the environment and therefore more accurate.
3. A-weighted sound ratings filter out very high and very low frequencies, to better approximate the response of "average" human ear. A-weighted measurements for Carrier units are taken in accordance with AHRI.

Typical two-fan RTU

Appendix E: CadnaA Calculation Output





Report (1225 Dundas St E.cna)

Calculation Configuration

Configuration	
Parameter	Value
General	
Country	(user defined)
Max. Error (dB)	0.00
Max. Search Radius (#(Unit,LEN))	2000.00
Min. Dist Src to Rcvr	0.00
Partition	
Raster Factor	0.50
Max. Length of Section (#(Unit,LEN))	1000.00
Min. Length of Section (#(Unit,LEN))	1.00
Min. Length of Section (%)	0.00
Proj. Line Sources	On
Proj. Area Sources	On
Ref. Time	
Reference Time Day (min)	960.00
Reference Time Night (min)	480.00
Daytime Penalty (dB)	0.00
Recr. Time Penalty (dB)	0.00
Night-time Penalty (dB)	0.00
DTM	
Standard Height (m)	0.00
Model of Terrain	Triangulation
Reflection	
max. Order of Reflection	2
Search Radius Src	100.00
Search Radius Rcvr	100.00
Max. Distance Source - Rcvr	1000.00 1000.00
Min. Distance Rcvr - Reflector	1.00 1.00
Min. Distance Source - Reflector	0.10
Industrial (ISO 9613)	
Lateral Diffraction	some Obj
Obst. within Area Src do not shield	On
Screening	Excl. Ground Att. over Barrier
	Dz with limit (20/25)
Barrier Coefficients C1,2,3	3.0 20.0 0.0
Temperature (#(Unit,TEMP))	10
rel. Humidity (%)	70
Ground Absorption G	0.20
Wind Speed for Dir. (#(Unit,SPEED))	3.0
Roads (RLS-90)	
Strictly acc. to RLS-90	
Railways (Schall 03 (1990))	
Strictly acc. to Schall 03 / Schall-Transrapid	
Aircraft (???)	
Strictly acc. to AzB	

Result Table

Receiver		Land Use	Limiting Value		rel. Axis			Lr w/o Noise Control		dL req.		Lr w/ Noise Control		Exceeding		passive NC
Name	ID		Day	Night	Station	Distance	Height	Day	Night	Day	Night	Day	Night	Day	Night	
			dB(A)	dB(A)	m	m	m	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)
POPOR1	POPOR1		0	0				42.7	39.6	42.7	39.6	0.0	0.0	-	-	-

Group Day and Night

Name	Expression	Partial Sum Level		
		POPOR1		
		Day	Evening	Night
Root	!*			

Partial Day/Night

Source			Partial Level		
Name	M.	ID	POPOR1		
			Day	Evening	Night
SHVAC01		SHVAC01	3.6	0.6	0.6
SHVAC02		SHVAC02	3.7	0.7	0.7
SHVAC03		SHVAC03	3.9	0.9	0.9
SHVAC04		SHVAC04	4.1	1.1	1.1
SHVAC05		SHVAC05	3.8	0.8	0.8
SHVAC06		SHVAC06	3.9	0.9	0.9
SHVAC07		SHVAC07	4.1	1.1	1.1
SHVAC08		SHVAC08	4.1	1.0	1.0
SHVAC09		SHVAC09	7.8	4.7	4.7
SHVAC10		SHVAC10	3.9	0.9	0.9
SHVAC11		SHVAC11	5.0	2.0	2.0
SHVAC12		SHVAC12	6.2	3.2	3.2
SHVAC13		SHVAC13	6.9	3.8	3.8
SHVAC14		SHVAC14	6.5	3.5	3.5
SHVAC15		SHVAC15	6.9	3.9	3.9
SHVAC16		SHVAC16	6.8	3.8	3.8
SHVAC17		SHVAC17	7.4	4.4	4.4
SHVAC18		SHVAC18	4.2	1.1	1.1
SHVAC19		SHVAC19	4.7	1.7	1.7
SHVAC20		SHVAC20	5.1	2.1	2.1
SHVAC21		SHVAC21	4.4	1.4	1.4
SHVAC22		SHVAC22	4.8	1.8	1.8
SHVAC23		SHVAC23	5.2	2.2	2.2
SHVAC24		SHVAC24	30.2	27.2	27.2
SHVAC25		SHVAC25	32.7	29.7	29.7
SHVAC26		SHVAC26	30.7	27.7	27.7
SHVAC27		SHVAC27	32.8	29.8	29.8
SHVAC28		SHVAC28	29.2	26.2	26.2
SHVAC29		SHVAC29	33.6	30.6	30.6
SHVAC30		SHVAC30	32.1	29.1	29.1
SHVAC31		SHVAC31	29.6	26.6	26.6
SHVAC32		SHVAC32	32.0	28.9	28.9
SHVAC33		SHVAC33	30.2	27.2	27.2
SHVAC34		SHVAC34	30.9	27.9	27.9
SHVAC35		SHVAC35	29.8	26.8	26.8
SHVAC36		SHVAC36	30.3	27.3	27.3
SHVAC37		SHVAC37	29.3	26.3	26.3
SHVAC38		SHVAC38	9.4	6.4	6.4

Sound Sources

Point Sources

Name	M.	ID	Result. PWL			Lw / Li		Correction			Sound Reduction		Attenuation	Operating Time			K0	Freq.	Direct.	Height		Coordinates		
			Day	Evening	Night	Type	Value	norm.	Day	Evening	Night	R	Area	Day	Special	Night						X	Y	Z
			(dBA)	(dBA)	(dBA)			dB(A)	dB(A)	dB(A)	dB(A)		(m²)	(min)	(min)	(min)	(dB)	(Hz)		(m)		(m)	(m)	(m)
SHVAC01		SHVAC01	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613764.76	4828987.82	9.10
SHVAC02		SHVAC02	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613768.13	4828985.18	9.10
SHVAC03		SHVAC03	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613771.22	4828982.72	9.10
SHVAC04		SHVAC04	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613775.35	4828982.46	9.10
SHVAC05		SHVAC05	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613769.49	4828997.74	9.10
SHVAC06		SHVAC06	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613773.50	4829003.02	9.10
SHVAC07		SHVAC07	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613777.33	4829000.11	9.10
SHVAC08		SHVAC08	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613776.78	4828994.74	9.10
SHVAC09		SHVAC09	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613814.15	4828960.16	5.80
SHVAC10		SHVAC10	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613803.98	4828988.80	5.80
SHVAC11		SHVAC11	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613814.76	4828982.87	5.80
SHVAC12		SHVAC12	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613818.68	4829000.19	8.70
SHVAC13		SHVAC13	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613822.44	4828996.44	8.70
SHVAC14		SHVAC14	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613830.49	4829015.28	8.70
SHVAC15		SHVAC15	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613833.42	4829009.98	8.70
SHVAC16		SHVAC16	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613842.66	4829028.27	5.70
SHVAC17		SHVAC17	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613849.62	4829022.32	5.70
SHVAC18		SHVAC18	77.6	77.6	77.6	Lw	One_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613867.31	4829039.52	5.80
SHVAC19		SHVAC19	77.6	77.6	77.6	Lw	One_Fan_HVAC		0.0	0.0	0.0			60.00	30.00	30.00	0.0		(none)	1.00	g	17613871.13	4829034.74	5.80

Name	M.	ID	Result. PWL			Lw / Li			Correction			Sound Reduction		Attenuation	Operating Time			K0	Freq.	Direct.	Height	Coordinates			
			Day	Evening	Night	Type	Value	norm.	Day	Evening	Night	R	Area		Day	Special	Night						X	Y	Z
			(dBA)	(dBA)	(dBA)			dB(A)	dB(A)	dB(A)	dB(A)		(m²)		(min)	(min)	(min)	(dB)	(Hz)		(m)		(m)	(m)	(m)
SHVAC20		SHVAC20	77.6	77.6	77.6	Lw	One_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17613877.26	4829038.60	5.80
SHVAC21		SHVAC21	77.6	77.6	77.6	Lw	One_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17613872.92	4829047.04	5.80
SHVAC22		SHVAC22	77.6	77.6	77.6	Lw	One_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17613876.16	4829043.51	5.80
SHVAC23		SHVAC23	77.6	77.6	77.6	Lw	One_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17613880.45	4829042.41	5.80
SHVAC24		SHVAC24	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614029.47	4828990.32	8.00
SHVAC25		SHVAC25	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614015.25	4829018.93	8.00
SHVAC26		SHVAC26	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614033.80	4829003.27	8.00
SHVAC27		SHVAC27	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614030.78	4829036.17	8.00
SHVAC28		SHVAC28	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614063.00	4829000.10	8.00
SHVAC29		SHVAC29	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614033.80	4829055.42	8.00
SHVAC30		SHVAC30	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614044.00	4829040.91	8.00
SHVAC31		SHVAC31	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614071.17	4829020.37	8.00
SHVAC32		SHVAC32	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614054.07	4829056.72	8.00
SHVAC33		SHVAC33	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614072.32	4829040.34	8.00
SHVAC34		SHVAC34	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614074.42	4829091.31	7.70
SHVAC35		SHVAC35	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614088.84	4829077.19	7.70
SHVAC36		SHVAC36	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614082.93	4829099.81	7.70
SHVAC37		SHVAC37	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17614097.35	4829086.55	7.70
SHVAC38		SHVAC38	81.7	81.7	81.7	Lw	Two_Fan_HVAC		0.0	0.0	0.0				60.00	30.00	30.00	0.0		(none)	1.00	g	17613988.37	4829192.93	18.80

Line Sources

Name	M.	ID	Result. PWL			Result. PWL'			Lw / Li		Correction			Sound Reduction		Attenuation	Operating Time			K0	Freq.	Direct.	Moving Pt. Src				
			Day	Evening	Night	Day	Evening	Night	Type	Value	norm.	Day	Evening	Night	R	Area		Day	Special	Night				Number		Speed	
			(dBA)	(dBA)	(dBA)	(dBA)	(dBA)	(dBA)		dB(A)	dB(A)	dB(A)	dB(A)	dB(A)		(m²)		(min)	(min)	(min)	(dB)	(Hz)		Day	Evening	Night	(km/h)

Geometry Line Sources

Name	Height		Coordinates			
	Begin	End	x	y	z	Ground
	(m)	(m)	(m)	(m)	(m)	(m)

Area Sources

Name	M.	ID	Result. PWL			Result. PWL"			Lw / Li			Correction			Sound Reduction		Attenuation	Operating Time			K0	Freq.	Direct.	Moving Pt. Src		
			Day	Evening	Night	Day	Evening	Night	Type	Value	norm.	Day	Evening	Night	R	Area		Day	Special	Night				Number		
			(dBA)	(dBA)	(dBA)	(dBA)	(dBA)	(dBA)		dB(A)	dB(A)	dB(A)	dB(A)			(m²)		(min)	(min)	(min)	(dB)	(Hz)		Day	Evening	Night

Geometry Area Sources

Name	Height		Coordinates			
	Begin	End	x	y	z	Ground
	(m)	(m)	(m)	(m)	(m)	(m)

Vertical Area Sources

Name	M.	ID	Result. PWL			Result. PWL"			Lw / Li			Correction			Sound Reduction		Attenuation	Operating Time			K0	Freq.	Direct.	
			Day	Evening	Night	Day	Evening	Night	Type	Value	norm.	Day	Evening	Night	R	Area		Day	Special	Night				
			(dBA)	(dBA)	(dBA)	(dBA)	(dBA)	(dBA)		dB(A)	dB(A)	dB(A)	dB(A)			(m²)		(min)	(min)	(min)	(dB)	(Hz)		

Geometry Vertical Area Sources

Name	Height		Coordinates			
	Begin	End	x	y	z	Ground
	(m)	(m)	(m)	(m)	(m)	(m)

Road

Name	M.	ID	Lme			Count Data		exact Count Data						Speed Limit		SCS	Surface		Gradient	Mult. Reflection		
			Day	Evening	Night	DTV	Str.class.	M			p (%)			Auto	Truck	Dist.	Dstro	Type		Drefl	Hbuild	Dist.
			(dBA)	(dBA)	(dBA)			Day	Evening	Night	Day	Evening	Night	(km/h)	(km/h)		(dB)		(%)	(dB)	(m)	(m)

Geometry Road

Name	Height		Coordinates				Dist	LSlope
	Begin	End	x	y	z	Ground	(m)	(%)
	(m)	(m)	(m)	(m)	(m)	(m)		

Receptors

Name	M.	ID	Level Lr			Limit. Value			Land Use			Height		Coordinates		
			Day	Evening	Night	Day	Evening	Night	Type	Auto	Noise Type			X	Y	Z
			(dBA)	(dBA)	(dBA)	(dBA)	(dBA)	(dBA)				(m)		(m)	(m)	(m)
POPOR1		POPOR1	42.7	39.6	39.6	0.0	0.0	0.0		x	Total	1.50 g		17613957.63	4829095.33	32.70

Obstacles

Barriers

Name	M.	ID	Absorption		Z-Ext.	Cantilever		Height	
			left	right		horz.	vert.	Begin	End
					(m)	(m)	(m)	(m)	(m)

Geometry Barriers

Name	M.	ID	Absorption		Z-Ext.	Cantilever		Height		Coordinates			
			left	right		horz.	vert.	Begin	End	x	y	z	Ground
					(m)	(m)	(m)	(m)	(m)	(m)	(m)	(m)	(m)

Building

Name	M.	ID			RB	Residents	Absorption	Height	
								Begin	
								(m)	
		Notes_Surrounding_Buildings			x	0		5.50	a
		Notes_Surrounding_Buildings			x	0		4.00	a
		Notes_Surrounding_Buildings			x	0		5.00	a
		Notes_Surrounding_Buildings			x	0		7.00	a
		Notes_Surrounding_Buildings			x	0		6.70	a
		Notes_Surrounding_Buildings			x	0		8.10	a
		Notes_Surrounding_Buildings			x	0		4.80	a
		Notes_Surrounding_Buildings			x	0		4.00	a
		Notes_Surrounding_Buildings			x	0		7.70	a
		Notes_Surrounding_Buildings			x	0		4.70	a
		Notes_Surrounding_Buildings			x	0		4.80	a
		Notes_Surrounding_Buildings			x	0		4.80	a
		Notes_Surrounding_Buildings			x	0		17.80	a
		Notes_Surrounding_Buildings			x	0		22.20	a
		Notes_Surrounding_Buildings			x	0		44.00	a
		Notes_Surrounding_Buildings			x	0		11.50	a
		Notes_Surrounding_Buildings			x	0		11.50	a
		Notes_Surrounding_Buildings			x	0		12.00	a
		Notes_Surrounding_Buildings			x	0		12.00	a
		Notes_Surrounding_Buildings			x	0		12.00	a
		Notes_Surrounding_Buildings			x	0		9.00	a
		Notes_Surrounding_Buildings			x	0		9.00	a
		Notes_Surrounding_Buildings			x	0		9.00	a
		Notes_Surrounding_Buildings			x	0		9.00	a
		Notes_Surrounding_Buildings			x	0		9.00	a
		Notes_Surrounding_Buildings			x	0		4.00	a
		Notes_Surrounding_Buildings			x	0		7.00	a
		Notes_Project_Buildings			x	0		7.90	a
		Notes_Project_Buildings			x	0		16.15	a
		Notes_Project_Buildings			x	0		22.05	a
		Notes_Project_Buildings			x	0		31.20	a
		Notes_Project_Buildings			x	0		41.50	a
		Notes_Project_Buildings			x	0		41.50	a
		Notes_Project_Buildings			x	0		47.50	a
		Notes_Project_Buildings			x	0		47.50	a
		Notes_Project_Buildings			x	0		11.15	a
		Notes_Project_Buildings			x	0		7.90	a
		Notes_Project_Buildings			x	0		11.15	a
		Notes_Project_Buildings			x	0		7.90	a
		Notes_Project_Buildings			x	0		11.15	a
		Notes_Project_Buildings			x	0		7.90	a
		Notes_Project_Buildings			x	0		11.15	a

Geometry Building

Name	M.	ID	RB	Residents	Absorption	Height	Coordinates			
						Begin	x	y	z	Ground
						(m)	(m)	(m)	(m)	(m)
		Notes_Surrounding_Buildings	x	0		5.50 a	17613932.98	4828953.82	5.50	0.00
							17613950.30	4828940.42	5.50	0.00
							17613957.46	4828949.67	5.50	0.00
							17613953.71	4828952.57	5.50	0.00
							17613958.71	4828959.04	5.50	0.00
							17613945.15	4828969.54	5.50	0.00
		Notes_Surrounding_Buildings	x	0		4.00 a	17613957.11	4828949.22	4.00	0.00
							17613962.58	4828944.98	4.00	0.00
							17613956.19	4828936.72	4.00	0.00
							17613950.72	4828940.96	4.00	0.00
		Notes_Surrounding_Buildings	x	0		5.00 a	17613996.49	4828956.66	5.00	0.00
							17614009.59	4828946.45	5.00	0.00
							17614014.35	4828952.31	5.00	0.00
							17614001.25	4828962.52	5.00	0.00
		Notes_Surrounding_Buildings	x	0		7.00 a	17613995.07	4829015.61	7.00	0.00
							17614051.26	4828963.15	7.00	0.00
							17614087.43	4829001.89	7.00	0.00
							17614081.14	4829007.77	7.00	0.00
							17614087.73	4829014.82	7.00	0.00
							17614081.69	4829020.45	7.00	0.00
							17614087.15	4829026.29	7.00	0.00
							17614081.03	4829032.01	7.00	0.00
							17614086.82	4829038.21	7.00	0.00
							17614045.72	4829076.58	7.00	0.00
							17614025.79	4829055.23	7.00	0.00
							17614027.49	4829053.64	7.00	0.00
							17614009.51	4829034.39	7.00	0.00
							17614011.16	4829032.85	7.00	0.00
		Notes_Surrounding_Buildings	x	0		6.70 a	17614061.57	4829092.33	6.70	0.00
							17614089.00	4829066.84	6.70	0.00
							17614109.01	4829088.37	6.70	0.00
							17614081.59	4829113.86	6.70	0.00
		Notes_Surrounding_Buildings	x	0		8.10 a	17613755.37	4828989.19	8.10	0.00
							17613774.02	4829013.68	8.10	0.00
							17613789.15	4829002.16	8.10	0.00
							17613779.57	4828989.58	8.10	0.00
							17613784.04	4828986.17	8.10	0.00
							17613774.97	4828974.26	8.10	0.00
		Notes_Surrounding_Buildings	x	0		4.80 a	17613809.44	4828958.92	4.80	0.00
							17613826.40	4828944.69	4.80	0.00
							17613831.43	4828950.67	4.80	0.00
							17613814.47	4828964.91	4.80	0.00
		Notes_Surrounding_Buildings	x	0		4.00 a	17613814.47	4828964.91	4.00	0.00
							17613811.88	4828967.08	4.00	0.00
							17613803.97	4828957.66	4.00	0.00
							17613821.09	4828943.29	4.00	0.00
							17613823.97	4828946.73	4.00	0.00
							17613809.44	4828958.92	4.00	0.00
		Notes_Surrounding_Buildings	x	0		7.70 a	17613809.19	4828996.08	7.70	0.00
							17613834.34	4829027.25	7.70	0.00
							17613851.25	4829013.60	7.70	0.00
							17613826.10	4828982.43	7.70	0.00
		Notes_Surrounding_Buildings	x	0		4.70 a	17613830.00	4829030.76	4.70	0.00
							17613853.55	4829011.75	4.70	0.00
							17613863.04	4829023.51	4.70	0.00
							17613839.49	4829042.52	4.70	0.00
		Notes_Surrounding_Buildings	x	0		4.80 a	17613795.35	4828987.83	4.80	0.00
							17613818.90	4828968.82	4.80	0.00
							17613828.39	4828980.58	4.80	0.00
							17613804.84	4828999.59	4.80	0.00
		Notes_Surrounding_Buildings	x	0		4.80 a	17613862.47	4829038.59	4.80	0.00
							17613873.26	4829030.03	4.80	0.00
							17613883.77	4829043.26	4.80	0.00
							17613872.98	4829051.83	4.80	0.00
		Notes_Surrounding_Buildings	x	0		17.80 a	17613981.60	4829191.15	17.80	0.00
							17614008.25	4829170.21	17.80	0.00
							17614018.77	4829183.61	17.80	0.00

Name	M.	ID	RB	Residents	Absorption	Height	Coordinates			
						Begin	x	y	z	Ground
						(m)	(m)	(m)	(m)	(m)
							17613997.66	4829200.20	17.80	0.00
							17614000.46	4829203.76	17.80	0.00
							17613968.16	4829229.13	17.80	0.00
							17613957.48	4829215.53	17.80	0.00
							17613984.24	4829194.52	17.80	0.00
		Notes_Surrounding_Buildings	x	0		22.20 a	17613990.84	4829201.09	22.20	0.00
							17613987.08	4829196.30	22.20	0.00
							17613991.14	4829193.11	22.20	0.00
							17613994.90	4829197.90	22.20	0.00
		Notes_Surrounding_Buildings	x	0		44.00 a	17614030.38	4829270.18	44.00	0.00
							17614041.40	4829261.50	44.00	0.00
							17614035.83	4829254.43	44.00	0.00
							17614048.42	4829244.52	44.00	0.00
							17614053.99	4829251.58	44.00	0.00
							17614065.40	4829242.59	44.00	0.00
							17614075.15	4829254.96	44.00	0.00
							17614063.73	4829263.95	44.00	0.00
							17614070.83	4829272.97	44.00	0.00
							17614058.25	4829282.89	44.00	0.00
							17614051.14	4829273.87	44.00	0.00
							17614040.12	4829282.55	44.00	0.00
		Notes_Surrounding_Buildings	x	0		11.50 a	17613753.35	4829055.15	11.50	0.00
							17613777.97	4829035.73	11.50	0.00
							17613786.34	4829046.34	11.50	0.00
							17613761.71	4829065.76	11.50	0.00
		Notes_Surrounding_Buildings	x	0		11.50 a	17613814.43	4829036.04	11.50	0.00
							17613843.95	4829073.17	11.50	0.00
							17613834.57	4829080.63	11.50	0.00
							17613805.05	4829043.50	11.50	0.00
		Notes_Surrounding_Buildings	x	0		12.00 a	17613768.15	4829088.14	12.00	0.00
							17613801.51	4829061.32	12.00	0.00
							17613808.84	4829070.42	12.00	0.00
							17613775.47	4829097.25	12.00	0.00
		Notes_Surrounding_Buildings	x	0		12.00 a	17613784.75	4829109.51	12.00	0.00
							17613818.24	4829082.15	12.00	0.00
							17613825.90	4829091.52	12.00	0.00
							17613792.41	4829118.89	12.00	0.00
		Notes_Surrounding_Buildings	x	0		12.00 a	17613738.82	4829097.50	12.00	0.00
							17613774.26	4829140.54	12.00	0.00
							17613784.73	4829131.92	12.00	0.00
							17613749.29	4829088.88	12.00	0.00
		Notes_Surrounding_Buildings	x	0		9.00 a	17613743.86	4829197.16	9.00	0.00
							17613832.47	4829123.93	9.00	0.00
							17613838.90	4829131.72	9.00	0.00
							17613750.29	4829204.94	9.00	0.00
		Notes_Surrounding_Buildings	x	0		9.00 a	17613748.25	4829238.69	9.00	0.00
							17613853.75	4829151.28	9.00	0.00
							17613859.60	4829158.34	9.00	0.00
							17613754.10	4829245.75	9.00	0.00
		Notes_Surrounding_Buildings	x	0		9.00 a	17613836.32	4829220.19	9.00	0.00
							17613876.94	4829181.89	9.00	0.00
							17613883.74	4829189.11	9.00	0.00
							17613843.12	4829227.41	9.00	0.00
		Notes_Surrounding_Buildings	x	0		9.00 a	17613775.43	4829275.81	9.00	0.00
							17613818.01	4829232.41	9.00	0.00
							17613826.06	4829240.32	9.00	0.00
							17613783.49	4829283.71	9.00	0.00
		Notes_Surrounding_Buildings	x	0		9.00 a	17613815.40	4829287.17	9.00	0.00
							17613897.86	4829209.19	9.00	0.00
							17613904.86	4829216.60	9.00	0.00
							17613822.40	4829294.57	9.00	0.00
		Notes_Surrounding_Buildings	x	0		4.00 a	17613912.98	4829242.97	4.00	0.00
							17613944.39	4829271.60	4.00	0.00
							17613951.27	4829264.05	4.00	0.00
							17613919.86	4829235.42	4.00	0.00
		Notes_Surrounding_Buildings	x	0		7.00 a	17613861.39	4829277.52	7.00	0.00
							17613892.29	4829315.49	7.00	0.00

Name	M.	ID	RB	Residents	Absorption	Height	Coordinates			
						Begin	x	y	z	Ground
						(m)	(m)	(m)	(m)	(m)
							17613900.93	4829308.45	7.00	0.00
							17613870.03	4829270.49	7.00	0.00
		Notes_Project_Buildings	x	0		7.90 a	17613854.96	4829100.30	7.90	0.00
							17613870.48	4829120.17	7.90	0.00
							17613882.01	4829111.16	7.90	0.00
							17613866.50	4829091.29	7.90	0.00
		Notes_Project_Buildings	x	0		16.15 a	17613990.41	4829138.44	16.15	0.00
							17613949.50	4829170.40	16.15	0.00
							17613934.10	4829150.68	16.15	0.00
							17613962.54	4829128.46	16.15	0.00
							17613925.32	4829080.82	16.15	0.00
							17613896.88	4829103.04	16.15	0.00
							17613881.47	4829083.32	16.15	0.00
							17613922.39	4829051.36	16.15	0.00
							17613931.10	4829052.42	16.15	0.00
							17613958.18	4829087.09	16.15	0.00
							17613956.59	4829088.33	16.15	0.00
							17613964.41	4829098.34	16.15	0.00
							17613966.00	4829097.10	16.15	0.00
							17613991.48	4829129.72	16.15	0.00
		Notes_Project_Buildings	x	0		22.05 a	17613990.41	4829138.44	22.05	0.00
							17613951.87	4829168.55	22.05	0.00
							17613936.46	4829148.83	22.05	0.00
							17613962.54	4829128.46	22.05	0.00
							17613925.32	4829080.82	22.05	0.00
							17613899.24	4829101.20	22.05	0.00
							17613883.83	4829081.48	22.05	0.00
							17613922.39	4829051.36	22.05	0.00
							17613931.10	4829052.42	22.05	0.00
							17613958.18	4829087.09	22.05	0.00
							17613956.59	4829088.33	22.05	0.00
							17613964.41	4829098.34	22.05	0.00
							17613966.00	4829097.10	22.05	0.00
							17613991.48	4829129.72	22.05	0.00
		Notes_Project_Buildings	x	0		31.20 a	17613987.58	4829136.84	31.20	0.00
							17613950.02	4829166.19	31.20	0.00
							17613938.31	4829151.21	31.20	0.00
							17613964.39	4829130.83	31.20	0.00
							17613923.47	4829078.46	31.20	0.00
							17613897.39	4829098.83	31.20	0.00
							17613885.69	4829083.85	31.20	0.00
							17613923.25	4829054.50	31.20	0.00
							17613929.49	4829055.27	31.20	0.00
							17613938.46	4829066.75	31.20	0.00
							17613937.68	4829067.36	31.20	0.00
							17613978.59	4829119.73	31.20	0.00
							17613979.38	4829119.12	31.20	0.00
							17613988.34	4829130.59	31.20	0.00
		Notes_Project_Buildings	x	0		41.50 a	17613938.31	4829151.21	41.50	0.00
							17613979.38	4829119.12	41.50	0.00
							17613988.34	4829130.59	41.50	0.00
							17613987.58	4829136.84	41.50	0.00
							17613950.02	4829166.19	41.50	0.00
		Notes_Project_Buildings	x	0		41.50 a	17613897.39	4829098.83	41.50	0.00
							17613938.46	4829066.75	41.50	0.00
							17613929.49	4829055.27	41.50	0.00
							17613923.25	4829054.50	41.50	0.00
							17613885.69	4829083.85	41.50	0.00
		Notes_Project_Buildings	x	0		47.50 a	17613904.86	4829087.54	47.50	0.00
							17613923.51	4829072.97	47.50	0.00
							17613917.10	4829064.76	47.50	0.00
							17613898.44	4829079.33	47.50	0.00
		Notes_Project_Buildings	x	0		47.50 a	17613957.49	4829154.90	47.50	0.00
							17613976.15	4829140.33	47.50	0.00
							17613969.73	4829132.12	47.50	0.00
							17613951.08	4829146.69	47.50	0.00
		Notes_Project_Buildings	x	0		11.15 a	17613856.28	4829099.27	11.15	0.00

Name	M.	ID	RB	Residents	Absorption	Height	Coordinates			
						Begin	x	y	z	Ground
						(m)	(m)	(m)	(m)	(m)
							17613871.79	4829119.14	11.15	0.00
							17613880.70	4829112.19	11.15	0.00
							17613865.18	4829092.32	11.15	0.00
		Notes_Project_Buildings	x	0		7.90 a	17613872.37	4829122.59	7.90	0.00
							17613887.88	4829142.47	7.90	0.00
							17613899.42	4829133.46	7.90	0.00
							17613883.90	4829113.59	7.90	0.00
		Notes_Project_Buildings	x	0		11.15 a	17613873.68	4829121.57	11.15	0.00
							17613889.20	4829141.44	11.15	0.00
							17613898.10	4829134.49	11.15	0.00
							17613882.59	4829114.61	11.15	0.00
		Notes_Project_Buildings	x	0		7.90 a	17613889.70	4829144.79	7.90	0.00
							17613905.22	4829164.67	7.90	0.00
							17613916.75	4829155.66	7.90	0.00
							17613901.24	4829135.79	7.90	0.00
		Notes_Project_Buildings	x	0		11.15 a	17613891.02	4829143.77	11.15	0.00
							17613906.53	4829163.64	11.15	0.00
							17613915.44	4829156.69	11.15	0.00
							17613899.92	4829136.81	11.15	0.00
		Notes_Project_Buildings	x	0		7.90 a	17613912.29	4829173.73	7.90	0.00
							17613931.65	4829198.52	7.90	0.00
							17613943.19	4829189.52	7.90	0.00
							17613923.82	4829164.72	7.90	0.00
		Notes_Project_Buildings	x	0		11.15 a	17613913.60	4829172.70	11.15	0.00
							17613932.96	4829197.50	11.15	0.00
							17613941.87	4829190.55	11.15	0.00
							17613922.51	4829165.75	11.15	0.00

3D Reflector

Name	M.	ID	Type	Attenuation	B	m	Height
				dB/100m	%	1/m	(m)

Geometry Absorption

Name	M.	ID	Type	Attenuation	B	m	Height	Coordinates			
				dB/100m	%	1/m	(m)	x	y	z	Ground
								(m)	(m)	(m)	(m)

Ground Absorption

Name	M.	ID	G
------	----	----	---

Geometry Absorption

Name	M.	ID	G	Coordinates	
				x	y
				(m)	(m)

Contour Lines

Geometry Contour Line

Name	M.	ID	OnlyPts	Height		Coordinates		
				Begin	End	x	y	z
				(m)	(m)	(m)	(m)	(m)