

LEGEND

Tree Inventory

Refer to Table 1 of report dated 2 November 2022 for tree inventory information. Trees greater than 10cm DBH on and within six metres of the subject property were included in the inventory.

Tree Removals

The removal of 42 trees is required to accommodate the proposed development as indicated with RED labels.

Tree Preservation

Preservation of one tree will be possible without the use of designated tree protection measures. Trees identified for preservation are indicated with GREEN labels.

Tree Label (GREEN), preservation recommended	
Tree Label (RED), removal required	
Tree Label (BLACK), has been removed	
Tree Label (ORANGE), removal recommended due to condition	
Minimum Tree Protection Zone (MAGENTA circle)	
Minimum Tree Protection Zone of tree to be removed (RED circle)	
Delinea (GREEN circle) for neighbouring trees	
Surveyed Tree	
Estimated Tree Location by KFCI	

Specifications for the Protection and Preservation of Existing Vegetation

The following notes are to be included on all tree preservation plans:

- All existing trees, which are to remain, shall be fully protected with hoarding to City Standard and shall be protected with approved tree protection measures and Segment Control Panels. To be satisfied prior to the start of the Community Services Department work, the site plan shall be approved by the Community Services Department. Groups of trees and other existing plantings to be protected, shall be treated in a like manner with hoarding around the entire diameter. Areas within the protective hoarding shall remain undisturbed and shall not be used for the storage of building materials or equipment.
- No rigging cables shall be wrapped around or installed in trees. Surplus soil, equipment, debris or materials shall not be placed over root systems of the trees within the protective fencing. No contaminants will be dumped or flushed where feeder roots of trees exist.
- The developer or his/her agents shall take every precaution necessary to prevent damage to trees or shrubs to be retained.
- Where limbs or portions of trees are removed to accommodate construction work, they will be removed carefully in accordance with accepted arboricultural practices.
- Where root systems of trees are exposed directly adjacent to or damaged by construction work, they shall be trimmed neatly, and the area backfilled with appropriate material to prevent desiccation.
- When necessary, the trees will be given an overall pruning to restore the balance between roots and top growth or to restore the appearance of the trees.
- Trees that have died or have been damaged beyond repair, shall be removed and replaced by the owner at the developer's own expense with trees of a size and species as approved by the Community Services Department.
- If grades around trees to be protected are likely to change, the owner shall be required to take such precautions as any welling, retaining walls and root feeding, to the satisfaction of the Community Services Department.

No.	Issue/Revisions	Date	By
1	Report Submission	2 Nov 2022	IB
1	Report Revision	9 Dec 2022	IB

Base Data: J.D. Barns Ltd. (top); Gender (Site Plan)

KUNTZ FORESTRY CONSULTING Inc.

146 Lakeshore Road West
PO Box 1287 Lakeshore W/PO
Oakville ON L6K 0B3
1.888.637.1871
e.counsil@kuntzforestry.ca
www.kuntzforestry.ca

Client
CRW 1 LP and CRW 2 LP
121 King Street West, Suite 200
Toronto, Ontario M5H 3T9

Property
2105, 2087, 2097, and 2077 Royal Windsor Drive
Mississauga, Ontario

Tree Inventory and Preservation Plan

Project P3438 Figure 1

Date 2 November 2022

Scale 1:250

