

St. Mark and St. Demiana Coptic Orthodox Church, 462 Falgarwood Drive Oakville, ON L6H 1N3



St. Mark and St. Demiana Coptic Orthodox Church, 462 Falgarwood Drive Oakville, ON L6H 1N3

R.J. Burnside & Associates Limited 292 Speedvale Ave. West, Unit 20 Guelph ON N1H 1C4 CANADA

May 2023 300044049.0000



# **Distribution List**

No. of Hard Copies	PDF	Email	Organization Name
-	Yes		-
-	Yes		-

# **Record of Revisions**

Revision	Date	Description	
0	April 2020	Re-Zoning Submission/Site Plan Approval	
1	December 2020	Second Submission	
2	January 2022	Third Resubmission	
3	May 2023	Fourth Resubmission	

#### R.J. Burnside & Associates Limited

**Report Prepared By:** 

Thom Rosborough, EIT

Engineering Assistant, Land Development TR:lam

**Report Reviewed By:** 

Steven Roorda, P.Eng. Vice President, Land Development



# **Table of Contents**

1.0	Intro	oduction and Background	1
	1.1	Objectives	1
	1.2	Site Description	1
	1.3	Background Information and Documentation	3
	1.4	Proposed Site Plan	3
2.0	Exis	sting Storm Drainage	6
	2.1	Drainage Conditions	6
	2.2	Soil Conditions	6
3.0	Prop	posed Site Grading	7
4.0	Stor	rmwater Management	8
	4.1	Design Criteria	8
	4.2	Pre-Development Surface Hydrology	8
	4.3	Post Development Surface Hydrology	11
		4.3.1 Post Development Catchments	11
		4.3.2 Stormwater Management Design	11
5.0	Was	stewater Servicing	18
	5.1	Design Criteria	18
	5.2	Wastewater Quantity	18
	5.3	Impact Assessment	18
	5.4	Proposed Sewage Treatment System	19
6.0	Wat	er Supply and Distribution	22
	6.1	Design Criteria	22
	6.2	Proposed Layout and Sizing	22
7.0	Eros	sion and Sediment Control	24
8.0	Sum	nmary Conclusion	25
		-	

# Tables

Table 1:	Pre-Development Catchment Parameters	8
Table 2:	Pre-Development Visual OTTHYMO Peak Flows	9
Table 3:	Post Development Catchment Parameters	11
Table 4:	Permanent Pool	11
Table 5:	Forebay Size	13
Table 6:	Extended Detention	13
Table 7:	SWM Facility Stage-Storage-Discharge	14
Table 8:	Post Development to Ninth Line	15
Table 9:	Maximum Daily Sanitary Sewage Flow	18
Table 10	Proposed Effluent Objectives	19

#### **Figures**

Figure 1:	Site Location Plan	2
Figure 2:	Proposed Site Plan – Phase 1	4
Figure 3:	Proposed Site Plan - Overall	5
Figure 4:	Pre-Development Drainage Area Plan	10
Figure 5:	Post-Development Storm Drainage Area Plan	12
Figure 6:	Stormwater Management Pond – Plan View	16
Figure 7:	Stormwater Management Pond – Section	17
Figure 8:	Proposed Sanitary Plan	21
Figure 9:	Proposed Watermain Layout	23

#### **Drawing List**

G1 Grading Plan

S1 Servicing Plan

ESC1 Erosion and Sediment Control Plan

# Appendices

Drawings

Appendix A Geotechnical Report

Appendix B Stormwater Management Calculations

Appendix C Watermain Calculations

#### Disclaimer

This document contains proprietary and confidential information. As such, it is for the sole use of the addressee and R.J. Burnside & Associates Limited, and proprietary information shall not be disclosed, in any manner, to a third party except by the express written permission of R.J. Burnside & Associates Limited. This document is deemed to be the intellectual property of R.J. Burnside & Associates Limited in accordance with Canadian copyright law.

### 1.0 Introduction and Background

R.J. Burnside & Associates Limited (Burnside) has been retained by St. Mark and St. Demiana Coptic Orthodox Church to complete a Functional Servicing and Stormwater Management Report (FSR) for a Church Development located at Ninth Line, Mississauga. This report will support applications for a Zoning By-law Amendment and Site Plan Approval by demonstrating that the subject lands can be serviced in accordance with applicable regulatory requirements and criteria.

#### 1.1 Objectives

The objectives of this report are to:

- Identify any applicable engineering constraints on the subject site.
- Verify the location of existing infrastructure both within and adjacent to the site.
- Confirm feasibility of on-site sanitary treatment.
- Assess and confirm that domestic and fire flow requirements are met for the supply and on-site distribution of municipal water.
- Evaluate options and constraints for stormwater management to:
  - Ensure post-development flows from the site are sufficiently controlled to pre-development levels.
  - Confirm adequate stormwater quality controls are provided.

#### 1.2 Site Description

The proposed St. Mark and St. Demiana Coptic Orthodox Church Development is located on Ninth Line in Mississauga, just south-east of Burnhamthorpe Road. The site is bordered by Ninth Line on the southwest property line and Highway 403 on the northeast property line. The neighboring property to the north has a storage building on site and the property to the south is currently vacant. The site is legally described as RCP 1542 Part of Lot 9, RP 43R37503, Part 6, 7 and 9, City of Mississauga, and is zoned as Employment (E2-93). The existing site is 3.93 ha in size and consists of a grassed area with a small portion of the site covered in gravel. The location plan in Figure 1 shows the property in the context of the surrounding area.



# **1.3 Background Information and Documentation**

The current report has been prepared in accordance with, and consideration of the information and recommendations provided in the following documents:

- City of Mississauga Development Requirements Section 2, January 2020.
- Public Works Design, Specifications & Procedures Manual Linear Infrastructure - Functional Servicing and Storm Water Management Report - Region of Peel, July 2009.
- Application User Guide for Pre-Application Meetings and Site Plan Approval.
- Topographic Plan of Survey of Part 9, Registrar's Compiled Plan 1542 by Stantec Geomatics Ltd., May 2019.
- Project Status Report DARC 19-164 W8, City of Mississauga, July 2019.
- Class Environmental Assessment Study Ninth Line (Regional Road 13) Transportation Corridor Improvement – Region of Halton, June 22, 2017.
- St. Mark and St. Demiana Church Parking Utilization Study Stantec Consulting Ltd., January 8th, 2020.
- Geotechnical Investigation Report CMT Engineering Inc., February 20, 2020.

# 1.4 Proposed Site Plan

The proposed development on the site has been separated into two phases. The first phase of development proposes a new church building 5,016 m<sup>2</sup> in size and accompanying at-grade parking spaces located on the eastern portion of the site, with a single entrance from Ninth Line located at the southern end of the site. The northern portion of the site will be utilized for a stormwater management (SWM) pond and an on-site sanitary wastewater treatment system.

Phase 2 will introduce additional parking spaces and a Community Centre replacing the previously constructed SWM pond and on-site sanitary treatment system as introduced within Phase 1. Phase 2 will be completed once municipal sanitary services are in place along Ninth Line. During Phase 2 additional detailed design will be completed. This report will concentrate only on Phase 1 of the proposed development. Refer to Figure 2 for the Phase 1 development and Figure 3 for the overall site plan with the proposed Phase 2 works.

As part of the proposed development, a portion of the existing site will be dedicated to the Halton Region for future road widening of Ninth Line. A total of 0.18 ha will be dedicated, resulting in a proposed development area of 3.75 ha.









Drawn	Checked	Date	Figure No.
TR	SR	23/05/10	
Scale 1:1250		Project No. 300044049	2





#### LEGEND



PROPERTY BOUNDARY PROPERTY SETBACK MTO SETBACK PHASE 1 - BORDER LINE POND LIMITS EXISTING WATERMAIN EXISTING DITCH EXISTING BELL ROAD WIDENING LANDS TO BE DEDICATED TO THE CITY PROPOSED STONE AREA PROPOSED LEACHING BED EXISTING BOREHOLE PROPOSED RETAINING WALL PROPOSED ADA PARKING PROPOSED 3:1 MAX GRADING PROPOSED CONCRETE CURB PROPOSED BIKE RACK PROPOSED TRANSFORMER PROPOSED GARBAGE STORAGE

0 25 50 75 Metres

# BURNSIDE

# St. MARK AND St. DEMIANA COPTIC ORTHODOX CHURCH

Figure Title

Client

NINTH LINE MISSISSAUGA

#### PROPOSED SITE PLAN - OVERALL

Drawn	Checked	Date	Figure No.
TR	SR	23/05/10	
Scale 1:1250		Project No. 300044049	3

100

# 2.0 Existing Storm Drainage

#### 2.1 Drainage Conditions

The existing site slopes from north to south with an approximate overall slope of 4 % across the site. There is an existing berm at the north-east side of the site that runs parallel to Highway 403. This berm is the high point within the site. A small portion of the site drains to the Highway 403 Right-of-Way (ROW), while the remainder of the site discharges towards the ditch that runs along the east side of the Ninth Line ROW. Flow that enters this ditch is conveyed under Ninth Line via a 400 mm CSP culvert.

#### 2.2 Soil Conditions

In February 2020, CMT Engineering Inc. completed a Geotechnical Investigation for the subject property, which can be found with Appendix A. Based on the preliminary geotechnical investigation, the native soils encountered on the site are generally considered to be suitable for supporting the proposed development. The soil stratigraphy was predominantly sandy clayey silt till. Based on the Geotechnical Investigation the site classification for seismic site response would be considered Site Class D (stiff soils).

As part of the preliminary geotechnical investigation, seven (7) boreholes were advanced to depths ranging from 4.6 to 7.6 m below grade. Boreholes 1, 5 and 6 were equipped with monitoring wells. The monitoring wells recorded groundwater at elevations ranging between 0.15 m and 4.27 m below grade. During the investigation accumulated groundwater was recorded within open BH2 and BH3, at which the groundwater was roughly 2.74 m and 4.72 m below existing grade, respectively.

# 3.0 Proposed Site Grading

The proposed site grading takes into consideration the following requirements and constraints:

- Conformance to the City of Mississauga's grading and drainage criteria.
- Optimization of required earthworks.
- Provision for adequate cover on proposed services.
- Provision for overland flow conveyance to the proposed SWM pond.
- Maintain a maximum ponding depth of 0.30 m within the parking lot.

The proposed grading plan is largely driven by the following site constraints:

- The highpoint within the site is adjacent to the Highway 403 ROW and results in considerably steep slopes within the site.
- The proposed parking lot and drive aisles are to slope towards the proposed SWM pond which, due to site plan constraints, is not located at the natural low point on the site.
- The proposed SWM pond is to discharge into the existing roadside ditch along Ninth Line, which drains towards the existing 400 mm CSP culvert crossing the road at an inlet invert of 178.26 m.

Based on the site constraints outlined above, the proposed grades within the drive aisles range from 0.50% to 5.00%. The proposed grading is shown on Drawing G1.

# 4.0 Stormwater Management

# 4.1 Design Criteria

Based on coordination with the City of Mississauga, the following criteria must be achieved through the stormwater management design for the site:

- Quantity Control: Control the 100-year post-development design storm flow to the 2year pre-development design storm flow.
- Quality Control: 80% TSS removal, Enhanced Protection Level (Level 1) quality control as specified in the Ministry of Environment's Stormwater Management Planning and Design Manual (2003).
- Water Balance: The 5 mm rainfall event shall be retained on site.
- Low Impact Development (LID) measures are required to be implemented.

# 4.2 Pre-Development Surface Hydrology

The existing site is delineated as two catchments, as demonstrated in Figure 4. Flows from Catchment 101 discharge to existing ditch along Ninth Line and flows from Catchment 102 are conveyed to the Highway 403 ROW. The peak flows discharged from the site under existing conditions have been calculated using the Visual OTTHYMO hydrologic modelling software. The following table summarizes the parameters for each catchment inputted into the model. The complete model results and supporting calculations are presented in Appendix B.

Outlet	Catchment	Area (ha)	SCS Curve Number	Time to Peak (hr)
Ninth Line	101	3.72	89.0	0.19
Highway 403	102	0.21	89.0	0.15*

	Table 1:	Pre-Develo	pment Cato	hment Pa	rameters
--	----------	------------	------------	----------	----------

\* Based on the City of Mississauga minimum time of concentration (Tc) of 15 minutes. Time to peak = 0.6xTc.

Using Ontario Soil Maps the native soils on the site are considered a mixture of Soil Groups C and D. The site is considered 50% Chinguacousy clay loam and 50% Oneida clay loam. From this and considering that the existing site is a mixture of grass and gravel, composite curve numbers were derived for each catchment. Appendix B contains further detail regarding the curve numbers and time to peaks for the site. The Visual OTTHYMO model was run using 4-hour Chicago storm distribution design storms for the 2, 5, 10, 25, 50 and 100-year design storm events. Table 2 summarizes the output from the model. Refer to Appendix B for the Visual OTTHYMO model output.

Decign Storm	Release Rate (L/s)			
Design Storm	Catchment 101	Catchment 102		
2-year	191	12		
5-year	314	20		
10-year	435	28		
25-year	535	35		
50-year	630	41		
100-year	730	47		

Table 2: Pre-Development Visual OTTHYMO Peak Flows

The flows from each catchment during each design storm will be used to determine the post development stormwater management plan. As per the City's quantity control criteria the target release rates from the site will be the 2-year pre-development flows.



# 4.3 Post Development Surface Hydrology

### 4.3.1 Post Development Catchments

The post development catchments have been delineated based on the proposed grading for the site. Under post development conditions the stormwater runoff from the entire site will drain towards Ninth Line. Flows from Catchment 201 will discharge uncontrolled to Ninth Line and flows from Catchment 202 will be directed to the stormwater management (SWM) Pond for attenuation prior to being discharged to the Ninth Line ditch. The proposed site imperviousness was determined based on the pervious and impervious areas shown on the proposed site plan (Figure 2). The following table summarizes the post development catchment parameters. Supporting calculations are included in Appendix B. The proposed catchments are shown on Figure 5.

Outlet	Catchment	Area (ha)	Percent Impervious	SCS Curve Number	Time to Peak (hr)
Ninth Lino	201*	0.42	28.0%	85.0	0.15
	202	3.50	56.3%	91.6	-

**Table 3: Post Development Catchment Parameters** 

\* Catchment drains uncontrolled from the site

#### 4.3.2 Stormwater Management Design

The stormwater management criteria for the site, as outlined above in Section 4.1, will be achieved through the use of a wet pond and an underground infiltration facility.

# 4.3.2.1 Quality Control

The SWM pond has been designed to provide Enhanced Protection water quality control. This level of quality control will be achieved through the permanent pool volume in the SWM pond, designed in accordance with Table 3.2 from the MOE Stormwater Management Planning and Design Manual (2003). Table 4 shows the permanent pool volume required to achieve the required quality control level.

#### Table 4: Permanent Pool

Storage Volume (m <sup>3</sup> /ha)	Volume Required (m <sup>3</sup> )	Volume Provided (m <sup>3</sup> )
154.6	541	676

As shown in the table above, the permanent pool volume provided in the pond exceeds the required volume. This volume is measured from the bottom of the pond (178.0 m) to the normal water level (NWL) for the pond which is set at 179.20 m. The plan view of the proposed pond is shown in Figure 6.



The other component of quality control in the pond is the forebay. The forebay is sized based on the greater of the settling length or dispersion length required based on the incoming flow. The forebay is sized to have a maximum allowable average flow velocity of 0.15 m/s. Forebay sizing calculations have been completed in accordance with the MOE Stormwater Management Planning and Design Manual. The following table outlines the forebay sizing requirements. Detailed calculations are included in Appendix B.

#### Table 5: Forebay Size

Inlat	Calculation	Calculation Design L:		.:W Dimensions		Provided Dimensions	
iniet	Method	(m <sup>3</sup> /s)	Ratio	Length (m)	Width (m)	Length (m)	Width (m)
East	Settling Length	0.013	2	9.3	4.6	26.0	13.0
	Dispersion Length	0.673	2	25.8	12.9	26.0	13.0

The design flow for the settling length is based on the extended detention release rate and the design flow for the dispersion length is based on the 10-year flow from the inletting sewer. The table above demonstrates that the size of the designed forebay exceeds the requirements for both settling length and dispersion length.

# 4.3.2.2 Extended Detention

The proposed pond has been designed to include erosion control in the form of extended detention. The required extended detention volume has been calculated based on the 25 mm storm event. Extended detention requirements are summarized in the table below.

#### Table 6: Extended Detention

Volume Required (m <sup>3</sup> )	Volume Provided (m <sup>3</sup> )		
493	713		

The extended detention volume will pond to a depth of 0.60 m above the NWL. The release rate from the pond will occur over a 24-hour period and will be released via a perforated extended detention riser that is connected to a maintenance hole structure via a reverse sloped pipe. The release rate from the structure will be controlled by an 80 mm diameter orifice plate. The preliminary schematic of the proposed outlet structure layout is shown in Figure 7.

#### 4.3.2.3 Quantity Control

Quantity control of the post development flows will be accomplished in the proposed SWM facility located in the southwest portion of the site. The proposed SWM facility is a wet pond with a drainage area of 3.50 ha and an average imperviousness of 56.3%. Post development catchment areas are shown in Figure 5. The calculations for the post development parameters are included in Appendix B.

#### St. Mark and St. Demiana Coptic Othodox Church

Functional Servicing and Stormwater Management Report - 3415 Ninth Line, Mississauga, ON May 2023

The Visual OTTHYMO hydrologic model was used to determine the post development flows and storage volumes required to meet the target flow rates. A 4-hour Chicago storm distribution using the City of Mississauga rainfall data was used to analyze the 2, 5, 10, 25, 50, and 100-year design storm events. Table 3 presents the catchment characteristics of each drainage area used in the Visual OTTHYMO hydrologic model.

The target release rates from the site will be the 2-year pre-development flow to the Ninth Line ditch, therefore the overall allowable flow from the site was determined to be 191 L/s.

Catchment 202 will be routed through the SWM pond while Catchment 201 will drain uncontrolled to the Ninth Line ditch. To meet the target flow rates, the combination of hydrographs from the SWM pond and the uncontrolled area results in the following stage-storage discharge characteristics in the SWM pond (refer to Table 4). The detailed Visual OTTHYMO model output is provided in Appendix B.

Design Storm	Outlet Flow (m³/s)	Storage Volume Required (m <sup>3</sup> )	Water Level Elevation (m)	
25 mm	0.009	493	179.8	
100-Year	0.082	1,694	180.42	

Table 7:	SWM Facility	y Stage-Storage-Discharge
----------	--------------	---------------------------

The SWM pond has a maximum storage volume of 2,218 m<sup>3</sup> at an elevation of 180.70 m. This is the maximum high-water level for the pond, which does not include the 0.3 m of freeboard provided between 180.70 m and 181.00 m. The pond provides a greater volume than required. The above noted stage-storage-discharge curve will be achieved through the proposed outlet control structure. The control structure includes the 80 mm extended detention outlet orifice plate and a 170 mm orifice plate to control flows up to the 100-year storm event. Preliminary outlet control calculations are provided in Appendix B. The preliminary schematic of the proposed outlet structure layout is shown in Figure 7.

Under emergency conditions, the pond will overflow into the roadside ditch along Ninth Line. The overflow will be controlled via a weir built into the side of the pond which will be designed as a part of detailed design.

Drainage from Catchment 202 will be captured in the on-site storm sewer system. Sewers have been sized for the 10-year design storm, as specified in the City's criteria. Stormwater discharged in the sewers will ultimately be conveyed to the SWM pond. However, to achieve the City's criteria of retaining the 5 mm event on-site, an infiltration system will be placed upstream of the SWM pond. This system will capture and infiltrate the 5 mm rain event. Detailed sizing and drawings from the infiltration system supplier will be provided as part of the detailed design.

Based on the proposed developable site area of 3.75 ha, with an average imperviousness of 54.2%, a storage volume of 101.4 m<sup>3</sup> is required to retain the 5 mm storm event on-site. Detailed calculations are provided in Appendix B.

During storms larger than the 5 mm event, stormwater will overflow from the infiltration system to the downstream sewers which then outlet into the forebay of the proposed SWM pond. During storms greater than the 10-year event, stormwater will be conveyed overland across the site and will discharge into the main cell of the SWM pond.

As shown in Table 3, Catchment 201 flows uncontrolled from the site. This uncontrolled flow has been accounted for when designing a stormwater management plan to ensure the allowable release rates were achieved. The flow from Catchment 201 is unable to be captured by the on-site storm sewer system due to restrictions associated with grading requirements to make the driveway in this area feasible. The flow from Catchment 201 will discharge directly to the Ninth Line ROW and into the roadside ditch. The following table outlines the post development flows to the Ninth Line outlet, considering the discharge from both Catchments 201 and 202.

Design Storm	Uncontrolled Flow – Catchment 201 (L/s) <sup>1</sup>	Release Rate from Pond – Catchment 202 (L/s) <sup>1</sup>	Total Release Rate (L/s) <sup>1</sup>	Allowable Release Rate (L/s) <sup>2</sup>
2-year	20	17	27	-
5-year	33	60	68	-
10-year	47	67	99	-
25-year	59	72	119	-
50-year	70	77	134	-
100-year	82	82	149	191

#### Table 8: Post Development to Ninth Line

Note: <sup>1</sup> Flow from the Visual OTTMYO model output. Refer to Appendix B for further details. <sup>2</sup> 2-Year pre-development flow to the Ninth Line Ditch (Catchment 101). Refer to Table 2.



# LEGEND



PROPERTY BOUNDARY PROPOSED POND LIMITS EXISTING DITCH CENTERLINE PROPOSED SPOT ELEVATION PROPOSED SLOPE TRANSITION PROPOSED STORM DRAIN PROPOSED STORM STRUCTURE ROAD WIDENING LANDS TO BE DEDICATED TO THE CITY PROPOSED STONE AREA PROPOSED RIPRAP OVERFLOW PROPOSED LEACHING BED EXISTING BOREHOLE PROPOSED 3:1 MAX GRADING



Client

# St. MARK AND St. DEMIANA COPTIC ORTHODOX CHURCH

Figure Title

NINTH LINE MISSISSAUGA

#### STORMWATER MANAGEMENT POND

Drawn	Checked	Date	Figure No.
TR	SR	23/05/10	•
Scale		Project No.	6
1:1250		300044049	

File: \\elmo\Shared Work Areas\044049 - Ninth Line Mississauga\07\_Figures\044049 - SWM FIG.dwg Date Plotted: May 10, 2023 - 10:27 /



**ORTHODOX CHURCH** 

Figure Title

# NINTH LINE MISSISSAUGA

# STORMWATER MANAGEMENT POND SECTION

Drawn	Checked	Date	Figure No.
TR	SR	23/05/10	
Scale		Project No.	· /
AS NOTED		300044049	_
			•

# 5.0 Wastewater Servicing

# 5.1 Design Criteria

The onsite sewage system design is based on both the requirements of Part 8 of the Ontario Building Code (OBC) and Ministry of the Environment, Conservation and Parks (MECP) Design Guidelines.

### 5.2 Wastewater Quantity

Daily design sanitary flows for the sewage system have been estimated using building floor plans provided to us, in conjunction with Table 8.2.1.3.B. of the OBC. The proposed development will consist of a church with a sanctuary accommodating up to 800 people, along with associated facilities and uses including administrative offices, a kitchen/cafeteria, and Sunday school classrooms. The lower level contains additional classrooms and office spaces to support church functions, as well as a gym and other activity spaces. The following table summarizes the total daily sanitary sewage flows for this facility.

	OBC Reference	Unit	OBC Flow/Unit	Number of Units	Total Daily Flow (L/day)	
Sunday						
Sanctuary	Churches with kitchen facilities	per seat	36	800	28,800	
Cafeteria	Food service operation, cafeteria	per meal	12	300	3,600	
Sunday School	Churches no kitchen facilities	per seat	8	200	1,600	
Total Daily Sewage Flow: 34,000 L/day						
Rounded Daily Sewage Design Flow: 36,000 L/da						

Table 9: Maximum Daily Sanitary Sewage Flow

The onsite sewage system has been sized to accommodate the estimated maximum daily flow of 36,000 L/day. Based on information provided to us, it is assumed that maximum uses of multiple facilities concurrently would be limited, and that this maximum flow rate is a conservative daily flow estimate, adequate to accommodate the maximum day of use at the facility in the future. We understand that some components of the building may be constructed in phases. During detailed design of the sewage system, options for phasing the construction of the sewage system can be reviewed and considered, as can other design optimization techniques such as flow balancing. For the purposes of this report, the intent is to demonstrate that the proposed building in its entirety can be serviced with the onsite system.

#### 5.3 Impact Assessment

The proposed sewage system must meet MECP requirements in terms of the level of treatment provided. A Hydrogeological Assessment (prepared under separate cover by

Burnside) has evaluated the site and the potential impact on both groundwater and surface resources from the proposed sewage system. In order to meet MECP requirements, we estimate that the sewage system will need to be capable of providing removal of nitrogen to an effluent concentration of approximately 5.4 mg/L or less.

Conventional septic systems do not provide nitrogen removal; therefore, an advanced wastewater treatment system with additional denitrification equipment will be required to provide sufficient nitrogen removal. Typically, this would include a two-stage process to remove nitrogen from the wastewater. The ammonia will be converted into nitrate in the aerobic treatment process, and then subsequently converted from nitrate to nitrogen gas in an anoxic reactor (i.e., lacking in dissolved oxygen) with a carbon source. The effluent from the anoxic reactor will then be polished and sent to the leaching bed for dispersal into the soil.

The proposed effluent objectives in treated wastewater for the proposed sewage treatment system are as follows:

Parameter	Units	Effluent Objective
Total Biochemical Oxygen Demand – 5 days (cBOD5)	mg/L	<10
Total Suspended Solids	mg/L	<10
Total Inorganic Nitrogen	mg/L	<5.4

#### Table 10: Proposed Effluent Objectives

# 5.4 Proposed Sewage Treatment System

Based on the results of the Hydrogeological Assessment it is our recommendation that the sewage system incorporate a treatment technology capable of Level IV effluent quality as defined by the Ontario Building Code (OBC), as well as supplementary equipment for denitrification to suitable levels. There are several packaged onsite wastewater treatment technologies that are capable of providing high quality treatment as required. The proposed sewage treatment system will in general consist of a septic or pre-settling tanks, a treatment unit for the treatment of organic matter and nitrification/denitrification and a subsurface leaching bed for disposal of treated effluent. Pumping elements will also be incorporated as required, depending on the location and configuration of the treatment tanks. The onsite sewage system will require regular ongoing maintenance and monitoring to ensure a properly functioning system. Specific requirements will be developed in consultation with the Ministry of the Environment, Conservation and Parks during the approval process.

As noted above the existing soil conditions consist of a sandy clayey silt till, which are not conducive to an in-ground leaching bed. Therefore, a fill based (i.e., raised) leaching bed will be required. A design T-time greater than 50 min/cm is assigned to the underlying soils.

#### St. Mark and St. Demiana Coptic Othodox Church

Functional Servicing and Stormwater Management Report - 3415 Ninth Line, Mississauga, ON May 2023

The use of an advanced treatment system meeting Level IV effluent quality will allow the use of a reduced size leaching bed as compared to a conventional septic system. The recommended leaching bed is a Type A Dispersal bed, which consists of a 200 mm stone layer protected by geotextile and underlain by a sand layer. The overall size of the bed is dictated by the hydraulic properties of the underlying soil, and the ability to infiltrate the treated effluent into the ground under the bed.

For preliminary sizing purposes, we have used the maximum day flow of 36,000 L/day in order to provide a conservative estimate of the footprint required.

The minimum stone area is calculated according to the following relationship for daily flows (Q) exceeding 3,000 L/day:

$$A_{stone} = Q/50$$

Therefore, for the design flow of 36,000 L/day, the minimum stone area required is 720  $m^2$ .

The T-time of the underlying soils is greater than 50 min/cm. The minimum sand area for underlying soil with a T-time that is greater than 15 min/cm is calculated according to the following formula:

A<sub>sand</sub> = QT/400 Where:

Q = daily design flow (L/day)

T = percolation rate (T-time) of underlying native soil

For the design flow of 36,000 L/day and a T-time of 50 min/cm, the minimum sand area required is 4,500 m<sup>2</sup>. This area represents the minimum total area required for the Type A Dispersal Bed based on the underlying soil properties and regulatory requirements. Figure 8 shows the preliminary layout of the sewage system.

As shown, the site has adequate space to accommodate a sewage treatment system for the proposed changes to the property and to meet all OBC setback distances. The leaching bed should be backfilled with porous material and topsoil to promote grass growth on the finished surface and must be protected from future vehicular traffic and parking. No construction vehicles may be permitted on the leaching bed after it has been constructed, therefore, development of the property will have to be carefully staged to protect this area.

Details of the type of treatment system, leaching bed design, and proposed phasing will be advanced during detailed design.



# 6.0 Water Supply and Distribution

# 6.1 Design Criteria

The following Region of Peel criteria have been applied in establishing the sizing of the watermain required to support the proposed institutional development:

- Average Day Per Capita Flow 140 L per capita per day.
- Maximum Day Factor peaking factor of 1.4.
- Peak Hour Factor peaking factor of 2.5.
- Fire Flow per Fire Underwriters Survey (FUS) requirements minimum non-fire pressure: 40 psi and minimum fire pressure: 20 psi.

# 6.2 Proposed Layout and Sizing

An existing 200 mm watermain is located on the west side of Ninth Line. In early 2019, the City of Mississauga and the Region of Peel modeled two development scenarios for the subject lands. Phase 1 of modeling was for the church and Phase 2 of modeling was for future uses. The modeling exercise determined that the existing 200 mm watermain on Ninth Line does not have sufficient capacity to service the Phase 1 maximum daily demand and fire flow. The Region of Peel design criteria states that a development of this size requires a connection to a minimum municipal watermain size of 300 mm. Therefore, the existing 200 mm watermain on Ninth Line will require an upgrade to a 300 mm watermain prior to servicing any phase of the proposed development. The results of the water modeling and assumed water demand calculations can be found in Appendix C. A proposed water service layout can be seen in Figure 9 and Drawing S1.





e: \\elimo\Shared Work Areas\044049 - Ninth Line Mississauga\07. Figures\044049 - PROPOSED WM.dwg Date Plotted: May 10. 2023 - 9:49 AM

# 7.0 Erosion and Sediment Control

During the site grading and servicing works, there is potential for sediment -runoff to be directed toward the adjoining properties and the municipal street. Therefore, prior to any grading activity, the erosion and sediment control strategies in accordance with the City of Mississauga (Erosion and Sediment Control Design Requirements (Section 2.08) and The Greater Golden Horseshoe Area Conservation Authorities (Erosion and Sediments Control Guidelines for Urban Construction) will be applied as follows:

- All activities on the site shall be conducted in a logical sequence to minimize the area of bare soil exposed at any one time.
- All disturbed ground left inactive shall be stabilized by seeding, sodding, mulching, or covering, or other equivalent control measure. The period of time of inactivity shall not exceed 30 days, unless otherwise authorized by the Commissioner of Transportation and Works.
- Temporary sediment basins shall be constructed on sites having a disturbed drainage area of greater than 2 ha or having an average slope greater than 12 %.
- Sediment control fences shall be placed along all downslope sides of a site along the edges of a drainage channel passing through the site, and along the perimeter of all other areas sensitive to sediment accumulation. The sediment control fence shall be constructed in accordance with City Standard Drawing No. 2940.010
- Catch basin sediment traps shall be provided for unpaved areas draining 2 ha or greater and less than 4 ha and shall be constructed in accordance with City Standard Drawing No. 2930.010.
- A minimum 3 m wide undisturbed buffer strip shall be maintained along the limits of the development adjacent to existing road boulevards. Where a sediment control fence is required, it shall be constructed in front of the buffer strip.
- All topsoil stockpiles containing more than 100 m3 of material shall be located a minimum of 10 m away from a roadway, drainage channel or an occupied residential lot. The maximum side slopes for topsoil stockpiles shall be 1.5 horizontal to 1.0 vertical.
- In order to reduce the tracking of mud onto a paved street, a pad of crushed stone shall be constructed at the site entrance and exit leading onto any existing road. The stone pad shall be a minimum of 300 mm thick, 15 m long and 10 m wide. The first 10 m from the entrance/exit shall be constructed with 50 mm clear stone. The remaining 5 m shall be constructed with 150 mm rip-rap. This stone pad must be maintained as required given the site conditions to ensure mud tracking is kept to a minimum. The Stone Pad Construction Entrance shall be constructed in accordance with City Standard Drawing No. 2970.010
- Rock check dams are to be installed in ditches and swales in accordance with City Standard Drawing No. 2980.010.

Erosion and Sediment control details are provided on drawing ESC1.

# 8.0 Summary Conclusion

The preceding report provides investigation of existing servicing capacities and a review of the proposed servicing for the proposed development at Ninth Line in Mississauga. The proposed servicing and grading address the requirements of the City of Mississauga. An external upgrade is required to the existing watermain on Ninth Line, no other upgrades to the existing external municipal infrastructure will be required.

This report addresses the servicing related requirements associated with the Zoning By-law Amendment and Site Plan Approval applications for the subject property. We therefore propose that the preceding Functional Servicing and Stormwater Management Report be accepted for review and approval by the City of Mississauga in order to facilitate the Planning Approvals for the subject property.



Drawings







2. ALL GRANULAR BASE AND SUB-BASE MATERIALS SHALL BE GRADED AND

PACTED TO 98% STANDARD PROCTOR DENSITY, FREE OF DEPRESSIONS

3. THE PAVEMENT STRUCTURE SHALL BE CONSTRUCTED OF THE MINIMUM THICKNESSES OF MATERIALS AS PER THE GEOTECHNICAL REPORT BY CM ENGINEERING INC. DATED FEBRUARY 20, 2020.

4. ALL BARRIER CURB WITHIN THE SITE TO BE CONSTRUCTED AS PER DETAIL ON DRAWING D1, UNLESS OTHERWISE SPECIFIED.

5. FROST SLABS ARE REQUIRED AT ALL DOOR LOCATIONS WHERE PROPOSED DUTSIDE GRADE IS FLUSH WITH FINISHED FLOOR ELEVATION.

6. REFER TO SITE PLAN FOR DIMENSIONS AND SITE DETAILS.

7. STEP JOINTS ARE TO BE USED WHERE PROPOSED ASPHALT MEETS EXISTING ASPHALT AS PER DETAIL ON DRAWING D1. ALL JOINTS MUST BE SEALED AS PER ASPHAL DETAIL.

8. TRANSITIONS WITHIN THE SUBGRADE WITHIN 1.2M FROM THE TOP OF PAVEMENT SHOULD INCLUDE 3H:1V TRANSITIONS AS PER DETAIL ON DRAWING D1.

9. EMBANKMENTS TO BE SLOPED AT MAX. 3:1. UNLESS OTHERWISE SPECIFIED.

10. ALL PAVEMENT MARKING, LINE PAINTING, DIRECTIONAL LINES/ARROWS ETC. SHALL BE PLACED IN ACCORDANCE WITH THE ARCHITECTURAL SITE PLAN OR THE OWNER'S TRAFFIC ENGINEERING CONSULTANT'S DRAWINGS.

11. THE CONTRACTOR SHALL PROVIDE TO THE ENGINEER 1 (ONE) SET OF AS CONSTRUCTED SITE SERVICING AND GRADING DRAWINGS.

2. SECTION A-A INCLUDED ON SEPARATE FIGURE ENTITLED "FIGURE STORMWATER MANAGEMENT POND SECTION".

LOT 9

PART 2

PIN 13413-0111(LT)

TORAGE FACILITY

PART 3 РАК I Э PLAN 43R-37503

-===

PIN 13413-

. . .

PART 8 PLAN 43R-37503

PART 1 PLAN 43R-3627

GENERAL NOTES:

1. ALL WORK SHALL BE CARRIED OUT IN COMPLIANCE WITH THE APPLICABLE HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECT

5. ROAD OCCUPANCY/ACCESS PERMIT MUST BE OBTAINED 48 HOURS PRIOR TO COMMENCING ANY WORKS WITHIN THE MUNICIPAL ROAD ALLOWANCE.







SCALE H1:500 V1:100









PROPERTYLINE 14.0m MTO SETBACK 187 187 186 186 185 185 EXISTING GRADE 184 184 183 183 182 182  $\rightarrow$ 181 181 PROPOSED GRADE 180 180 SECTION F-F SCALE H1:500 V1:100





hecked Date SR 23/05/10 Revision No. 0 **S1** CONTRACT NO.



Appendix A

**Geotechnical Report**
# **GEOTECHNICAL INVESTIGATION**

## PROPOSED CHURCH NINTH LINE MISSISSAUGA, ONTARIO

CMT Project 20-026.R01

H

**Prepared for:** 

St. Mark and St. Demiana Coptic Orthodox Church

February 20, 2020





CMT Engineering Inc. 1011 Industrial Crescent, Unit 1 St. Clements, Ontario NOB 2M0 Tel: 519-699-5775 Fax: 519-699-4664 www.cmtinc.net

February 20, 2020

20-026.R01

St. Mark and St. Demiana Coptic Orthodox Church The Diocese of Mississauga, Vancouver and Western Canada 2188 Robinwood Court Mississauga, Ontario L5M 5B9

Dear Sir/Madame:

## Re: Geotechnical Investigation Proposed Church Ninth Line, Mississauga

As requested, CMT Engineering Inc. conducted a geotechnical investigation at the above-referenced site, and we are pleased to present the enclosed report.

We trust that this information meets your present requirements and we thank you for allowing us to undertake this project. Should you have any questions, please do not hesitate to contact our office.

Yours truly,

Shawn Wheatley, M.Eng.

ks

1cc: R.J. Burnside and Associates Limited - Angela Mason

#### **TABLE OF CONTENTS**

#### 3.0 FIELD AND LABORATORY PROCEDURES ...... 1 4.1. 4.2. 4.3. Sand 4.4. 4.5. 4.6. 5.1. 5.2. 5.3. 5.4. 5.4.1. 5.4.2. 5.4.3. 5.5. 5.6. 5.7. Construction Dewatering Considerations ...... 15 5.8. 5.9. Chemical Testing was NOT Undertaken ...... 21 5.12.1. 5.12.2. 5.14. Radon Drawing 1 - Site Location Map Drawing 2 - Site Plan Showing Borehole Locations Appendix A - Borehole Logs Appendix B - Grain Size Analyses

Appendix C - Well Records

#### Page

#### 1.0 <u>INTRODUCTION</u>

The services of CMT Engineering Inc. (CMT Inc.) were retained by Ms. Angela Mason, M.Sc., P.Geo., of R.J. Burnside & Associates Limited, on behalf of the St. Mark and St. Demiana Coptic Orthodox Church, to conduct a geotechnical investigation for a proposed church building to be located at Ninth Line in Mississauga, Ontario. The geotechnical investigation was carried out in conjunction with a hydrogeology study completed by R.J. Burnside & Associates Limited, which will be provided under separate cover. The location of the site is shown on Drawing 1.

The purpose of the geotechnical investigation was to assess the existing soil and groundwater conditions encountered in the boreholes. Included in the assessment are the soil classification and groundwater observations, as well as comments and recommendations regarding geotechnical resistance (bearing capacity); serviceability limit states (anticipated settlement); dewatering considerations; site classification for seismic site response; recommendations for site grading, site servicing, excavations and backfilling, recommendations for slab-on-grade construction; pavement design/drainage; soil design properties; storm water infiltration, and a summary of the laboratory results.

#### 2.0 EXISTING SITE CONDITIONS

The site is currently primarily used for agricultural crop production. An unpaved parking area and temporary work/storage area for lumber currently exists at the east side of the property. The site has undulating topography, with a range in elevation of approximately 4.5 m across the borehole locations. The site is bounded by Ninth Line to the south, Highway 403 to the north, a commercial storage facility to the west, and vacant land to the east.

#### 3.0 FIELD AND LABORATORY PROCEDURES

Prior to the commencement of the field drilling program, ON1Call locates were organized by CMT Inc. to ensure that underground utilities would not be damaged.

The field investigation was conducted on February 10 and February 12, 2020, and comprised the advancement of seven (7) boreholes (referenced as Boreholes 1 to 7), utilizing a Geoprobe 7822DT drillrig operated by employees of CMT Drilling Inc.

The borehole depths ranged from approximately 4.57 m (15.0 ft) to 7.62 m (25.0 ft) below the existing ground surface elevations as directed by R.J. Burnside & Associates Limited. Standard penetration testing (SPT) and sampling was carried out in all boreholes using 38 mm inside diameter split spoon sampling equipment and an automatic hammer, in accordance with ASTM D 1586 "Standard Test Method for Standard Penetration Test (SPT) and Split-Barrel Sampling of Soils". SPT soil sampling was generally conducted at 0.76 m (2.5 ft) intervals to approximately 3.0 m (10.0 ft) and about every 1.52 m (5.0 ft) thereafter to borehole termination. Macro core (MC5) soil sampling was conducted between the deeper SPT samples in the majority of the

boreholes. Technical staff from CMT Inc. observed the drilling operation and collected and logged the recovered soil samples. A small portion of each sample was placed in a sealed, marked jar for moisture content determinations.

As requested, representative samples from the following boreholes and depths were submitted to our laboratory for grain size analyses:

- Borehole 1 approximate depth 0.76 m to 1.37 m (2.5 ft to 4.5 ft)
- Borehole 2 approximate depth 1.52 m to 2.13 m (5.0 ft to 7.0 ft)
- Borehole 4 approximate depth 3.66 m to 4.57 m (12.0 ft to 15.0 ft)
- Borehole 6 approximate depth 3.05 m to 3.66 m (10.0 ft to 12.0 ft)

The borehole logs are provided in Appendix A and the resulting grain size analyses can be found in Appendix B.

CMT Inc. may be contacted for additional laboratory testing on samples should it be required. Samples are typically kept for three months, unless other arrangements are made.

Boreholes 1, 5 and 6 were equipped with 50 mm diameter PVC monitoring wells comprising a 1.5 m long prepacked screen backfilled with #2 sand filter and then riser pipe, backfilled with bentonite. The monitoring wells were installed according with the Ontario Water Resources Act, Regulation 903 (O.Reg. 903) by well technicians licensed by the Ministry of the Environment, Conservation and Parks (MECP), working for a contractor also licensed by the MECP. The monitoring wells are registered with the MECP and must be decommissioned in accordance with O.Reg. 903 prior to future construction. The well log records are provided in Appendix C.

CMT Inc. surveyed the ground surface elevations at the borehole locations (using laser survey equipment) on February 12, 2020. A geodetic monument, located immediately west of the intersection of Ninth Line and Burnhamthorpe Road, was used as a benchmark with a reported elevation of 181.90 m above sea level. The ground surface elevations at the borehole locations ranged from about 177.84 m to 182.49 m. The locations of the boreholes are shown on Drawing 2.

## 4.0 <u>SUBSOIL CONDITIONS</u>

The soils encountered in the boreholes are described briefly below and a more detailed stratigraphic description is provided on the borehole logs in Appendix A. The following paragraphs have been simplified into terms of major soil strata. The soil boundaries indicated have been inferred from non-continuous samples and observations of sampling and drilling resistance and typically represent transitions from one soil type to another rather than exact planes of geological change. Further, the subsurface conditions are anticipated to vary between and beyond the borehole locations.

## 4.1. <u>Topsoil</u>

Very loose to loose, dark brown, silty, organic topsoil was encountered at the surface of all boreholes. The topsoil was considered to be in a moist state. The topsoil ranged in thickness from approximately 50 mm to 120 mm (average 90 mm) at the borehole locations. Given the variation in topsoil thicknesses at the borehole locations, and the undulating nature of the topography, some variance in the topsoil thickness should be expected outside of the sampled areas. It would be expected that topsoil thicknesses would be thinner on the hill tops, with more significant accumulation expected in the low-lying areas. Materials designated as topsoil in this report were classified based solely on visual and textural evidence. Testing of organic content or for other nutrients was not carried out. Therefore, materials classified herein as topsoil cannot necessarily be relied upon for support and growth of landscaping vegetation without supplemental soil nutrient analyses.

## 4.2. <u>Clayey Silt</u>

Brown to grey, clayey silt, clay and silt, or clayey sandy silt, with some sand and up to some gravel, was encountered underlying the topsoil in all boreholes. The clayey silt immediately underlying the topsoil was observed to be mottled red, brown and dark brown, and contained trace amounts of organic material from root structures. The clayey silt was considered to be very soft to hard, with SPT N-values ranging from 1 to in excess of 100 blows per 0.3 m (average 28 blows per 0.3 m). Typically, the soft to firm clayey silt was encountered directly underlying the topsoil. It is expected that this material has become loosened/soft from frost action and may require further inspection and remedial action (further compactive effort) at the time of construction, if it will be intended to be utilized during site grading. The clayey silt was considered to be moist, with moisture contents ranging from about 8.5% to 29.9% (average 14.5%).

## 4.3. <u>Sand</u>

Brown to grey sand with trace to some gravel and silt, and up to trace amounts of clay was encountered underlying the clayey silt in Boreholes 1 and 6, underlying the silt till in Borehole 2, and underlying the sandy clayey silt till in Boreholes 1 and 6. The sand was considered to be dense to very dense, with SPT N-values ranging from 44 to in excess of 100 blows per 0.3 m (average 72 blows per 0.3 m). The sand was considered to be moist to wet, with moisture contents ranging from about 10.0% to 20.9% (average 17.7%).

## 4.4. Sandy Clayey Silt Till

Brown to grey sandy clayey silt till with trace to some gravel was encountered underlying the sand in Borehole 1, underlying the silt till in Boreholes 3 and 6, as well as underlying the clayey silt in Boreholes 4 and 5. The sandy clayey silt till was considered to be dense

to very dense, with SPT N-values ranging from 36 to in excess of 100 blows per 0.3 m (average 66 blows per 0.3 m). The sandy clayey silt till was observed to be moist to wet, with moisture contents ranging from about 9.4% to 13.8% (average 11.1%).

## 4.5. <u>Silt Till</u>

Brown to grey silt till with some sand and clay, and up to trace amounts of gravel was encountered underlying the clayey silt in Boreholes 2, 3 and 7, underlying the sandy clayey silt till in Boreholes 4 and 5, as well as underlying the sand in Borehole 6. The silt till was considered to be compact to very dense, with SPT N-values ranging from 28 to in excess of 100 blows per 0.3 m (average 67 blows per 0.3 m). The sandy clayey silt till was observed to be moist to wet, with moisture contents ranging from about 7.6% to 24.4% (average 12.5%).

## 4.6. <u>Groundwater</u>

Boreholes 1, 5 and 6 were equipped with monitoring wells. The monitoring wells were installed and registered in accordance with the Ontario Water Resources Act, Regulation 903 (O.Reg. 903) by well technicians licensed by the Ministry of the Environment (MOE), working for a contractor also licensed by the MOE. The boreholes that were not instrumented with a monitoring well were backfilled with bentonite in accordance with O.Reg. 903.

CMT Engineering Inc. staff measured the water levels in the wells on February 12, 2020. The following table summarizes the borehole number, ground surface elevation, elevation of water in the monitoring well upon completion of drilling, cave elevation, and the bottom of borehole elevation for each borehole:

Borehole No.	Ground Surface Elevation (m)	Measured Elevation of Water in Monitoring Well February 12, 2020 (m)	Measured Elevation of Water in Open Borehole (m)	Cave Elevation (m)	Bottom of Borehole Elevation (m)
1	179.66	177.92	1		172.04
2	179.52		176.78	176.47	174.95
3	180.13		175.41	175.10	174.95
4	182.49			177.82	177.31
5	177.84	177.69			171.74

Borehole No.	Ground Surface Elevation (m)	Measured Elevation of Water in Monitoring Well February 12, 2020 (m)	Measured Elevation of Water in Open Borehole (m)	Cave Elevation (m)	Bottom of Borehole Elevation (m)
6	181.68	177.41			174.06
7	179.02				173.84

It should be noted that the hard and/or fine-grained, less permeable clayey silt, sandy clayey silt till, and silt till soils have the potential to create perched water conditions. Groundwater conditions are generally dependent on the amount of precipitation, control of surface water, as well as the time of year, and can fluctuate significantly in elevation and volume. As such, provisions for site dewatering should be part of the site development and construction process. Recommendations with respect to dewatering conditions are provided in Section 5.8 of this report.

## 5.0 DISCUSSION AND RECOMMENDATIONS

This section of the report provides CMT Inc.'s interpretation of the factual geotechnical data obtained during the investigation and is intended for the guidance of the owner and design engineer. Where comments are made on construction, they are provided only to highlight those aspects which could affect the design of the project. Contractors bidding on or undertaking the work should make their own independent interpretation of the factual subsurface information provided as it affects their proposed construction means and methods, equipment selection, scheduling, pricing, and the like.

Utilizing the information gathered during the geotechnical investigation and assuming that the borehole information is representative of the subsoil conditions throughout the site, the following comments and recommendations are provided.

## 5.1. Serviceability and Ultimate Limit Pressure

Based on the information obtained from the boreholes, the following table provides the estimated geotechnical reaction at the Serviceability Limit States (SLS) and factored geotechnical resistance Ultimate Limit States (ULS) pressures at the various elevations, including soil types:

Borehole No.	Ground Surface Elevation (m)	SLS kPa (psf)	ULS kPa (psf)	Estimated Highest Founding Elevation (m)	Depth to Highest Founding Elevation (m)	Soil Type
1	179.66	150 (3,000)	225 (4,500)	178.90 to 172.04 (termination)	0.76	Clay and Silt/Sand/Sandy Clayey Silt Till
2	179.52	150 (3,000)	225 (4,500)	178.00 to 174.95 (termination)	1.52	Clayey Sandy Silt/Silt Till/Sand
3	180.13	150 (3,000)	225 (4,500)	179.37 to 174.95 (termination)	0.76	Clayey Silt/Silt Till/Sandy Clayey Silt Till
4	182.49	150 (3,000)	225 (4,500)	181.73 to 177.31 (termination)	0.76	Clayey Silt/Sandy Clayey Silt Till/ Silt Till
5	177.84	150 (3,000)	225 (4,500)	177.08 to 171.74 (termination)	0.76	Clayey Silt/Sandy Clayey Silt Till/Silt Till
6	181.68	150 (3,000)	225 (4,500)	180.92 to 174.06 (termination)	0.76	Clayey Silt/Sand/Silt Till/Sandy Clayey Silt Till
7	179.02	150 (3,000)	225 (4,500)	178.26 to 173.84 (termination)	0.76	Clayey Silt/Silt Till

Should footings be designed to be constructed at elevations higher than the elevations indicated in the table above, then structural fill will be required in order to achieve the design grades for the proposed foundations. The serviceability limit pressure for structural fill placed and compacted in accordance with Section 5.4.3 of this report and constructed on approved competent native soils is estimated to be at least 150 kPa (3,000 psf) at SLS and 225 kPa (4,500 psf) at ULS. Alternatively, footings could be stepped down to bear on approved undisturbed founding soils.

Footings may be placed at a higher elevation relative to another footing provided that the slope between the outside face of the footings is separated by a minimum slope of 10 horizontal to 7 vertical (10H:7V) with an imaginary line projected from the underside of the footings. This must be taken into account for any deep structures such as sump pits.

With respect to the Serviceability Limit State (SLS), the total and differential footing settlements are not expected to exceed the generally acceptable limits of 25 mm (1") and 19 mm (3/4") respectively.

All exterior footings must be provided with a minimum of 1.2 m of soil cover or equivalent thermal insulation (sufficient thermal insulation is required to protect all footings and slab-on-grades during construction until such a time that the structure is heated) in order to provide protection from frost action.

It should be noted that the native soils that exist at or below founding elevations may be in a wet/saturated state and may be too wet to provide suitable bearing for foundations without construction of a mud mat or granular drainage layer. It is imperative that the subgrade soils be inspected and approved by competent geotechnical personnel to ensure that the founding soils are suitable for bearing. Dewatering during construction may be required (see Section 5.8 of this report), along with the potential construction of a mud mat or granular drainage layer.

At the time of investigation, the proposed founding elevations were not available. CMT Inc. would be pleased to review design drawings when they become available and provide further recommendations with respect to bearing and foundation elevations.

## 5.2. Seismic Site Classification

The site classification for seismic response in Table 4.1.8.4 of the 2012 Ontario Building Code relates to the average properties of the upper 30 m of strata. The information obtained in the geotechnical field investigation was gathered from the upper 4.57 m to 7.62 m of strata. Based on the information gathered in the geotechnical field investigation, the site classification for seismic site response would be considered Site Class D (stiff soils) for structures founded on the native soils at the recommended founding elevations provided in Section 5.1 of this report. For foundations constructed on structural fill, placed in accordance with Section 5.4.3 of this report, the site classification for seismic site response D (stiff soil). The structural engineer responsible for the design of the structure should review the earthquake loads and effects.

#### 5.3. Soil Design Parameters

The following table provides the estimated soil design parameters for imported granular fill, as well as the native soils encountered on-site.

Soil Type	Soil Density (kg/m <sup>3</sup> )	Friction Angle (Degree)	Coefficient of Active Pressure (K <sub>a</sub> )	Coefficient of Passive Pressure (K <sub>p</sub> )	Coefficient of At-Rest Pressure (K <sub>0</sub> )	Coefficient of Friction (µ)	Cohesion (kPa)
Imported Gran 'A'/Gran 'B' (OPSS 1010)	2,100	34°	0.28	3.54	0.44	0.45	0
Clayey Silt	1,850	30°	0.33	3.00	0.50	0.38	10
Sand	1,800	33°	0.29	3.39	0.46	0.43	0
Sandy Clayey Silt Till	1,850	32 °	0.31	3.25	0.41	0.41	5
Silt Till	1,900	33°	0.29	3.39	0.46	0.43	0

The estimated soil design parameters can be utilized for the design of perimeter shoring, foundations and retaining walls, as required:

#### 5.4. Site Preparation

The site preparation for the proposed church is anticipated to include topsoil stripping, vegetation grubbing, the subexcavation of all relatively loose/soft native soils deemed not capable of supporting the design bearing capacity, the removal or relocation of any existing services (field tiles), followed by the placement of structural fill (as required) and site grading to achieve proposed grades.

#### 5.4.1. Topsoil Stripping/Vegetation Grubbing

Due to the undulating topography and erosion, it should be expected that the thickness of topsoil may vary significantly throughout the site.

All existing topsoil, vegetation (including tree roots and all loose/disturbed soils associated with tree roots) must be removed from within the proposed building envelopes, driveways and parking lots to expose approved competent subgrade soils. The topsoil may be used in landscaped areas where some settlement can be tolerated; otherwise, it should be properly disposed of off-site.

Swelling and shrinkage factors of topsoil during site grading operations is generally relative to the insitu density and moisture content at the time of construction, as well as the type of equipment utilized and the compactive effort that the topsoil is subjected to during stockpiling and the subsequent placement during the final grading process. When topsoil is stripped and then placed in stockpiles with heavy earthmoving equipment such as motor scrapers or rock trucks and bulldozers, it tends to compact considerably in the stockpile. As previously indicated, the amount of compaction is generally relative to the weight of the equipment utilized, the number of passes that the equipment makes over the stockpiled topsoil, as well as the moisture content of the topsoil at the time of construction. Therefore, the swelling and shrinkage factors can vary significantly. Determination of swelling and shrinkage factors would require considerable laboratory testing throughout the construction process in order to provide an average that may be considered reasonable for quantity calculations. A frequently used practice to determine stripped quantities of topsoil would be to do a topographic survey prior to and following the stripping process. Due to the typical relatively loose insitu state of the topsoil, it should be expected that compacted volumes (when the topsoil is put back down) will be considerably less (again relative to the type and weight of equipment, the number of passes and the moisture content at the time of construction) than in the insitu state.

The volume of topsoil removed during the stripping process is also relative to the equipment utilized for the stripping process as well as the moisture conditions at the time of stripping. If an excavator with a smooth bucket is utilized for stripping, there would generally be less potential for topsoil to become intermixed with the underlying relatively loose subsoil and therefore less concern of over-excavation to remove all topsoil. If the topsoil is stripped with wheeled equipment or bulldozers, then there is an increased potential for the topsoil and subsoil to become intermixed, subsequently requiring additional excavation to remove all topsoil. This is further influenced by rutting which can occur during wet conditions.

It should also be noted that the clayey silt soils that were encountered directly underlying the topsoil are likely in a soft to firm state and may not be suitable to support foundations in their current state. As such, the upper clayey silt soils may require reworking with further compactive effort; otherwise these soils will require subexcavation to expose competent approved native mineral soils. This material will also be subjected to significant volume changes during the construction process.

## 5.4.2. Removal/Relocation of Existing Services

Any existing tile drains (field tiles or municipal tile drains) that may be located within the proposed building envelopes, driveways or parking lots must be completely removed to a minimum distance of 15.0 m (50.0 ft) outside of the construction envelopes. All drains that are terminated must be completely sealed with concrete or grout at termination points to prevent the migration of soils into pipe voids which may result in potential settlement. Ideally, depending on flow direction, any existing tile drains (if present) should be redirected and reconnected outside of the building envelopes in order to maintain flow and prevent subsurface

accumulation of water. It may be prudent (if feasible) to incorporate existing field tiles into the storm sewer system or a separate collection system, to assist in systematically draining the subsurface soils in the church building. All existing trench backfill material associated with the drains must be subexcavated and the subsequent excavation must be backfilled with approved soils placed in accordance with Section 5.4.3 of this report. The location of existing field tiles is commonly identified by lines of buried topsoil within the subgrade soils and/or water boiling out of the ground following excavation. The field tiles are historically installed at 15.0 m (50.0 ft) intervals, however this can vary from site to site.

The monitoring wells that have been installed as a part of this investigation can be decommissioned by an MECP licensed well contractor with a Class 1, Class 2 or Class 3 license in accordance with Reg. 903.

## 5.4.3. Site Grading

Currently, there are no design grades available. However, based on the existing grades and topography, it is expected that significant cut and fill operations will be required to achieve the final design elevations across the site.

Following stripping of the topsoil, the removal of all trees roots (including all relatively loose soils associated with the tree roots), as well as the subexcavation of any relatively soft native soils deemed unsuitable of supporting the design bearing capacity, the exposed subgrade must be proof-rolled, and any soft or unstable areas must be further subexcavated and replaced with approved fill materials. Any fill materials required to achieve the design site grades should be placed according to the following procedures:

- Should the native subgrade soils at the design founding elevation in the proposed building envelope comprise wet or saturated soils, as was observed in some of the boreholes, then a granular drainage layer, constructed in accordance with Section 9.14.4 of the current Ontario Building Code (OBC) may be required. Alternatively, a lean mix concrete mud mat may be poured overlying the subgrade soils to provide a stable base;
- Prior to placement of any structural fill or bulk fill, the subgrade for the proposed buildings, driveways and roads must be prepared large enough to accommodate a 1:1 slope commencing a distance of 1.0 m beyond the outside edge of the proposed foundation and pavement/concrete edge down to the approved competent founding soils;

- Soils approved for use as structural fill must be placed in loose lifts not exceeding 0.3 m (12") in depth for granular soils (recommended fill material) and 0.2 m (8") in depth for silts and clays, or the capacity of the compactor (whichever is less);
- Imported granular fill materials (OPSS 1010 Type III Granular 'B' recommended for this application) can be compacted utilizing adequate heavy vibratory smooth drum compaction equipment;
- Fine-grained silt and clay soils (not recommended) must be compacted utilizing adequate heavy padfoot vibratory compaction equipment;
- Approved fill materials must be at suitable moisture contents to achieve the specified compaction. The wet to saturated soils encountered in the boreholes would generally be considered difficult for use as structural fill as they would require extensive air-drying in order to achieve the specified density. Soil moisture will also be dependent on weather conditions at the time of construction. Granular soils may require the addition of water in order to achieve the specified compaction;
- Approved structural fill materials that will support structures (including foundations, interior slab-on-grades, sidewalks, large expansive exterior slabs) must be compacted to a minimum of 98% standard Proctor maximum dry density (SPMDD);
- Approved bulk fill (exterior foundation wall backfill in landscaped areas, bulk fill for roadway (including sidewalk subgrade) and driveways) must be compacted to a minimum 95% SPMDD;
- Granular 'B' subbase and Granular 'A' base materials for the roads and driveways must be compacted to 100% SPMDD;
- It is recommended that compactive effort be applied to bulk fill in landscaped areas in order to reduce the effects of long-term settlement.

Based on the subsurface conditions observed in the boreholes, wet soils may be encountered, depending on the depth of excavation. As such, for soils excavated from the zone of saturation, significant air-drying along with working of the soils may be required in order to achieve the specified compaction of 98% SPMDD for structural fill and 95% SPMDD for bulk fill for the parking lot and driveways. Utilizing the existing soils during site grading may be more achievable if work is completed during the generally drier summer months. Reuse of excavated soils on-site will be subject to approval from qualified geotechnical personnel.

It should also be noted that the native soils encountered in the lower zone of the boreholes typically became very dense/hard with depth (SPT N-values in excess of 50 blows per 0.3 m) and may prove difficult to excavate with conventional excavating equipment. It is imperative that if the very dense/hard soils are utilized as fill, the material must be broken down (pulverized) to minimize void space and reduce the potential for settlement. Problems associated with compacting very dense/hard soils include the potential for long-term settlement due to excessive void space caused by the generally blocky structure of the excavated soils. As such, the very dense, blocky material must <u>not</u> be used as structural fill. The contractor must have equipment on-site that can effectively break down (pulverize) the very dense excavated soil into workable sizes (as required). Backfilling utilizing this material must be performed in thin lifts with considerable compactive effort applied, thereby reducing the void space and minimizing long-term settlement. This process could be difficult and time-consuming.

## 5.5. <u>Foundation Subgrade Preparation</u>

The native soils encountered in the boreholes are sensitive to changes in moisture content and can become loose/soft if the soils are subjected to additional water or precipitation, as well as severe drying conditions. The native subgrade soils could also be easily disturbed if traveled on during construction. Once they become disturbed, they are no longer considered adequate for the support of shallow foundations. To ensure and protect the integrity of the founding soils during construction operations, the following is recommended:

- During construction, the subgrade should be sloped or ditched to a sump located outside the building footprint in the excavation to promote surface drainage of rainwater or seepage and the collected water should be pumped out of the excavation. The environmental consultant must be consulted prior to any on-site water being pumped and/or discharged to municipal outlets to ensure that proper procedures are followed. It is critical that all water be controlled (not allowed to pond) and that the subgrade and foundation preparation commence in dry conditions;
- Should the native subgrade soils at the design founding elevation in the proposed building envelope(s) comprise saturated soils, as was observed in some of the boreholes, then a granular drainage layer, constructed in accordance with Section 9.14.4 of the current Ontario Building Code (OBC) may be required;
- Construction equipment travel and foot traffic on the founding soils should be minimized;

- If construction is to be undertaken during subzero weather conditions, the founding native soils and any potential fill materials must be maintained above freezing;
- Prior to pouring concrete for the foundations, the founding soils must be cleaned of all disturbed or caved materials;
- The foundation formwork and concrete should be installed as soon as practical following the excavation, inspection and approval of the founding soils. The longer that the excavated soils remain open to weather conditions and groundwater seepage, the greater the potential for construction problems to occur;
- If it is expected that the founding soils will be left open to exposure for an extended period of time, it is recommended that a 75 mm concrete mud slab be poured in order to protect the structural integrity of the founding soils.

## 5.6. <u>Slab-on-Grade/Modulus of Subgrade Reaction</u>

Prior to the placement of the granular base for the slab-on-grade construction, the subgrade soils should be proof-rolled. Any soft or weak zones, as well as any potential unsuitable fill in the subgrade (field tile trenches), should be subexcavated and backfilled with approved fill materials (see Section 5.4.3 of this report).

The following table provides the estimated modulus of subgrade reaction (k) for imported granular fill, as well as the native soils encountered on-site:

Soil Type	Modulus of Subgrade Reaction (k)
Imported Sand and Gravel (OPSS 1010)	81,000 kN/m <sup>3</sup> (300 lb/in <sup>3</sup> )
Clayey silt	40,000 kN/m <sup>3</sup> (150 lb/in <sup>3</sup> )
Sand	40,000 kN/m <sup>3</sup> (150 lb/in <sup>3</sup> )
Sandy Clayey Silt Till	47,000 kN/m <sup>3</sup> (175 lb/in <sup>3</sup> )
Silt Till	47,000 kN/m <sup>3</sup> (175 lb/in <sup>3</sup> )

In dry conditions, the floor slab can be founded on a minimum thickness of 150 mm (6") of Granular 'A' (OPSS 1010) and compacted to 100% SPMDD. Alternatively (particularly in wet conditions), 150 mm (6") of 19 mm clear crushed stone (OPSS 1004) should be used instead of Granular 'A'. Compactive effort should be utilized to consolidate the clear stone.

It is recommended that areas of extensive exterior slab-on-grade (sidewalks, accessibility ramps and exterior stairs) be constructed with a Granular 'B' subbase (450 mm) and a Granular 'A' base (150 mm), as well as incorporating subdrains, to provide rapid drainage and reduce the effects of frost heaving. This is particularly critical at barrier-free access points. Alternatively, a structural frost slab or thermal insulation could be designed and constructed at door entrances.

## 5.7. <u>Excavations</u>

All excavations must be carried out in accordance with Ontario Regulation 213/91 (Reg 213/91) of the Occupational Health and Safety Act and Regulations for Construction Projects.

**Type 2 Soils** - In general, the hard or very dense native clayey silt, silt till, and sandy clayey silt till encountered in a drained state (not wet or saturated), would be classified as Type 2 soils under Reg 213/91. The Type 2 soils must be sloped to within 1.2 m of its bottom with a slope having a minimum gradient of 1 horizontal to 1 vertical. Soils underlain by Type 3 or Type 4 soils that are exposed in the excavation must be treated accordingly as Type 3 or Type 4 soils (see below). Soils in a saturated condition (if encountered) must be treated as Type 4 soils, addressed below.

**Type 3 Soils** - In general, the native sand, and any fill soils encountered in a drained state (not wet or saturated), would be classified as Type 3 soils under Reg 213/91. The Type 3 soils must be sloped from the bottom of the excavation at a minimum gradient of 1 horizontal to 1 vertical. All saturated soils encountered must be treated as Type 4 soils, as described below.

<u>**Type 4 Soils</u>** - In general, any wet to saturated soils would be classified as Type 4 soils under Reg 213/91. Type 4 soils must be sloped from the bottom of the excavation at a minimum gradient of 3 horizontal to 1 vertical.</u>

If it is not practical to excavate according to the above requirements, then a trench support system (designed in accordance with the Ontario Health and Safety Act Regulations) may be utilized. When using a temporary trench support system consisting of trench boxes to reduce the lateral extent of the excavations, it should be noted that the support system is intended primarily to protect workers as opposed to controlling lateral soil movement. Any voids between the excavation walls and the support system should be immediately filled to reduce the potential for loss of ground and to provide support to existing adjacent utilities and roadways, and it is recommended that the excavation be carried out in short sections, with the support system installed immediately upon excavation completion.

As previously noted, the native clayey silt, silt and clay/clay and silt, and silt soils encountered in the lower zone of Boreholes 4, 5 and 6 became very dense/hard with depth (SPT N-values in excess of 50 blows per 0.3 m) and may prove difficult to

excavate with conventional excavating equipment, impacting the production schedule. It is imperative that when the very dense/hard soils are utilized as fill, the material must be broken down (pulverized) to minimize void space and reduce the potential for settlement.

## 5.8. <u>Construction Dewatering Considerations</u>

Wet to saturated soils were encountered in Boreholes 1 to 6, as described in Section 4.6 of this report. The relatively impermeable fine-grained, hard/very dense, clayey silt, silt till, as well as the sandy clayey silt till observed in the lower zone of the boreholes, may have the potential to create perched water conditions.

Seepage control requirements and groundwater conditions during construction are generally dependent on the amount of precipitation, control of surface water, the time of year, the area of work on the site, the depth of the excavations, and can fluctuate significantly in elevation and volume. As such, it is critical that provisions for site dewatering be part of the site development and construction process. As required, seepage should generally be adequately controlled using conventional construction dewatering techniques such as pumping from sump pits. However, if heavy seepage occurs, it may be necessary to increase the number of pumps during construction.

Dewatering should be performed in accordance with OPSS 517 and the control of water must be in accordance with OPSS 518. It is the responsibility of the contractor to propose a suitable dewatering system based on the groundwater elevation at the time of construction. Collected water should discharge a sufficient distance away from the excavation to prevent re-entry. Sediment control measures must be installed at the discharge point of the dewatering system to avoid any potential adverse impacts on the environment.

It is recommended that R.J. Burnside & Associates Limited be consulted prior to any on-site water being discharged to municipal outlets to ensure that proper procedures are followed.

## 5.9. <u>Service Pipe Bedding</u>

It is expected that the native soils encountered in the geotechnical investigation will be in a saturated state and therefore it is expected that it will be necessary to increase the thickness of the granular base and utilize 19 mm clear stone to create an adequate supporting base for the service pipes and/or manholes and catch basin structures. As such, it is recommended that provisions for extra pipe bedding and clear stone be part of the project tendering and construction process. The general contractor is responsible to protect service piping from damage by heavy equipment. Pipe embedment, cover and backfill for both flexible and rigid pipes should be in accordance with all current and applicable OPSS, OPSD, and OBC standards and guidelines, and as follows: **Flexible Pipes** – The pipe bedding should be shaped to receive the bottom of the pipe. If necessary, pipe culvert frost treatment should be undertaken in accordance with OPSD-803.030 and OPSD-803.031. The trench excavations should be symmetrical with respect to the centreline of the pipe. The granular material placed under the haunches of the pipe must be compacted to 95% SPMDD prior to the continued placement and compaction of the embedment material. The homogeneous granular material used for embedment should be placed and compacted uniformly around the pipe. Should wet conditions be encountered at the base of the trench, the pipe bedding should consist of 19 mm clear crushed stone (meeting OPSS 1004 specifications). Normally, it would be recommended to wrap the clear crushed stone with geotextile to prevent fine soils from entering the clear stone and thereby creating voids around the pipe. However, in the saturated conditions expected, it is not typically feasible to wrap the clear stone, nor is it necessary, as the void space is quickly filled with fine soils as water (with suspended fine soils) rapidly enters the excavation.

**<u>Rigid Pipes</u>** - In general, the pipe installation recommendations for rigid pipes are the same as those for flexible pipes, except that the minimum bedding depth below a rigid pipe should be 0.15D (where D is the pipe diameter). In no case should this dimension be less than 150 mm or greater than 300 mm.

## 5.10. Perimeter Building Drainage, Foundation Wall Backfill and Trench Backfill

In order to assist in maintaining a dry building with respect to surface water seepage, it is recommended that exterior grades around the buildings be sloped down and away at a 2% gradient or more, for a distance of at least 1.5 m to 2.0 m (depending on side yard setbacks). Any surface discharge rainwater leaders must be constructed with solid piping that discharges with positive drainage at least 1.5 m away from building foundations and/or beyond sidewalks to a drainage swale or appropriate storm drainage system.

The founding elevations for the proposed structures were not available at the time of preparation of this report. CMT Inc. can provide further recommendations for building drainage once the design drawings are completed and the founding elevations have been confirmed.

It should be noted that based on the observations in the boreholes, there is potential for perched water conditions. The construction of foundations, slabs-on-grade, and deep structures such as sump pits within or below zones of saturation will require design of site-specific waterproofing systems constructed in accordance with the 2012 OBC. If required, it would be recommended that a waterproofing supplier/specialist be consulted to recommend an appropriate product and installation requirements that would be suited to this site. It is recommended that a good quality sump pump be utilized, and that the system be equipped with a battery backup in the event of power failure, (keeping in mind that a battery backup system does not typically have a long run time).

It is anticipated that the new building will have a basement level. An exterior perimeter weeping tile system comprising perforated drainage pipe with a factory installed filter sock, bedded in 19 mm clear crushed stone and wrapped in geotextile filter fabric such as Terrafix 270R (or equivalent), must be installed at an elevation that is below the proposed basement slab-on-grade elevation and provided with positive drainage into a sump pit. The portion of the piping that connects the exterior weeping tile system into the sump pit must comprise solid piping to prevent exterior water from being introduced into the interior basement as well to provide an outlet for any water that may collect in the subslab stone. It is also recommended that a capped cleanout port(s) be extended up to the ground surface elevation to provide future access (if required). The rainwater leaders must not be connected to the perimeter weeping tile system.

In order to reduce the effects of surficial frost heave in areas that will be hard surfaced, it is recommended that the exterior foundation backfill consist of free-draining granular material such as approved on-site sand and gravel or imported Granular 'B' Type I or Type III (OPSS 1010), with a maximum aggregate size not exceeding 100 mm, and that it extend a minimum lateral distance of 600 mm out from the foundation walls and/or beyond perimeter sidewalks and entranceway slabs. It is critical that particles greater than 100 mm in diameter are not in contact with the foundation wall to prevent point loading and overstressing. The backfill material used against the foundation walls must be placed so that the allowable lateral capacities of the foundation walls are not exceeded. Where only one side of a foundation wall will be backfilled, and the height of the wall is such that lateral support is required, or where the concrete strength has not been achieved, the wall must be braced or laterally supported prior to backfilling. In situations where both sides of the wall are backfilled, the backfill should be placed in equal lifts, not exceeding 200 mm differential on each side during backfill operations and the backfill should be compacted to a minimum of 98% SPMDD.

The native mineral soils (non-organic) are generally considered suitable for reuse as trench backfill and bulk fill in the driveways and parking lots; however, the wet soils may require air-drying in order to achieve the specified compaction. Air-drying cannot typically be achieved during winter construction; therefore, depending on the time of year that construction takes place, it may be more feasible to utilize an imported granular fill for this project.

Backfilling operations should be carried out with the following minimum requirements:

- Adequate heavy smooth drum or padfoot vibratory compaction equipment (suited to soil type) should be used for the compaction and to break down any large blocky pieces of soil;
- Loose lift thicknesses should not exceed 0.3 m (12") for granular soils or 0.2 m (8") for silt soils or the capacity of the compactor (whichever is less);

- The soils must be at suitable moisture contents to achieve compaction to a minimum 95% SPMDD in non-structural bulk fill areas. Service trenches excavated the zone of influence of footings for structures must be compacted to a minimum of 98% SPMDD;
- It is recommended that inspection and testing be carried out during construction to confirm backfill quality, thickness and to ensure that compaction requirements are achieved;
- Service trench backfill materials may consist of approved excavated soils with no particles greater than 100 mm and no topsoil or other deleterious materials;
- If construction operations are undertaken in the winter, strict consideration should be given to the condition of the backfill material to make certain that frozen material is not used.

## 5.11. <u>Pavement Design/Drainage</u>

All topsoil and vegetation (including tree roots and all loose/disturbed soils containing roots or organics material), and any loose/soft native soils, must be subexcavated from within the proposed driveways and parking lot areas. It is recommended to either subexcavate any existing soft subgrade materials or provide further consolidation with vibratory compaction equipment in order to prepare a proper, stable subgrade.

Prior to placement of the granular base, the subgrade must be proof-rolled, and any soft or unstable areas should be subexcavated and replaced with suitable drier materials. The subgrade should be graded smooth (free of depressions) and properly crowned to ensure positive drainage, with a minimum grade of 3% toward the catch basins or to the parking lot/driveway edge (provided that collection and proper gravity drainage to a suitable outlet is provided). When service pipes are installed, pipe bedding and backfilling should be undertaken as indicated in Sections 5.9 and 5.10 of this report.

Rapid drainage of the pavement structure is critical to ensure long-term performance and to help minimize frost heave. The requirement for subdrains will be dependent on the composition of the prepared pavement subgrade soils. Some of the native soils encountered in the boreholes are frost-susceptible soils and, as such, it is recommended to install subdrains (provided gravity drainage to a suitable outlet can be provided). It is recommended to install minimum 100 mm diameter perforated subdrains to collect and redirect water beneath the pavement surface. Subdrains should be designed and installed in accordance with OPSS 405 and OPSD 216.021. If Granular 'A' bedding (OPSS 1010) is utilized, the subdrains should be equipped with a factory installed filter sock. If 19 mm clear stone (OPSS 1004) is utilized as bedding for the subdrain, then the bedding must be wrapped completely with geotextile filter fabric such as Terrafix 270R (or equivalent) and a factory installed filter sock is not required. Installation of rigid subdrains allows for better grade control and less potential for damage during installation; however, it would

be expected that there would be higher cost implications associated with the installation of rigid subdrains over flexible subdrains. Positive drainage through grade control of subdrains is critical, as improperly installed subdrains can turn drainage systems into reservoirs, which can fuel frost action. The subdrains will hasten the removal of water, thereby reducing the risk and effects of frost heaving and load transfer in saturated conditions. It is suggested that, at a minimum, subdrains be installed through all low areas in the parking lot and driveways, and ideally along the curb lines as well to prevent water from entering the granular subbase. The subdrains should be installed in a 0.3 m (1.0 ft) by 0.3 m (1.0 ft) trench in the subgrade and bedded approximately 50 mm (2") above the bottom of the trench. The subgrade must be prepared with positive drainage to the subdrains must be installed with positive drainage into a catch basin structure or other suitable outlet.

Should the subgrade soils comprise free-draining granular soils (minimum 1.0 m thick with positive drainage at the interface with any relatively impermeable soils), then the installation of subdrains may not be required.

The native subgrade soils are sensitive to change in moisture content and can become loose or soft if the soils are subject to inclement weather and seepage or severe drying. Furthermore, the subgrade soils could be easily disturbed if traveled on during construction. As such, where this material will be exposed, it is recommended that the granular subbase be placed immediately upon completion of the subgrade preparation to protect the integrity of the subgrade soils.

It is expected that the driveways and parking lots will experience light traffic (personal vehicles) and some heavy traffic (delivery trucks, as well as maintenance and emergency vehicles). Based on the anticipated vehicle loading and frost-susceptibility of the subgrade soils, the following pavement design is provided:

Material	Recommended Thickness For New Pavement		
	Light Traffic	Heavy Traffic	
A 1 14 :- C u u t	HL3-40 mm (1.5")	HL3-50 mm (2.0")	
Asphaltic Concrete	HL4 or HL8-50 mm (2.0")	HL4 or HL8-60 mm (2.5")	
Granular 'A' Base	150 mm (6.0")	150 mm (6.0")	
Granular 'B' Subbase	400 mm (16.0")	450 mm (18.0")	

Given the potential for wet subgrade conditions, it is recommended that the driveways and parking lot subgrade soils be assessed at the time of excavation by qualified personnel. Depending on conditions encountered at the time of construction, different options may need to be undertaken to construct a stable driveway and parking lot base. These options may include subexcavation and increasing the thickness of the Granular 'B' subbase, the use of reinforcing geotextile and/or geogrid, or a combination of all. As such, it is recommended that provisions for subexcavation and disposal of wet soils, importing and placing additional Granular 'B' (OPSS 1010), as well as supply and placement of a reinforcing geotextile (Terrafix 270R or equivalent) and geogrid (Tensar BX1200 or equivalent) should be included in the tender documents.

The granular base and subbase materials must conform to the physical property and gradation requirements of OPSS 1010 and must be compacted to 100% SPMDD. Asphaltic concrete should be supplied, placed and compacted to a minimum 92.0% Marshall maximum relative density, in accordance with OPSS 1150 and OPSS 310.

Construction joints in the surface asphalt must be offset a minimum of 150 mm to 300 mm (6" to 12") from construction joints in the binder asphalt so that longitudinal joints do not coincide.

Frost tapers must be constructed at any changes from light traffic to heavy traffic areas within the driveways and parking lots. If heavy traffic routes are not delineated by barriers or if it is anticipated that heavy equipment (such as loader and dump trucks) will be utilized for snow removal, it would be recommended that the heavy traffic pavement structure be utilized throughout the driveways and parking lots.

Where new asphalt is joined into existing asphalt, it is recommended that the existing asphalt be sawcut in a straight line prior to being milled to a depth of 40 mm and a width of 150 mm as per OPSD 509.010. It is recommended that a tackcoat be applied to the edge and surface of all milled asphalt prior to placement of new asphalt in conformance with OPSS 308.

The pavement should be designed to ensure that water will not pond on the pavement surface. If the surface asphalt is not placed within a reasonable time following placement of the binder asphalt, it is recommended that the catch basin lids are set at a lower elevation or apertures provided to allow surface water to drain into the catch basins and not accumulate around the catch basins. The strength of the pavement structure relies on all of the components to be in place in order to provide the design strength; therefore, it is strongly recommended that the surface asphalt be placed shortly after placement of the binder asphalt so as to avoid undue stress on the binder asphalt by not having the complete pavement structure in place.

It should be noted that, currently, asphalt mixes tend to be more flexible and, as such, there is a tendency for damage to occur from vehicles turning their steering wheels or applying excessive brake pressure. The damage can occur from both passenger vehicles as well as large vehicles. The condition is further intensified during hot weather. In high traffic/tight turning areas, it is recommended that rigid Portland cement pavement be considered.

#### 5.12. <u>Excess Soil Management</u>

#### 5.12.1 Chemical Testing was NOT Undertaken

Generally, if surplus soils are to be exported off-site, it will be necessary to perform chemical analysis of the soils. Chemical analysis was not undertaken as part of this geotechnical investigation. Should chemical analysis tests be required, the required tests vary and will be dependent on the disposal site utilized by the general contractor.

Most commonly, the soils are tested for the following:

- F1-F4, VOC's, BTEX as per O. Reg. 153/04 as amended by R511
- SVOC as per O. Reg. 153/04 as amended by R511
- Metals/Inorganics as per O. Reg. 153/04 amended by R511

The chemical analysis results are then compared to Ontario Regulation 153/04 - as amended by O.Reg. 511 - April 15, 2011 Standards = [Suite] - ON-511-T1/T2-SOIL-RPI.

#### 5.12.2 <u>TCLP Requirement</u>

If soils are transported to a landfill facility, additional chemical testing in accordance with Ontario Regulation 347, Schedule 4, as amended to Ontario Regulation 558/00, dated March 2001, Toxicity Characteristic Leaching Procedure (TCLP) will be required.

When transporting soils off-site, the following is recommended:

- All chemical analyses and environmental assessment reports must be fully disclosed to the receiving site owners/authorities, who must agree to receive the material.
- An environmental consultant must confirm the land use at the receiving site is compatible to receive the material.
- An environmental consultant must monitor the transportation and placement of the materials to ensure that the material is placed appropriately at the pre-approved site.
- The excess materials may not be transported to a site that has previously had a Record of Site Condition (RSC) filed, unless the material meets the criteria outlined in the RSC.

It should be noted that landfill sites will generally only accept laboratory test results that have been completed within 30 days of exporting. Therefore, it is recommended that provisions for chemical analysis be included in the tender documents. It should also be noted that the laboratory testing generally takes five (5) working days to process with a regular turnaround time.

## 5.13. <u>Coefficient of Permeability/T-time</u>

As part of the geotechnical investigation, gradation analyses were performed on samples of the native clayey silt, the silt and clay/clay and silt, as well as the silt soils. The following table provides the sample location (monitoring well/borehole number), sample depth, corresponding estimated coefficient of permeability (k) and T-time, as well as soil type:

Borehole No.	Depth (m)	Estimated Coefficient of Permeability (k) cm/s	Estimated T-time (T) min/cm	Soil Type
1	0.76 – 1.37	< 1.0 x 10 <sup>-6</sup>	> 50	Clay and silt, some sand, trace gravel (ML)
2	1.52 – 2.13	< 1.0 x 10 <sup>-6</sup>	50	Clayey, sandy silt trace gravel (ML)

#### 5.14. <u>Radon</u>

According to information provided by Health Canada, radon is a radioactive gas that is naturally formed through the breakdown of uranium in soil, rock and water. When radon escapes the earth in the outdoors, it mixes with fresh air, resulting in concentrations that are too low to be of concern. However, when radon enters an enclosed space, such as a building, high concentration of radon can accumulate and become a health concern. Health Canada indicates that most buildings have some level of radon in them. Unfortunately, it is not possible to predict before construction whether or not a new building will have high radon levels as radon can only be detected by radon measurement devices, which would be installed in a home, post construction. Section 9.13.4.1 Soil Gas Control of the current 2012 Ontario Building Code (OBC) states that "Where methane or radon gases are known to be a problem, construction shall comply with the requirements for soil gas control in MMAH Supplementary Standard SB-9, Requirements for Soil Gas Control".

## 6.0 SITE INSPECTIONS

Qualified geotechnical personnel should supervise excavation inspections as well as compaction testing for structural filling, site grading and site servicing. This will ensure that footings are founded in the proper strata and that proper material and techniques are used and the specified compaction is achieved. CMT Engineering Inc. would be pleased to review the design drawings and provide an inspection and testing program for the construction of the proposed development.

## 7.0 LIMITATIONS OF THE INVESTIGATION

This report is intended for the Client named herein and for their Client. The report should be read in its entirety, and no portion of this report may be used as a separate entity. Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties.

The recommendations made in this report are in accordance with our present understanding of the project. We request that we be permitted to review our recommendations when the drawings and specifications are complete, or if the proposed construction should differ from that mentioned in this report.

It is important to emphasize that a soil investigation is, in fact, a random sampling of a site and the comments are based on the results obtained at the test locations only. It is therefore assumed that these results are representative of the subsoil conditions across the site. Should any conditions at the site be encountered which differ from those found at the test locations, we request that we be notified immediately in order to permit a reassessment of our recommendations.

It should be noted that this report specifically addresses geotechnical aspects of the project and does not include any investigations or assessments relating to potential subsurface contamination. As such, there should be no assumptions or conclusions derived from this report with respect to potential soil or water contamination. Soil or water contamination is generally caused by the presence of xenobiotic (human-made) chemicals or other alteration processes in the natural soil and groundwater environment. If necessary, the investigation, assessment and rehabilitation of soil and water contaminants should be undertaken by qualified environmental specialists.

The samples obtained during the geotechnical investigation will be stored for a period of three months, after which time they will be disposed of unless alternative arrangements are made.

We trust that this report meets with your present requirements. Should you have any questions, please do not hesitate to contact our office.

Prepared by:

Shawn Wheatley, M.Eng.

ks







## APPENDIX A

0

0

# **BOREHOLE LOGS**







BOREH	OLE 4			Page 1 of 1
Date Drilled: Februar Rig: Geoprobe 78221 Contractor: CMT Dri Drilling Method: SPT	ry 12, 2020 DT Iling Inc. Elevation: 182.49 F Logged by: SW	9 m	Project No.: 20-026 Project: Geotech - Location: Ninth Lin	) Proposed Church e, Mississauga, ON
<ul> <li>Depth (ft/m)</li> <li>Sample Type</li> <li>Recovery (%)</li> <li>Sample Number</li> <li>Symbols</li> </ul>	SOIL DESCRIPTION	Well Installation	Moisture Content % ≪Vp [X] WÞ 10 20 30 40	Pocket Penetrometer
ft       m         0       0         1       SS         2       SS         3       SS         4       SS         6       SS         7       SS         6       SS         7       SS         6       SS         7       SS         10       SS         11       SS         12       SS         13       SS         14       MC5         15       SS         16       SS         17       SS         18       SS         19       6         20       SS         21       SS         13       SS         14       SS         15       SS         16       SS         17       SS         18       S         19       S         20       S         21       S         22       S         23       S         24       S         25       S	Ground Surface (m) 182.4 TOPSOIL 0.000 Loose, dark brown, silty organic topsoil, moist (100mm) 181.7 O.760 CLAYEY SILT 0.760 Soft, brown and dark brown mottled clayey silt, some sand, trace gravel, organics and rootlets, moist 180.2 Becoming very stiff, brown, no organics and rootlets 180.2 Becoming hard 2.29 179.2 SANDY CLAYEY SILT TILL 3.20 Very dense, brown sandy clayey silt till, trace gravel, 178.66 moist 3.81 Becoming grey 177.77 SILT TILL 4.72 Dense, grey silt till, some sand 177.37 and clay, moist 5.18 End of Borehole Borehole caved at about 4.67 m below ground surface. No accumulated groundwater encountered open borehole.		23.9 14.4 13.3 12.3 11.0 12.0 10.0 13.3	3 28 45 50(4") 41
	10 St. ph	11 Industrial Crescent, Unit 1 Clements, Ontario NOB 2M0 one 519-699-5775 fax 519-699- w.cmlinc.net	4664	C MI DIC



BOREHOLE 6	Page 1 of 1			
Date Drilled: February 10, 2020 Rig: Geoprobe 7822DT Contractor: CMT Drilling Inc. Drilling Method: SPT	Elevation: 181.68 m Logged by: SW		Project No.: 20-020 Project: Geotech - Location: Ninth Lin	6 Proposed Church e, Mississauga, ON
Depth (ft/m) Sample Type Recovery (%) Sample Number Symbols	IL DESCRIPTION	Well Installation	Moisture Content %	Pocket Penetrometer
ft       m       TOPSC         0       0       SS       1       TOPSC         2       3       1       SS       2       CLAYE         3       1       SS       2       Firm, brown       mottled         4       5       SS       3       Becomin       SAND         8       SS       4       Becomin       SILT TI         10       3       SS       5       Becomin         10       3       SS       5       Becomin         10       3       SS       5       Becomin         11       MC5       6       SAND       Very der         13       4       MC5       6       SANDY         13       4       MC5       8       SANDY         14       4       MC5       8       SANDY         17       Hard, greatric       SAND       Very den         18       MC5       8       SAND         20       6       SAND       Very den         21       7       MC5       9       SAND         24       8       Groundwa       4.27 m be         31	Ground Surface (m)       181.68         IL       0.00         ark brown, silty       0.00         opsoil, moist (80mm)       180.92         Y SILT       0.76         wm, red, and grey       0.76         blayey silt, some sand       179.98         g hard, brown       1.70         se, brown sand, trace       2.29         ravel, moist       2.74         g wet, some silt       2.74         L       2.74         rown silt till, some       2.74         Iclay, wet       176.96         CLAYEY SILT TILL       4.72         y sandy clayey silt till, vel, moist       175.58         6.10       6.10         se, grey sand, some       174.06         clay and gravel, wet       174.06         End of Borehole       7.62         tter measured at approximately       10w ground surface (elev. 177.41         . 12, 2020.       1000000000000000000000000000000000000	Somm Slot 10 Screen	15.7 12.5 10.0 19.0 19.5 10.6 9.4 9.4	4 32 50(5") 44 54 50(5")
CMT ENGINEERING INC. 1011 Industrial Crescent, Unit 1 St. Clements, Ontario NOB 2MO phone 519-699-5775 fax 519-699-4664 www.cmtinc.net				


# APPENDIX B

1

# **GRAIN SIZE ANALYSES**



St. Clements, ON	Project No.: 20-026	Figure	1
	<b>Project:</b> Ninth Line Mississauga, Ontario		
CMT Engineering Inc.	<b>Client:</b> St. Mark and St. Demiana Copile Orthodox C	Jurch	



St.	Clements,	ON	Project No.:	20-026

Figure 2





# APPENDIX C

# WELL RECORDS

Mail owner's information         Last Name / Organization           First Nime         Last Name / Organization         Email Address           First Nime         Last Name / Organization         Province         Point Code           Mailing Address (Street NumberName)         Mailing Address (Street NumberName)         Mailing Address (Street NumberName)         Province         Point Code           Viel Location         Construction (Street NumberName)         Los Code         Los Code         Different NumberName)           Viel Codemain Street NumberName)         Construction (Street NumberName) </th <th>Page of     Well Cons     ALCHTACL by Well On lephone No. (inc. area    )      Decession     Postal Cod         Depth (n</th> <th>Pag IHEB_MICHY Telephon BPI     Concess Province Ontario Other</th> <th>E-mail Address E-NI CANADA ATIN'. Molte Province Postal Code LE Lucida</th> <th>2604</th> <th>ation</th> <th>e / Organiza</th> <th>Last Name /</th> <th>formation</th> <th>/ner's Inf</th> <th>Well Ow</th>	Page of     Well Cons     ALCHTACL by Well On lephone No. (inc. area    )      Decession     Postal Cod         Depth (n	Pag IHEB_MICHY Telephon BPI     Concess Province Ontario Other	E-mail Address E-NI CANADA ATIN'. Molte Province Postal Code LE Lucida	2604	ation	e / Organiza	Last Name /	formation	/ner's Inf	Well Ow
First Nume       Ext Nume       Ext Nume       Ext Nume         THE DidCDSE       Child Address       Ext Nume       Province       Province       Province         THE DidCDSE       Child Address       Manifold Mill       Main Status       Province       Province       Province         ZIESS       Column Status       Manifold Nume       Main Status       Column       Column         Address Of Viell Location       Ext Nume       Main Status       Column       Column         Address Of Viell Location (Street Number/Name)       Main Status       Column       Ontaria         Minis Column       Column       Column       Ontaria       Ontaria         Minis Column       Main Status       Column       Ontaria       Ontaria         Convertured n and Bedrock Materials/Abandomment Sealing Record (are instatuctions on the back of this form)       Onter Material       Onter Material         Back Line       Mont Control Naterial       Mont Control Naterial       Onter Material       Onter Material         Back Line       Site T       Control       Material       Denses       Denses         Back Line       Site T       Control       Mont Control Naterial       Denses       Denses         Site T       Control       Control	Well Cons     MICHAEL by Well O lephone No. (inc. area     Docession     Postal Cod     Depth     From	Province Ontario	E-mail Address CANADA ATTN: Molde Province Postal Code		ation	e / Organiza	Last Name /	ormation	mer 5 mi	TTCH OW
THE Draces of Lifestizsanesa, unexcouved a number       Municipality       Province       Pr	A ICHAEL by Well O lephone No. (inc. area 	HEB MICHA Telephon BA     Concess Province Ontario Other	Province Postal Code	and 110 different incompanyation			Laormanio		e	First Name
2126     Results of Vell Yeld To       Weil Location     Could State Number/Name)       Number Name)     Townahip       Number Name)     Townahip       Number Name)     Townahip       UTM Coordinates Zone Easting     Northing       Number Name)     Marked Jean And State Sta	Depth (     From	Province Ontario		Z AND WESTER	ANCOUVER	VGA, UF	5155Aug	E OF MIS	NDCE5E	THE I Mailing Ad
Well Location         Construction	Depth (     From	Concess Province Ontario Other	ON LDMDD	MISSISSANGA		T	COURT	NWOOD	ROBI	2188
Address of wein Location (states number)         Lot         Construction           NINTIAL LINES (CEON) SE OF Bully NATURACE PDE)         Province         Ontraining           CountryDistrict/Municipality         Northing         Municipal Plan and Subiol Number         Ohter           ND RISTIAL LINES (CEON)         Experimental State Stat	ioncession Postal Cod io	Province Ontario Other						(Cl	ation	Well Loc
CountyDibinchMultipality Count Count of Construction Results of Well Yield Technology (Convertice) Construction Record - Screen Cooling All Counting (Convertice) Construction Record - Screen Cooling All Cooling Construction Record - Screen Cooling All Cooling Construction Record - Screen Cooling All Cooling	Postal Coc io	Province Ontario Other	Lot	TURR PDE	R.A. MAN	e) - 05 7	mber/Name)	= (500)		Address of
UTM Coordinates! Zone	10	Ontario Other	) Pr	City/Town/Village	DEN MAN		in ce	cipality	strict/Munici	County/Dis
NAD       813       11       12       13       14       13       14       13       14       <	Depth From	Other	of Number Ot	OAKVILLE		Northing	N	ne Fasting	dinates Zor	UTM Coord
Diverburden and Bedrock Materials/Abandomment Sealing Record (see instructions on the back of this form)           General Colour         Most Common Material         Other Meterials         General Description           BLACK         ToPSolL         HARD         General Description           BLACK         ToPSolL         HARD         General Description           BLACK         ToPSolL         HARD         General Description           GeC+1         SILT         CLAH         ToPSC           GeC+1         SILT         CLAH         ToPSC           Depth Set al (MY)         Type of Sealant Used (Material and Type)         Volume Placed (mid) (if india (if if pumping discontinued, give reason: tevel         Three Volume (Description)           SH         S(B. HacePuics         L1         Static Static         Three Volume (Description)         Three Volume (Description)         Static (Description)         Three Volume (Description)         Static (Description)         Three Volume (Description)	Depth (m				94166	4811	1711	7603	831	NAD
General Colour       Meel Common Material       Other Materials       General Description         BLACK       ToPSCIL	From		e back of this form)	ord (see instructions on the	Sealing Reco	donment	ials/Aband	edrock Materi	len and Be	Overburd
BLACK       ToPPaiL         BROWN       SILT       CLAH         GRE-1       SILT       DENSE         GRE-1       SALD       SILT         Deptified       SILT       DENSE         Commonic (Material and Type)       Charter (Material and Type)       Charter (Material and Type)         O       S-H       3 (B. HacePusc       Li         Method of Construction       (Material and Type)       Dense       Balance         Cable Tool       Denned       Public       Construction       Time Value         Cable Tool       Dense       Dense       Construction       1         Rotary (Conventional)       Jetting       Description       10       1         Cable Tool       Depth (mit)       Wall Use       Depth (mit)       20         Construction       Other, specify       Intelse       Material       20         Construction       Other, specify       The Redamp Wall       30       10         Construction Record - Screen       Other, specify       3			General Description	ner Materials	Oti	rial	mon Materia	Most Com	Colour	General C
BECAUN       SILT       CLA-I       HARD         GB2-1       SILT       CLA-I       Tepsse         GB2-1       SILT       Dense       Tepsse       Tepsse         GB2-1       SILT       Dense       Tepsse       Tepsse         GB2-1       SILT       Dense       Content Class       Not teps         GB2-1       Dianod       Well Use       Duration of pumping       Tepsse         GB2-1       Dianod       Well Well Well Well Well Well Well Well	00							TOPSOIL		BLACK
GRE-1     SULT     CLMH     DENSE       GRE-1     SULT     CLMH     DENSE       GRE-1     SULT     DENSE       GRE-1     The results of Well Vield Term       GRE-1     The results of Well Vield Term       GRE-1     The results of Well Vield Term       SULT     GRE-1       GRE-1     The result of Well Vield Term       GRE-1     Dense       GRE-1     Densetring	0.3 4		HARD		CLAI			SILT	SN	BROW
Cit2C-       SPAD       SINT       DENSE         Annular Space       Annular Space       Results of Well Yield Te         Depth Set at (mit)       Type of Sealant Used       (mit)       Darks         O       S.Ч       3 (B       Pacefulce       L1         Method of Construction       Used       (mit)       2         Method of Construction       Uvalue       Not used       1         Cable Tool       Demond       Uvalue       Pumping rate (lmin / GPM)       2         Cable Tool       Demond       Uvalue       Demond       1         Cable Tool       Demond       Duate       Demond       1         Cable Tool       Obmestic       Manicipal       Demonded       10         Cable Tool       Demonde       Connersica       Not used       Not used         Construction       Well Use       Institute       1       1         Cable Tool       Digging       Institute       1       1         Cable Tool       Obmestic       Connersica       Not used       1       1         Diration of pumping timing	4.5 6		DENSE		CLAN			SILT		GRE-1
Annular Space       Results of Well Yield Te         Depth Set at (mit)       Type of Sealart Used (min)       Volumg Placed (Material and Type)       After test of well yield, water was: Depth Set at (mit)       Development (min)         O       5.4       3 (B       HorcePues       L1         SH       7.6       142       Space       Dawn         SH       7.6       142       Space       L1         Method of Construction       Public       Commercial       Not used         Cable Tool       Demond       Public       Commercial       Not used         Boring       Digging       Digging       Digging       10         Cable Tool       Connectic       Test Hole       Zommercial       Not used         Other, apedity       Construction Record - Casing       Status of Well       16         Concrete, Plastic, Steel       Well Depth (m/t)       Recommended pump depth (m/t)       25         Construction Record - Casing       Construction Record - Casing       Not used       Not used         Digging       Digging       Digging       Depth (m/t)       Recommended pump depth (m/t)       25         Construction Record - Casing       Construction Record - Casing       Status of Well       Not instificient Supply <tr< td=""><td>6.0 7</td><td></td><td>DENSE</td><td></td><td>SILT</td><td></td><td></td><td>SALD</td><td>۱<u> </u></td><td>GRE</td></tr<>	6.0 7		DENSE		SILT			SALD	۱ <u> </u>	GRE
Annular Space         Description       Type of Sealant Used (Material and Type)       Volume Placed (m2/P)         0       5.4       3 (b)       Accurrence       L1         5.4       7.6       H2 Space       L1         6       1       1       1         9       5.4       3 (b)       Accurrence       L1         1       1       1       1         9       1       1       2         1       1       2       1         1       1       2       1         1       1       2       1         1       1       2       1         1       1       2       1         1       1       2       1         1       1       2       1         1       1       2       1         1       1       2       1         1       1       2       1         1       1       2       1         1       1       1       2         1       1       1       2         1       1       1       2         1								-		
Annular Space         Results of Well Yield Te         Depth Set at (m/t)       Type of Sealant Used (Material and Type)       Volume Placed (m/t)         O       5.4       3 (s)       Hacepuse       L1         Static       Construction       L1       Pumping discontinued, give reason       Static Level         Method of Construction       Well Use       Pumping rate (limin / GPM)       3         Coherence       Domestic       Commercial       Dot used (Material and Type)       Pumping rate (limin / GPM)         Method of Construction       Well Use       Pumping rate (limin / GPM)       4         Pacture (Reverse)       Dring       Lowatering (Generate, Fase(limin / GPM)       4         Construction Record - Casing       Status of Well       Mater Supply       Recommended pumping (m/t)         Inside (Generate, Fase(limin / GPM)       Construction Record - Casing       Status of Well       Recommended pump depth (m/t)         Socie       PLASTIC       O       6.1       Depth (m/t)       Well Supply         Construction Record - Screen       Opth (m/t)       Depth (m/t)       Material Method       Depth (m/t)       Plase genty         Socie       PLASTIC       O       6.1       Depth (m/t)       Material Method       Depth (m/t)										
Annular Space         Depth Setal ( <i>m</i> )       Type of Sealant Used ( <i>Material and Type</i> )       Volume Placed ( <i>m</i> )?         O       S-H       3 (B       HacePusso       L1         Static       Construction       L1       Dave of ( <i>m</i> )?       Dave of ( <i>m</i> )?         Method of Construction       Well Use       Duration of ( <i>m</i> )?       Duration of ( <i>m</i> )?       Duration of ( <i>m</i> )?       Duration of ( <i>m</i> )?         Method of Construction       Well Use       Domestic       Downsite       Downsite       Duration of ( <i>m</i> )?       Duration of pumping         Cable Tool       Diamoder       Public       Commercial       Downsite       Downsite       Duration of pumping       Its         Construction Record - Casing       Status of Well       Mater Scalar       Nontoing       Its       Its       Its         Other, specify       Deph( <i>m</i> ?)       To       Deplacement Well       Rescure of pumping ( <i>m</i> ?)       Rescure of pumping ( <i>m</i> ?)       Its       Its         Diameter       Construction Record - Screen       To       Deplacement Well       Rescure of pumping ( <i>m</i> ?)       Recommended pump rate ( <i>m</i> ?)       Re										
Annular Space         Perform       Type of Sealant Used (Material and Type)       Volump Placed (m?d?)         O       5.4       3 (b       HacePutes       L 1         Statistic       Material and Type)       Oher, specify       Deavor         Statistic       Material and Type)       Construction       Damond       Deavor         Statistic       Matrixial       Deavor       I         Mathod       O Construction       Well Uses       Pumping alscontinued, give reason:       Deavor         Mathod       O Construction       Well Uses       Pumping alscontinued, give reason:       Duration of pumping         Mathod       Deavor       Difference       Manicipal       Deavor       Manicipal         Boring       Districe       Construction Record - Casing       Status of Well       Mater Supply         Insident       Deph (m?t)       Observation and/ Material       Mater Supply       Reacharge Well       Soc         Construction Record - Screen       Material       Deph (m?t)       Deph (m?t)       Deph (m?t)       Mater Coality       Mater Coality         Outside Giffin       Material       Deph (m?t)       Deph (m?t)       Deph (m?t)       Bathono addition and/ Mathon, Grave       Mater Supply       Bathono additherein										
Annular space       Results of Well Yield very         Depth Set al (m?)       Type of Sealant Used (Material and Type)       Volume Placed (m?)?         O       5.4       3 (B       Haccebus       L1         S.4       3 (B       Haccebus       L1         S.4       3 (B       Hacebus       L1         Method of Construction       L1       If pumping discontinued, give reason: Bitic       If all (min)         Construction       Well Use       Ommercial       Not used (min)       Not used (min)       Not used (min)         Construction       Image       Dommestic       Commercial       Not used (min)       Not used (min)       Not used (min)         Construction Record - Casing       Image       Image       Image       Image       Image         Other, specify       Open Hole CR Material (Galvanized, Fibriglass, Ginin       Depth (m/n)       Image       Image       Image         Diside for Ginin       Construction Record - Screen       Depth (m/n)       Detextering Well       Recommended pump rate (min / GPM)       Image       Image         Inside Diameter       Construction Record - Screen       Observation and material       Image       Image       Image       Image         Sce       PUPSTLC       IO       Image							1. C. C. M. P. 193		ALC: NO.	
From       Tot       (Material and Type)       (m/t)t         0       5.4       3 (6       HacePuxs       L1         5.4       7.6       #2.5BND       L1         Image: Static production       L1       Image: Static production       Image: Static production       Image: Static production         Construction       Diamond       Public       Commercial       Not used         Method of Construction       Diamond       Public       Commercial       Not used         Material       Diamond       Domestic       Material       Monitoring         Baring       Diagond       Industrial       Construction Record - Casing       Status of Well         Material       Open Hole OR Material       Thickness       From       To       Readmap Well         Depth (m/t)       Open Hole OR Material       Material       Wall       Depth (m/t)       Recommended pump depth (m/t)       25         S. c.B.       PLASTIC       O       6.1       Depth (m/t)       Bandoned, OPen       40         Diameter       Material       Stot No.       From       To       Recharge Well       Dewatering Well         Depth (m/t)       Abandoned, OPen       Wall Coality (Diameter, Specify)       Abandoned, OPen       6	Testing Down Recov	Draw Down	Results of Well	Volume Placed	ed	lar Space Sealant Use	Annula Type of Se	and an average	et at (m/ft)	Depth Se
0       5.4       5.4       5.4       7.6       th2 space       1         5.4       7.6       th2 space       1         1       1       1       1         1       1       1       1         1       1       1       1         1       1       1       1         1       1       1       1         1       1       1       1         1       1       1       1         1       1       1       1         1       1       1       1         1       1       1       1         1       1       1       1         1       1       1       1         1       1       1       1         1       1       1       1         1       1       1       1       1         1       1       1       1       1         1       1       1       1       1       1         1       1       1       1       1       1       1         1       1       1       1       1	ater Level Time Wate	Time Water Le	Clear and sand free	(m <sup>3</sup> /ft <sup>3</sup> )	<u> </u>	and Type)	(Material a		<u>`</u> סר	From
S.4       7.6       #2 SPAD       L         Image: Status of Construction       Image: Status of Well       Pump intake set at (m/ti)       2         Image: Status of Construction       Image: Status of Well       Pumping rate (lmin / GPM)       3         Image: Status of Well       Image: Status of Well       Dewatering       Image: Status of Well       Image: Status of Well         Image: Status of Well       Other, specify       Image: Status of Well       Image: Status of Well       Image: Status of Well         Image: Status of Well       Open Hole OR Material       Wall       Depth (m/ti)       Recharge Well         Image: Gig/mini Construction Record - Casing       Image: Status of Well       Image: Status of Well       Recharge Well         Image: Gig/mini Construction Record - Casing       Image: Status of Well       Image: Status of Well       Recomment Well         Image: Gig/mini Construction Record - Casing       Image: Status of Well       Recomment Well       Recomment Well         Image: Construction Record - Screen       Image: Status of Well       Image: Status of Well       Recommended pump rate         Image: Construction Record - Screen       Image: Status of Well       Image: Status of Well       Recommended pump rate         Image: Construction Record - Screen       Image: Status of Well       Image: Status of Well       Image: Statu		Static	If pumping discontinued, give reason:	L1		UG	Hacepu	5/8 1	5.4	D
Method of Construction       Well Use         Cable Tool       Diamond       Public       Commercial       Not used         Retary (Conventional)       Jetting       Dormestic       Municipal       Dewatering         Boring       Digging       Inside       Digging       Inside       Municipal       Dewnestic         Minicipal       Dormestic       Municipal       Dewnestic       Municipal       Dewnestic         Material       Diversion       Industrial       Ocoling & Air Conditioning       Inside       Municipal       Depth (m/ti)         Inside       Open Hole OR Material       Wall       Depth (m/ti)       Replacement Well       Recommended pump depth (m/ti)       25         S. DB       PLASTIC       O       Galvanized, Fibreglass, Galvanized, Steel)       Thickness       From       To       Recharge Well       30         Observation and/ored, Material       Material       Depth (m/ti)       Abandoned, other, specify       30       40       50       50         Outside       Material       Depth (m/ti)       Abandoned, other, specify       40       50       50         S. DB       PLASTIC       IO       Galvanized, Steel)       Stot No.       From       To       Please provide a map below follo	1	Level		LI			ND	#2 SA	7.6	5.4
Method of Construction       Well Use         Cable Tool       Diamond       Public       Commercial       Not used         Retary (Conventional)       Detting       Dormestic       Municipal       Dewnestic       Municipal         Boring       Digging       Livestock       Test Hole       Monitoring       Inside       Open Hole OR Material       Open Hole OR Material       Depth (m/ti)       If flowing give rate (l/min / GPM)       15         Inside       Open Hole OR Material       Wall       Depth (m/ti)       Recharge Well       Recommended pump depth (m/ti)       25         Concrete, Plastic, Steel)       Trickness       From       To       Recharge Well       30         S. c>B       PLPSTIC       O       6.1       Dewatering Well       0berstration       30         Construction Record - Screen       Mandoned, other, specify       Abandoned, other, specify       40       50         S. c>B       PLPSTIC       O       6.1       Dewatering Well       Obertarial       0bertarial       40         Observation andored, other, specify       Status of Well       Sol No.       Sol No.       60       10         Disinfected?       Sol No.       From       To       Abandoned, other, specify       40       50		2	Pump intake set at (m/ft)							
Method of Construction       Well Use       Pumping rate (l/min / GPM)       3         Cable Tool       Diamond       Public       Commercial       Not used         Rotary (Conventional)       J sting       Domestic       Municipal       Develating         Boring       Digging       Ilvestock       Test Hole       Monitoring         Motter, specify       Industrial       Construction Record - Casing       Status of Well         Method of Construction Record - Casing       Status of Well       Recommended pump depth (m/ti)       10         Inside       Open Hole OR Material       Wall       Depth (m/ti)       Recommended pump rate       30         Social       PLASTIC       O       6.1       Devalering Well       Sol       30         Method at Depth       Material       Stot No.       From       To       To       Secify       40         Sol       PLASTIC       O       6.1       Devalering Well       Sol       Sol       Sol       Sol       Sol         Outside       Planchoned, other, specify       Stot No.       From       To       Status of Well       Sol	2	2								
□ Cable Tool       □ Diamond       □ Public       □ Commercial       □ Not used         □ Rotary (Conventional)       □ Etiting       □ Domestic       □ Municipal       □ Dewatering         □ Boring       □ Digging       □ Irrigation       □ Cooling & Air Conditioning       □ Inside         □ Other, specify	3	3	Pumping rate (I/min / GPM)	e	Well Us			onstruction	hod of Co	Metl
Dividity (Converse)       Dividing       Dividing <td>4</td> <td>4</td> <td>Duration of pumping</td> <td>rcial Not used</td> <td>Comme</td> <td>Public Domostic</td> <td></td> <td>Diamond</td> <td>ol</td> <td>Cable To</td>	4	4	Duration of pumping	rcial Not used	Comme	Public Domostic		Diamond	ol	Cable To
□ Bring       □ Digging       □ Irrigation       □ Cooling & Air Conditioning         □ Air percussion       □ Other, specify       □       10         □ Other, specify       □       □ Other, specify       10         □ Status of Well       □ Status of Well       □       15         □ Inside       Open Hole OR Material       Wall       Depth (m/lt)       □       Water Supply         □ So & PLASTIC       O       6.1       □       Devalering Well       Recharge Well         □ So & PLASTIC       O       6.1       □       Devalering Well       Well production ( <i>l/min / GPM</i> )       40         ○ Outside       □       □       □       □       Abandoned, Insufficient Supply       0         □ Dianeter       Material       Stot No.       Depth (m/lt)       □       Abandoned, other, specify       0         □ Outside       Material       Stot No.       Depth (m/lt)       □       Abandoned, other, specify       0         □ So & PLASTIC       Io       6.1       7.6       0       0       0       0         □ So & Other, specify       □       Stot No.       Depth (m/lt)       □       Abandoned, other, specify       0       0         □ So & Other, specify	5	5	hrs + min	e Dewatering	Test Hol	Livestock			Reverse)	Rotary (F
Other, specify       Other, specify       15         Construction Record - Casing       Status of Well         Inside       Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)       Wall       Depth (m/ti)         Thickness       From       To       Test Hole         S. c. B       PLPSTIC       O       6.1       Devatering Well         Outside       Outside       Alteration       Alteration       40         Disinfected?       Outside       Depth (m/ti)       Abandoned, Insufficient Supply       Well production (l/min / GPM)       50         Outside       Material (Plastic, Galvanized, Steel)       Slot No.       Depth (m/ti)       Abandoned, Insufficient Supply       Abandoned, other, specify       Please provide a map below following instruction         S. 3       PLASTIC       IO       6.1       7.6       Other, specify       Status of Well       Status of Well         Water found at Depth       Kind of Water:       From       To       Diagneter from       Other, specify       Status of Well       Status of Well         Water found at Depth       Kind of Water:       Fresh       Untested       Depth (m/ti)       Diagneter from       Diagneter from       Construction	10	10	Final water level end of pumping (m/ft)	& Air Conditioning	Cooling	Irrigation Industrial	International In	Digging	ission	Boring
Construction Record - Casing       Status of Well         Inside Digmeter (Galvanized, Steel)       Wali       Depth (m/ti)       Water Supply         S. 0.8       PLASTIC       0       6.1       Test Hole         S. 0.8       PLASTIC       0       6.1       Devatering Well       25         S. 0.8       PLASTIC       0       6.1       Devatering Well       26         Outside       Alteration       Construction Record - Screen       0       0.1       9         Outside       Material       Depth (m/ti)       Abandoned, Insufficient Supply       Well production (l/min / GPM)       40         Solution       Depth (m/ti)       Depth (m/ti)       Devatering Well       0       40         Outside       Material       Depth (m/ti)       Abandoned, Insufficient Supply       Map of Well Location         Solution       From       To       Depth (m/ti)       Abandoned, other, specify       Solution (l/min / GPM)       60         Diameter       Material       Ion of the specify       Depth (m/ti)       Depth (m/ti)       SEE       Abandoned, other, specify         S.3       PLASTIC       IO       6.1       7.6       Other, specify       SEE       SEE         Water found at Depth	15	15	If flowing give rate (Vmin / GPM) 1		ify	Other, specif	_ 🗌 Ot		pecify	Other, sp
Diameter (Galvanized, Fibreglass, Concrete, Plastic, Steel)       Thickness (cmvin)       Depth (mv)       Replacement Well       Recharge Well         5.08       PLPSNL       0       6.1       Recharge Well       Recharge Well       30         0       Well production ( <i>lmin / GPM</i> )       0       40       40       40         0       0       Abandoned, Insufficient Supply       0       60       40         0       0       Abandoned, Insufficient Supply       0       60       60         0       Material (Plastic, Galvanized, Steel)       Slot No.       Pepth (mv)       0       Abandoned, other, specify       Please provide a map below following instruction         5.3       PLASTIC       10       6.1       7.6       0       0       SEE ATTTACH         Water found at Depth       Kind of Water:       From       To       Depth (mv)       Diagneter from       0       Diagneter from       Other, specify       SEE ATTTACH	20	20	Recommended pump depth (m/ft)	Status of Well	)enth (m/ft)	asing	ecord - Ca	onstruction R	Co Open Ho	Inside
Store       PLASTIC       O       6.1       Becharge Well       Recharge Well       Becharge Well       30         Dewatering Well       Dewatering Well       Observation and/or       Monitoring Hole       40       50         Outside       Alteration       Construction       Alteration       60       50         Outside       Material       Depth (m)t)       Abandoned, Nature Quality       60       60         Sold No.       From       To       Abandoned, other, specify       Stot No.       From       From       To         Sold No.       From       To       Other, specify       Other, specify       Stot No.       Stot No.       Stot No.       Stot No.       From       To         Sold No.       From       To       Other, specify       Other, specify       Stot No.       Stot	25	25		Replacement Well	n To	s From	Thickness	zed, Fibreglass,	(Galvaniz	Diameter (cm/in)
S.OG       10PS IIC       O       6-1       Dewatering Well       Well production ( <i>Imin / GPM</i> )         Observation and/or Monitoring Hole       Alteration (Construction)       Alteration (Construction)       Please provide a map below following instruction         Outside Diameter (Plastic, Galvanized, Steel)       Slot No.       Depth ( <i>M</i> )       Depth ( <i>M</i> )       Please provide a map below following instruction         5.3       PUASTIC       10       6.1       7.6       Other, specify         State found at Depth       Kind of Water:       Fresh       Untested       Depth ( <i>m</i> )       Diameter found at Depth       SEE       ATTTACH	30	30	Recommended pump rate	Test Hole     Recharge Well	( )		(citrin)	Dr.	DIGO	6 -0
Outside     Material     Depth (mit)       0utside     Material       Diameter     Slot No.       From     To       S.3     PLASTIC       10     6.1       7.6     Other, specify	40	40		Dewatering Well	6.1				100	2.00
Outside     Material     Depth (m)t)     Abandoned, lnsufficient Supply       Outside     Material     Depth (m)t)       Plastic, Galvanized, Steel)     Slot No.     From       To     Abandoned, other, specify       S.3     PLASTIC     10       Water Detailis     Hole Diameter       Water found at Depth     Kind of Water:       (m/th)     Gas	50	50	Well production (Vmin / GPM)	Monitoring Hole	_					
Outside       Material       Construction Record - Screen       Abandoned, Insufficient Supply         Outside       Material       Image: Solution of Weill Location         Diagreter       Plastic, Galvanized, Steel)       Slot No.       Depth (mit)         5.3       PLASTIC       IO       6.1       7.6         Other, specify       Other, specify       Other, specify       Steel         Water Details       Hole Diameter       Diagneter         (m/ft)       Gas       Other, specify       Diagneter		60	Disinfected?	Alteration (Construction)						
Construction Record - Screen       Map of Well Location         Outside Diageter (Plastic, Galvanized, Steel)       Slot No.       Depth From       Depth To       Abandoned, Poor Waler Quality       Please provide a map below following instruction         5.3       PLASTIC       10       6.1       7.6       Other, specify       Depth (m)t)	00			Abandoned, Insufficient Supply					-	1951 1912 1913
Diagneter (Plastic, Galvanized, Steel)     Slot No.     From     To     Abandoned, other, specify       5.3     PLASTIC     10     6.1     7.6     Other, specify       Water Details     Hole Diameter     Other, specify     Other, specify       Water found at Depth     Kind of Water:     Fresh     Untested       (m/ft)     Gas     Other, specify     Diameter	on ions on the back.	g instructions or	Map of Well L Please provide a map below following in	Abandoned, Poor Water Quality	epth (77)	Creen	ecord - Sci	Anterial	Co	Outside
5.3     PLASTIC     10     6.1     7.6     Other, specify       Water Details       Water Details       Water Details       Hole Diameter       Water Tound at Depth       (m/ft)       Gas       Other, specify				Abandoned, other,	То	From	Slot No.	alvanized, Steel)	(Plastic, Ga	Diameter (cm/jn)
Water Details     Hole Diameter       Water found at Depth Kind of Water:     Fresh Untested Depth (m/ft)					7.6	61	10	TIC	DIAST	53
Water Details     Hole Diameter       Water found at Depth (m/ft)     SEE       (m/ft)     Gas				Other, specify			,-		19.0	0.0
Water found at Depth Kind of Water: Fresh Untested Depth (m)(1)   Diameter (m)(1)	JED LIAD	TACILE	SEC MET	ole Diameter	н		ails	Water Det	i Marajar	Participante de la composition de la co
(m/t) Gas Other, specify	TO MIT	ITTLACT.	UCE AII	h (m/ft) Diameter	ted Dept		: Fresh	Kind of Water	d at Depth	Water found
Water found at Denth Kind of Water: Eresh Ulptested	\$			7.10 12	ted A		Cify	Kind of Water	n/ft) ⊡Gas	(m Water four
( <i>m/ft</i> ) GasOther, <i>specify</i>							cify	Other, spe	u/ft) ⊡Gas	(m
Water found at Depth Kind of Water: Fresh Untested					ted	Untest	: Fresh	Kind of Water:	d at Depth	Water found
(m/n)GasOther, specify							cify	∐Other, spe	u/tt) ∐Gas	(m.
Bi ance No.				ance No.	(#1)					iii Bi
CMT Drilling Inc. License No. 7366				. 7366	cense No	Lic	nc.	Drilling In	CMT D	C
1011 Industrial Cres, Unit 1, St. Clements			Comments:	ments	St. Cle	Unit 1.	Cres, U	dustrial (	011 In	1
Pi Ontario, NOB 2M0 cblack@cmtinc.net				nc.net	ck@cmti	chlac	M0	, NOB 21	Ontario	ν C
Biack Chrise Well owner's Date Package Delivered	Ministry Use Only	A AL	Well owner's Date Package Delivered information		c Chria	Black		9-5775	19-690	- - -
$\begin{array}{c c} 3711 \\ $		Audit No	delivered Y Y Y M M D I	2	, CIII15	DIAUK	200		711	
W J/II Z020/02/25 Pers Date Work Completed	43245	Audit No.	- I loto Mork Completed	100	2020/0	-	ne	U I	/11	

	ients recor	ded in: 🚺	Metric 🗌	Imperial	A28	3260	5			Page	1	of
Well Ow	ner's Info	ormation			a tangan s							
First Name	DISCO		Last Name /	Organizatio	on Os kara ak	-0		E-mail Address	8 N.		Well by W	Cons ell Ov
Mailing Ad	dress (Stree	t Number/Nar	ne)	JAA, V	HNCOSVI	Municipality	WESTER	Province Postal Code		Telephone	No. (inc.	area
2188 Well Loc	ROBIN	INCOD C	OURT	igaalaa ka shi		UISSIS	SAUGA	ON LISMS	IBM1			(CSA)
Address of	Well Locati	on (Street Nur	mber/Name)	1011-555,000		Township		Lot	0	Concession	n	1000
NINTI County/Dis	4 UNE	(SOOM	SE OF	BURHAN	ATHORPE	City/Town/V	) /illage		Provinc	се	Posta	Co
						GAKU	ue		Onta	ario		
UTM Coord NAD	linates Zon	e Easting		orthing	3118	Municipal P	lan and Sublo	t Number	Other			
Overburd	en and Be	drock Materi	ials/Abando	onment Se	ealing Reco	ord (see ins	tructions on th	e back of this form)				
General C	olour	Most Comr	mon Material		Ot	ner Materia	ls	General Description			Dep From	th (n
BLACK		TOPSO									0	C
BROW	N	CLAN		5	SILT			DENSE			0.3	1
GREY		SILT			LA-			DENSE			1.5	+
GREA		SILT						DENSE			4.9	+
												+
												-
												-
	4											
			Annular	Space		a ga sari	1944 1944	Results of W	ell Yield	1 Testing	(1) (1) (1) (1)	
Depth S From	et at (ħ7/ft)		Type of Sea (Material ar	alant Used nd Type)		Volum	ne Placed n³√ft³)	After test of well yield, water was:	Dra Time	aw Down Water Leve	R I Time	ecov Wat
0	4.5	318 1	the COLUC			4	<i>J</i> ′	Other, specify	(min)	(m/fi)	(min)	(
4.5	67	₩2 S	AND	_		4		If pumping discontinued, give reason:	Level			
				8				Dump intoko oot ot (m#)	1		1	
								Pump make set at (mm)	2		2	
Met	nod of Co	nstruction			Well Us	ie		Pumping rate (Vmin / GPM)	3		3	
Cable To	ol			blic	Comme	rcial	Not used	Duration of pumping	4		4	
Rotary (F	<pre>verse)</pre>			estock	Test Hol		Monitoring	hrs + min	5		5	
Air percu	ssion			gation Iustrial		& Air Conditi	oning	Final water level end of pumping (m/tt)	10		10	
Other, sp	ecify			ner, specify		1 04-44	6 10/- 11	If flowing give rate (Vmin / GPM)	15		15	
Inside	Open Hol	e OR Material	Wall	Dept	h (17)	Water	Supply	Recommended pump depth (m/ft)	20		20	
Diameter (cm/in)	(Galvanize Concrete,	d, Fibreglass, Plastic, Steel)	Thickness (cm/in)	From	То	Replace	cement Well lole		25		25	
5.08	PLAS	Γiς,		0	5.1	Recha	arge Well	(I/min / GPM)	30		30	
						Obser	vation and/or	Well production (I/min / GPM)	40		40	
							tion	Disinfected?	50		50	
						Aband	loned,	Yes No	60		60	
10 2		nstruction R	ecord - Scr	een		Insuffic	cient Supply loned, Poor	Map of We	ell Loca	ation	ho hr -	
	Co	aterial	Slot No.	Dept From	h (@)\$)   To	Water	Quality loned, other,	riease provide a map below followin	ng instru	ICUONS ON t	ne back	•
Outside Diameter	Co Mi (Plastic, Ga	Ivanized, Steel)			1	specify	v I					
Outside Diameter (Thin)	Co Mi (Plastic, Ga	Ivanized, Steel)	10	51	167			SEG DT	mail	ED L	IPP	
Outside Diameter (Thy) 5.3	Co M (Plastic, Ga PLAST	Ivanized, Steel)	10	5.1	6.7	Other,	specify	OLC HII	HAH			
Outside Diameter (The second s	Co M (Plastic, Ga PLAST	Water Det		5.1	6.7		specify	OCC HI	PLH			
Outside Diameter (Min) 5.3 Water foun	Co M (Plastic, Ga PLAST J at Depth	Water Det	\O ails : □Fresh [	5. j	6.7 H	lole Diame	specify eter Diameter	OLC HI	PLA			
Outside Dianeter (The provide the second S. 3 Water foun (7 Water foun	Co M (Plastic, Ga PLASI J at Depth /ft) _Gas	Water Det Kind of Water	\O ails : □Fresh [ ccify; : □Freeh [		6.7 Dept From	lole Diame	specify eter Diameter (cm/n)	OCC AT				
Outside Diameter (Thy) 5.3 Water foun (n Water foun (m	Co M (Plastic, Ga PLAS J at Depth /ft)Gas J at Depth /ft)Gas	Water Det         Water Det         Kind of Water         Other, spe         Kind of Water         Other, spe         Kind of Water         Other, spe	AD ails : _ Fresh [ .ccify	5. ] ] Untested	6.7 Depi From	Iole Diame	specify Diameter (cm/n)					
Outside Diameter (mm) 5.3 Water foun ( <i>n</i> Water foun ( <i>m</i> Water foun	Co M (Plastic, Ga PLASI J at Depth /fl)Gas J at Depth /fl)Gas J at Depth /fl)Gas	Water Det Kind of Water Other, spe Kind of Water Other, spe Kind of Water Other, spe	\O ails : □Fresh [ ccify : □Fresh [ ccify_ : □Fresh [	S. ] Untested	6.7 Depi From	lole Diame	specify ster Diameter (cm)(n) 1/2	OCC AT				
Outside Diameter (Fff)) 5.3 Water foun (m Water foun (m Water foun (m 7	Co M (Plastic, Ga DLASS J at Depth //1) □Gas J at Depth //1) □Gas J at Depth //1) □Gas	Water Det Kind of Water Other, spe Kind of Water Other, spe Kind of Water Other, spe	\0 ails :Fresh [ ccfy	S. ] Untested	6.7 Pept From	lole Diame	specify Diameter (m/n) 1/2	OCC AT	( P\$_{(			
Outside Dianeter (The provide the provided the pro	Co M (Plastic, Ga PLASI j at Depth //1)Gas j at Depth //1)Gas j at Depth //1)Gas	Water Det Kind of Water Other, spe Kind of Water Other, spe Kind of Water Other, spe	\O ails : _ Fresh [ ccify	5.1 Untestee Untestee	6.7 Depi From	lole Diame h (1) 6.7	specify Diameter (m/n) 1/2 cence No.					
Outside Diameter (mm) 5.3 Water foun (m Water foun (m Water foun (m	Co M (Plastic, Ga PLASI d at Depth //fl)Gas j at Depth //fl)Gas j at Depth //fl)Gas j at Depth //fl)Gas	Water Det Kind of Water Other, spe Kind of Water Other, spe Kind of Water Other, spe Ling Inc.	\O ails : Fresh [ icify	5.1 Untested Untested	6.7 Dept From O	lole Diame h (1) 7366 ents	specify Diameter (cm)n) V2. cence No.	Comments:				
Outside Diameter (m) 5.3 Water foun (m) Water foun (m) Water foun (m) (m) (m) (m) (m) (m) (m) (m) (m) (m)	Co M (Plastic, Ga PLASS d at Depth //1) _Gas d at Depth //1) _Gas f at Depth //1) _Gas f T Dril [1 Indu	Water Def Kind of Water Other, spe Kind of Water Other, spe Kind of Water Other, spe Ling Inc. Istrial Cr	\O rails : □Fresh [ icify : □Fresh [ cify cify	Untested	6.7 Depi From See No. '	Iole Diame h (1) To 6.7 7366 ents	specify	Comments:				
Outside Diameter (min) 5.3 Water foun (n Water foun (n Water foun (n (n (n) (n) (n) (n) (n) (n) (n) (n)	Co M (Plastic, Ga PLAS d at Depth //1)Gas d at Depth //1)Gas d at Depth //1)Gas d at Depth //1)Gas d at Depth //1)Gas	Water Det Kind of Water Other, spe Kind Other, spe Kind of Water Other, spe Kind of Water Other, spe Kind of Water Kind Other, spe Kind Other, spe	Image:	Untestee	6.7 Depi From O See No. 7 t. Clem	Iole Diame h (1) To b (2) To b (2) To to the Diame To to the Diame To to the Diame To to to the Diame To to to to to to to to to to to to To to to To To to To To To To To To To To To To To To To	specify Diameter (m/n) 1/2 cence No.	Comments:		Minis	try Use	On
Outside Diameter (m) 5.3 Water foun (m Water foun (m Water foun (n (m) (n) (m) (n) (n) (m) (m) (n) (n) (n) (n) (n) (n) (n) (n) (n) (n	Co M (Plastic, Ga PLAST d at Depth //fl)Gas d at Depth //fl)Gas d at Depth //fl)Gas d at Depth //fl)Gas d at Depth //flGas d at Depth //fl	Water Det         Mater Det         Kind of Water         Other, spe         Kind of Water         Kind of Water         Other, spe         Kind of Water         Strigger         Kind of Water         Kind o	\0 ails : Fresh [ ccify	Untestee	6.7 Dept From See No. 7 t. Clem	Iole Diame h m To 6.7 7366 ents c.net	specify Diameter (cm)(n) V2 cence No.	Comments:		Minis Audit No. Z	try Use	Or
Outside Diameter (m) 5.3 Water foun (m) Water foun (m) Water foun (m) Utside (m) (m) (m) (m) (m) (m) (m) (m) (m) (m)	(Plastic, Ga (Plastic, Ga (	Water Det Kind of Water Other, spe Kind of Water Other, spe Kind of Water Other, spe Kind of Water Other, spe Ling Inc. Istrial Cr VOB 21M0 5775	\O ails : □Fresh [ ccify : □Fresh [ ccify : □Fresh [ ccify cres, Uni 0 <u>cl</u> B]	Untested Untested Untested Licens t 1, S <u>black(a</u> lack, C	b.7 Depi From See No. ' t. Clem Chris	other, in	specify  ter  Diameter (cm/n)  V2  cence No.	Well owner's information package delivered y   y   y   y   M   M       Yes		Minis Audit No. Z	try Use 324	on ] 5

					L FIZO	2000							
Well Ow First Name	ner's Info	ormation	Last Name /	Organizatio	'n		1999 - 1999 1997 - 1997 1997 - 1997	E-mail Ac	Idress				Constr
THE I	NOCESE	OFMIS	SISSAUC	A, VA	NCOUVE	R AND	WESTER	N CANADA	ATTN' MOHE	B MI	HAEL	by W	ell Owr
Mailing Add	dress (Strei	et Number/Na	me)	,		Municipality	116.0	Province	Postal Co	de SIRIA	Telephone	e No. (inc.	. area c
Well Loca	ation		OURI			M(33133)	HUGIN	100					
Address of	Well Locat	ion (Street Nu	mber/Name)	2) 1110		Township -			Lot		Concessi	on	
County/Dis	strict/Munici	pality	ADRPE R	DJ NINI	IN CINE	City/Town/Vill	lage			Provir	nce	Posta	I Code
UTM Coord	dinates Zor	e Easting	, N	orthing		Municipal Pla	an and Sublo	ot Number		Offer	al 10		
NAD	831	76041	1804	18/19	363						ALC: NO.	ALC: NO. ALC: NO.	ALL AND DESIGN
General C	olour	Most Com	mon Materia	onment Se	ot	her Materials	uclions on th	e back of this for	m) General Description	on		Dep	oth (m/h
BROW	N)	TEPSOL										0	0.
BRaun	2	CLA-I			SIST			D	ENSE			03	2.3
GREI		CLA-1			SILT			D	nse			2.3	4.4
GRE-1		SAND			SILT			D	ENSE			45	7.
	una la contra		Annula	Space					Results of V	Nell Yiel	d Testino	1	
Depth Se	et at (htt)	1. (* 1. a.	Type of Se	alant Used	nd in the second	Volume	Placed	After test of we	ell yield, water was:	Dr	aw Down	R	ecover
0	51	3/4 1					<u></u>	Other, sp	ecify	(min)	(m/ft)	(min)	(m/i
0	0.1	10 r	ULPLU	9				If pumping dis	continued, give reaso	n: Level			
CI	210	#2	Chi D					11					
5.1	7.6	#2 :	SAND			LI				1		1	
5.1	7.6	#2 :	SAND					Pump intake s	et at <i>(m/ft)</i>	1		1 2	
<u>5</u> . \ Meth	7.6	#2 :	SAUD		Well Us	j L j		Pump intake s Pumping rate	et at (m/ft) (//min / GPM)	1 2 3		1 2 3	
5. \ Meth	A.G.	#2 a		blic	Well Us	Se rrcial	Not used Dewatering	Pump intake s Pumping rate	et at (m/ft) (//nin / GPM) mping	1 2 3 4		1 2 3 4	
S. \ Meth Cable To Mctary (C Rotary (C Boring	hod of Co ol Conventional Reverse)	→ + 2 ±		blic mestic restock cation	Well Us	se ercial le & Air Condition	Not used Dewatering Monitoring	Pump intake s Pumping rate Duration of pu hrs +	et at (m/ħ) (//min / GPM) mping minmin	1 2 3 4 5		1 2 3 4 5	
	hod of Co nol Conventional Reverse)			blic mestic restock gation dustrial best encocific	Well Us Comme Municip Test Ho Cooling	se ercial la le & Air Condition	Not used Dewatering 'Monitoring ning	Pump intake s Pumping rate Duration of pu hrs + Final water lev	et at (m/ft) (/min / GPM) mping min el end of pumping (m/	1 2 3 4 5 (71) 10		1 2 3 4 5 10	
S. \ Cable To Wr Rotary (F Boring Air percu Other, sp	hod of Co hol Conventional Reverse)	the 2 second seco	SAND d   Pu   Do   Liv   Ini   Ini   Case Record - Case	blic mestic restock gation Justrial her, <i>specify</i>	Well Us Comme Municip Test Ho Cooling	Se rrcial la le Status	Not used Dewatering 'Monitoring ning of Well	Pump intake s Pumping rate Duration of puhrs +	et at (m/ft) (//min / GPM) mping min el end of pumping (m/ rate (l/min / GPM)	1 2 3 4 5 70) 10 15		1 2 3 4 5 10 15	
S. \       Meth       Cable To       Lable To       Lable To       Lable To       Air percu       Other, sp       Inside       Diameter	A-G hod of Co ol conventional Reverse) sssion Deerify Co Open Ho (Galvanic)	the C and C a	d Pu d Pu d Int int eccord - Cas Wall Thickness	blic omestic restock gation Justrial her, <i>specify</i> _ <b>sing</b> Depti	Well Us Comme Municip Test Ho Cooling	Se rcial ral le 2 Status Status Dentes	Not used Dewatering Monitoring ning of Well Supply smart Woll	Pump intake s Pumping rate Duration of puhrs +Final water lev If flowing give i Recommende	et at (m/ft) (/min / GPM) mping min el end of pumping (m/ rate (//min / GPM) d pump depth (m/ft)	1 2 3 4 5 70) 10 15 20 25		1 2 3 4 5 10 15 20	
S. 1 Cable To Cable To Cable To Cable To Actary (F Boring Air percu Other, sp Other, sp Diameter (Trijn)	A.G       hod of Co       hod of Co       col       Conventional       Reverse)       ussion       becity       Co       Open Hol       (Galvaniz)       Concrete,		d Pu d Pu d Do Liv lim lim lin co Vall Thickness (cm/in)	bilc mmestic estock gation Justrial her, <i>specify</i> sing  From	Well Us           □ Comme           □ Municip           □ Test Ho           □ Cooling	se al   k Air Condition Status Water S Replace Test Hol	Not used Dewatering 'Monitoring ning of Well Supply sment Well le	Pump intake s Pumping rate Duration of pu hrs + Final water lev If flowing give i Recommende Recommende	et at (m/ft) (/min / GPM) mping min el end of pumping (m/ rate (l/min / GPM) d pump depth (m/ft) d pump rate	1 2 3 4 5 7 7 7 7 7 10 15 20 25 20		1 2 3 4 5 10 15 20 25	
S. \ Meti Cable To Mctary (C Boting Boring Air percu Other, sp Diameter (∰) S. CS	A-Co hod of Co ol Conventional Reverse) sssion pecify Open Ho (Galvaniz Concrete, PLA:		d Pu d Pu d Do Liv lin d Ini cou Wall Thickness (cm/in)	blic mestic essock gation tustrial her, specify _ sing Depti From	Well Us           Comme           Municip           Test Ho           Cooling           To           To           6_1	se al al a	Not used Dewatering Monitoring ning of Well Supply ement Well le ge Well ring Well	Pump intake s Pumping rate Pumping rate Duration of puhrs +	et at (m/ti) (//min / GPM) min el end of pumping (m/ rate (l/min / GPM) d pump depth (m/ti) d pump rate	1 2 3 4 5 7 7 10 15 20 25 30		1 2 3 4 5 10 15 20 25 30	
5.1       Meth       □ Cable To       1/ Rotary (C       □ Rotary (F       □ Boring       □ Air percu       □ Other, sp       □ Inside       Diameter       (m)       5.08	P.40       hod of Co       hol       conventional       Reverse)       ission       peedfy       Co       Open Hol       (Galvaniz)       Concrete,       PLAS	the C state of the state	d Pu d Du Liv Im Bu Court Record - Cas Wall Thickness (cm/in)	blic imestic gation lustrial her, specify Sing Depti From	Well Us           □ Comme           □ Municip           □ Test Ho           □ Cooling           h (m)n)           To           - \	se ercial	Not used Dewatering 'Monitoring ning of Well Supply ament Well le ge Well ring Well ation and/or ing Hole	Pump intake s Pumping rate Duration of pu hrs + Final water lev If flowing give i Recommende ( <i>l/min / GPM</i> ) Well productio	et at (m/ft) (/min / GPM) mping min el end of pumping (m/ rate (/min / GPM) d pump depth (m/ft) d pump rate n (/min / GPM)	1 2 3 4 5 10 15 20 25 30 40		1 2 3 4 5 10 15 20 25 30 40	
S. \ Cable To Cable To Cable To Cable To Actionary (f Boring Darreter Diameter () 5. CS	A.G       hod of Co       ool       Conventional       Reverse)       sssion       pecify       Co       Open Hoi       (Galvaniz       Concrete,       PLAN		d Pu d Pu d Do Liv Ini d Ini ot tecord - Cas Wall Thickness (cm/in)	blic mestic restock gation tustrial her, specify _ Sing Depti From	Well Us           Comme           Municip           Test Ho           Cooling           (m/n)           To           6 - 1	Se al al Be Status Status Status Status Replace Test Hol Recharg Observa Monitori Alteratio	Not used Dewatering 'Monitoring ning of Well Supply ement Well le ge Well ation and/or ing Hole on uction)	Pump intake s Pump intake s Pumping rate Duration of puhrs +	et at (m/ft) (l/min / GPM) mping min et end of pumping (m/ rate (l/min / GPM) d pump depth (m/ft) d pump rate n (l/min / GPM)	1 2 3 4 5 10 15 20 25 30 40 50 60		1 2 3 4 5 10 15 20 25 30 40 50	
S. \       Meth       □ Cable To       \u03c4 Cotary (C       □ Rotary (F       □ Boring       □ Air percu       □ Other, sp       □ Inside       □ Diameler       (m)n)       S. C &	P.6       hod of Co       hol       Conventional       Reverse)       ission       Conventional       Conventional       Conventional       Open Hol       (Galvaniz)       Conventional       PLAY		d Pu Dic Liv Infi Ot Record - Cas Wall Thickness (cm/in)	blic imestic gation lustrial her, specify _ From C	Well Us           Comme           Municip           Test Ho           Cooling	See ercial al & Air Condition & Air Condition Bewaters Beplace Test Hol Recharg Dewaters Dewaters Monitori Alteratio (Constrin Alteratio (Constrin Alteratio (Constrin Alteratio (Constrin Alteratio (Constrin Alteratio (Constrin Alteratio (Constrin Alteratio (Constrin Alteratio (Constrin Alteratio (Constrin Alteratio (Constrin Alteratio (Constrin Alteratio (Constrin Alteratio (Constrin Alteratio (Constrin	Not used Dewatering Monitoring ning of Well Supply ement Well le ge Well ation and/or ing Hole on uction) ned, ent Supply	Pump intake s Pumping rate Pumping rate Duration of puhrs + Final water lev If flowing give i Recommende Recommende (Umin / GPM) Well productio Disinfected?Yes	et at (m/ft) (/min / GPM) mping min el end of pumping (m/ rate (/min / GPM) d pump depth (m/ft) d pump rate n (/min / GPM) No	1 2 3 4 5 77) 10 15 20 25 30 40 50 60	ation	1           2           3           4           5           10           15           20           25           30           40           50           60	
S. \ Metri Cable To Wr Rotary (C Boring Air percu Other, sp Diameter () S. C.S. Outside Diameter	A-Co hod of Co ol Conventional Reverse) ssion Decify Co Open Ho (Galvaniz Concrete, PLAS Co Co M		d Pu d Pu d Do Liv lim lim d Int d Ol Wall Thickness (cm/in)	blic mmestic estock gation lustrial her, specify sing Dept1 From C	Well Us           Comme           Municip           Test Ho           Cooling	se al al al bl bl construction constr	Not used Dewatering 'Monitoring ning of Well Supply ement Well le ge Well ation and/or ing Hole on uction) ned, ent Supply ned, Poor Quality	Pump intake s Pump intake s Pumping rate Duration of pu Ins + Final water lev If flowing give i Recommende Recommende (//min / GPM) Well productio Disinfected? Yes Please provid	et at (m/ft) (l/min / GPM) mping min el end of pumping (m/ rate (l/min / GPM) d pump depth (m/ft) d pump rate n (l/min / GPM) No Map of V e a map below follow	1           2           3           4           5           10           15           20           25           30           40           50           60           Well Loce	ation	1           2           3           4           5           10           15           20           25           30           40           50           60	
S. N Metil Cable To La Cable To La Cable To La Cable To La Cable To La Cable To La Cable To Densite Diameter (Trijn) Outside Diameter (Trijn)	A.G       hod of Co       ol       conventional       Reverse)       sssion       pecify       Co       Open Hol       (Galvaniz       Concrete,       PLA*       Co       M       (Plastic, Gal		SAND	blic imestic gation lustrial her, specify _ From C Depti From Depti From	Well Us           Comme           Municip           Test Ho           Cooling           m(mn)           To           6.1           m(mn)           To           M(mn)           To	se al al al & Air Condition & Air Condition & Air Condition & Replace Test Hol Replace Constru- Monitori Alteratio (Constru- Abandon Valer Q Abandon Valer Q Abandon Specify	Not used Dewatering 'Monitoring ning of Well Supply ement Well le ge Well ation and/or ing Hole on uction) ned, ent Supply ned, Poor Quality ned, other,	Pump intake s Pump intake s Pumping rate Duration of puhrs + Final water lev If flowing give t Recommende ( <i>l/min / GPM</i> ) Well productio Disinfected? Yes Please provid	et at (m/ti) (//min / GPM) mping min el end of pumping (m/ rate (//min / GPM) d pump depth (m/ti) d pump rate n (//min / GPM) No Map of N e a map below follow	1 2 3 4 5 70 10 15 20 25 30 40 50 60 Well Loc	ation uctions on	1       2       3       4       5       10       15       20       25       30       40       50       60	
S. N Cable To Qable To Qable To Qable To Air percu Other, sp Diameler (@m) S. CC Outside Diameler (@m) S. 3	PCo       hod of Cc       ol       Conventional       Reverse)       sssion       pecify       Co       Open Hol       (Galvaniz       Concrete,       PLAS	# 2       Important Control       Important       Important Control </td <td>d Pu d Do Liv lini lini cord - Cas Wall Thickness (cm/in) cecord - Scr Slot No.</td> <td>bilc mestic restock gation fustrial her, specify _ From C C C C C C C C C C C C C C C C C C C</td> <td>Well Us           Comme           Municip           Test Ho           Cooling           (mm)           To           6.1           """"""""""""""""""""""""""""""""""""</td> <td>Status Status St</td> <td>of Well Supply ement Well le ge Well ation and/or ing Hole on uction) ned, Poor buality ned, Poor buality ned, other, pecify</td> <td>Pump intake s Pump intake s Pumping rate Duration of punrs +</td> <td>et at (m/ft) (l/min / GPM) mping min el end of pumping (m/ rate (l/min / GPM) d pump depth (m/ft) d pump rate n (l/min / GPM) No Map of V see a map below follow SEE ACTT</td> <td>1       2       3       4       5       10       15       20       25       30       40       50       60       Well Loc</td> <td>ation uctions on</td> <td>1 2 3 4 5 10 15 20 25 30 40 50 60</td> <td></td>	d Pu d Do Liv lini lini cord - Cas Wall Thickness (cm/in) cecord - Scr Slot No.	bilc mestic restock gation fustrial her, specify _ From C C C C C C C C C C C C C C C C C C C	Well Us           Comme           Municip           Test Ho           Cooling           (mm)           To           6.1           """"""""""""""""""""""""""""""""""""	Status St	of Well Supply ement Well le ge Well ation and/or ing Hole on uction) ned, Poor buality ned, Poor buality ned, other, pecify	Pump intake s Pump intake s Pumping rate Duration of punrs +	et at (m/ft) (l/min / GPM) mping min el end of pumping (m/ rate (l/min / GPM) d pump depth (m/ft) d pump rate n (l/min / GPM) No Map of V see a map below follow SEE ACTT	1       2       3       4       5       10       15       20       25       30       40       50       60       Well Loc	ation uctions on	1 2 3 4 5 10 15 20 25 30 40 50 60	
S · \ Meth Cable To La Cable To Cable To Ar percu Dianeler (m) 5.08 Outside Diameler (m) 5.3	PLAS		d Pu Do Liv Im Ol Record - Cas Wall Thickness (cm/in) Cecord - Scr Slot No.	bilc mestic gation Justrial her, specify From C een C een C bepti From	Well Us           Comme           Municip           Test Ho           Cooling	se al le Status	Not used Dewatering 'Monitoring ning of Well Supply ament Well le ge Well ring Well ation and/or ing Hole on uction) ned, Poor Quality ned, Poor Quality ned, other, pecify	Pump intake s Pumping rate Pumping rate Duration of pu hrs + Final water lev If flowing give I Recommende Recommende ( <i>Vmin J GPM</i> ) Well productio Disinfected? Yes Please provid	et at (m/ft) (/min / GPM) mping min el end of pumping (m/ rate (//min / GPM) d pump depth (m/ft) d pump rate n (//min / GPM) No No SEE ATTT	1       2       3       4       5       10       15       20       25       30       40       50       60       Well Loc	ation uctions on	1 2 3 4 5 10 15 20 25 30 40 50 60 €	
S. \ Metil Cable To Qradie To Qradie To Air percu Other, sp Inside Diameter Carry (Carry (Carry) Other, sp Other, sp Carry (Carry) S. C.C.S. Outside Diameter (Carry) S. 3. Water founce	A LO hod of Co ol Conventional Reverse) sssion recify Co Open Hol (Galvaniz Concrete, PLA Co Co (Plastic, Ga PLA Co Co M (Plastic, Ga Co		d   Pu   Du   Du   Du   Du   Du   Du   Du   D	bilc mestic restock gation fustrial her, specify From  reen  reen  bept  from  bept  bept  from  from  bept  from  from	Well Us           Comme           Municip           Test Ho           Cooling           (mm)           To           (6.1)           (7.6)           (7.6)           (7.6)           Prom           Prom	Status alignment status	Not used Dewatering 'Monitoring ning of Well Supply ement Well le ge Well ation and/or ing Hole on uction) ned, Poor buality ned, Poor buality ned, other, pecify Lignmeter (CmTyn)	Pump intake s Pump intake s Pumping rate Duration of punrs +	et at (m/ft) (l/min / GPM) mping min el end of pumping (m/ rate (l/min / GPM) d pump depth (m/ft) d pump rate n (l/min / GPM) No Map of I SEE ACTO	1       2       3       4       5       10       15       20       25       30       40       50       60       Well Loc	ation uctions on	1 2 3 4 5 10 15 20 25 30 40 50 60 €	
S. \       Metif       □ Cable To       \u03c4 Cable To	P6       hod of Co       co       conventional       Reverse)       sssion       co       Open Hol       (Galvaniz)       Concrete,       PLAS       co       (Plastic, Ge       PLAS       d at Depth       v/ft) □Gas       d at Depth			blic mestic gation tustrial her, specify From C een Depth From C Untested Untested	Well Us           □ Comme           □ Municip           □ Test Ho           □ Cooling           𝑘𝑘)           To           𝑍. \           𝑘𝑘)           To           𝑍. \           𝑘𝑘)           To           𝑍. \           𝑘𝑘)           To           𝑘𝑘           To           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘           𝑘 </td <td>See  recial al le Status Air Condition  Status  Status  Status  Conserved  Air Condition  Replace  Test Hol Recharg  Dewate  Construe  Abandon Specify  Other, sy  Hole Diamett  th (Troft) To</td> <td>Not used Dewatering 'Monitoring ning of Well Supply ament Well le ge Well ring Well ation and/or ing Hole on uction) ned, ent Supply ned, Poor Supply ned, other, pecify is ing Diameter com(n) 12</td> <td>Pump intake s Pumping rate Pumping rate Duration of puhrs +</td> <td>et at (m/ti) (//min / GPM) (//min / GPM) el end of pumping (m/ rate (//min / GPM) d pump depth (m/ti) d pump rate n (//min / GPM) No SEE Matrix</td> <td>1 2 3 4 5 70 10 15 20 25 30 40 50 60 0 Well Loc</td> <td>ation D WP</td> <td>1 2 3 4 5 10 15 20 25 30 40 50 60 €</td> <td></td>	See  recial al le Status Air Condition  Status  Status  Status  Conserved  Air Condition  Replace  Test Hol Recharg  Dewate  Construe  Abandon Specify  Other, sy  Hole Diamett  th (Troft) To	Not used Dewatering 'Monitoring ning of Well Supply ament Well le ge Well ring Well ation and/or ing Hole on uction) ned, ent Supply ned, Poor Supply ned, other, pecify is ing Diameter com(n) 12	Pump intake s Pumping rate Pumping rate Duration of puhrs +	et at (m/ti) (//min / GPM) (//min / GPM) el end of pumping (m/ rate (//min / GPM) d pump depth (m/ti) d pump rate n (//min / GPM) No SEE Matrix	1 2 3 4 5 70 10 15 20 25 30 40 50 60 0 Well Loc	ation D WP	1 2 3 4 5 10 15 20 25 30 40 50 60 €	
S. \     Mett     Cable To     Water founc     (m     Water     founc     (m     Water founc     (m     Wate	P.46       hod of Co       hod of Co       conventional       Reverse)       ission       peerfy       Co       Open Hol       (Galvaniz)       Concrete,       PLAS       co       d at Depth       /ft)       Gas       d at Depth       /ft)       Gas			blic mestic estock gation lustrial her, specify sing Pepti From een een Untested Untested	Well Us           Comme           Municip           Test Ho           Cooling	Status       al       la       la  <	Not used Dewatering 'Monitoring ning of Well Supply ement Well le ge Well ation and/or ing Hole an uction) ned, even uction) ned, even uction) ned, even uction) ned, even uction) ned, other, pecify ier	Pump intake s Pump intake s Pumping rate Duration of pu Ins + Final water lev If flowing give i Recommende Recommende (//min / GPM) Well productio Disinfected? Yes Please provid	et at (m/ft) (l/min / GPM) mping min el end of pumping (m/ rate (l/min / GPM) d pump depth (m/ft) d pump rate n (l/min / GPM) No Map of N e a map below follow SEE ATT	1         2         3         4         5         10         15         20         25         30         40         50         60         Wing instruction	ation uctions on	1 2 3 4 5 10 15 20 25 30 40 50 60 €	
S. \     Meti     Cable To     Water founc     (m)     Cable To     Water founc     (m)     Outside     Diameter     (m)     S. 3	A.G         hod of Co         col         conventional         Reverse)         sssion         pcd         Co         Open Hol         (Gatvaniz         Concrete,         PLAS         data         Plastic, Gat         PLAS         dat         dat         pth         Gas         dat         control         dat         pth         Gas         dat         pth         dat         pth         dat         pth         dat         pth         dat         pth	# 2       a         mistruction       Diamone         Diamone       Diamone         Diamone       Digging         mistruction R       e OR Material ed, Fibreglass, Plastic, Steel)         Still       C         mistruction R       elaterial alvanized, Steel)         Still       C         Material ed, Fibreglass, Plastic, Steel)       Still         Still       C         Material ed, Fibreglass, Steel)       Still         Still       C         Material ed, Steel)       Still         Still       C         Material ed, Steel)       Still         Still       C         Still       C         Still       C         Still       Still         Other, spe       Kind of Water         Other, spe       Kind of Uther, spe         Still       Still       Still	SAND	blic mestic restock gation tustrial her, specify sing Depti From C een Depti From C Untested Untested	Well Us           Comme           Municip           Test Ho           Cooling           (mm)           To           (Gm)	Status       al       al  <	Not used Dewatering 'Monitoring ning of Well Supply ement Well le ge Well ation and/or ing Hole on uction) ned, ever builty ned, Poor builty ned, other, pecify iter Diameter Compn (2	Pump intake s Pump intake s Pumping rate Duration of puhrs +	et at (m/ti) (l/min / GPM) mpingmin el end of pumping (m/ rate (l/min / GPM) d pump depth (m/ti) d pump rate n (l/min / GPM) No Map of V SEE ACTO	1         2         3         4         5         10         15         20         25         30         40         50         60         Well Loc	ation D LLP	1 2 3 4 5 10 15 20 25 30 40 50 60 €	
S. \     Mett     Cable To     Water found     (m)     S. 3	A.6         hod of Co         co         conventional         Reverse)         ussion         co         Open Hol         (Galvaniz)         Concrete,         PLAS         dat Depth         vff)Gass         dat Depth         vff)Gass         dat Depth         vff)Gass			bilc mestic gation Justrial her, specify sing Depti From C een Depti From C Untested Untested	Well Us           Comme           Municip           Test Ho           Cooling	See         al         le         Xatus         Water S         Replace         Test Hol         Recharg         Dewater         Wontori         Alteration         Monitori         Abandoo         Insuffici         Abandoo         Specify         Other, sy	Not used Dewatering 'Monitoring ning of Well Supply ament Well le ge Well ring Well ation and/or ing Hole on uction) ned, Poor Quality ned, Poor Quality ned, other, Diameter Compy (2	Pump intake s Pumping rate Pumping rate Duration of pu hrs + Final water lev If flowing give I Recommende Recommende ( <i>Vmin J GPM</i> ) Well productio Disinfected? Yes Please provid	et at (m/ft) (//min / GPM) mping min el end of pumping (m/ rate (//min / GPM) d pump depth (m/ft) d pump rate n (//min / GPM) No No SEE ATTT	1         2         3         4         5         10         15         20         25         30         40         50         60         Well Loc	ation uctions on	1 2 3 4 5 10 15 20 25 30 40 50 60	
S. N     Mett     Cable To     Water founc     (m     Water     Mater     Mater founc	A.G         hod of Cc         ol         conventional         Reverse)         ssion         biological         Co         Open Hoi         (Galyaniz         Concrete,         PLAT         Concrete,         PLAT         Co         (Plastic, Ga         d at Depth         v/ft) Gas         d at Depth         v/ft         Gas         CMT T	# 2         instruction         Diamone         Stite         Stite         Stite         Instruction R         Interial         Interial         Invariated, Steel)         Tite         Water Dete         Kind of Water         Other, spe         Kind of Water         Other, spe         Diamone         Diamone         Diamone         Diamone	SAND  SAND	blic mestic estock gation lustrial her, specify From C een Depti From C Untested Untested Untested Lice	Well Us           Comme           Municip           Test Ho           Cooling           (mn)           To           (Gn)           (Gn) <tr< td=""><td>Status alignment Status Status</td><td>Not used Dewatering 'Monitoring ning of Well Supply ement Well le ge Well ation and/or ing Hole on uction) ned, Poor Yuality ned, Poor Yuality ned, Poor Yuality ned, other, pecify ier Diameter (myn) 12</td><td>Pump intake s Pump intake s Pumping rate Duration of pu hrs + Final water lev If flowing give i Recommende (<i>l/min / GPM</i>) Well productio Disinfected? Yes Please provid</td><td>et at (m/ft) (l/min / GPM) mping min et end of pumping (m/ rate (l/min / GPM) d pump depth (m/ft) d pump rate n (l/min / GPM) No Map of V SEE ACT</td><td>1       2       3       4       5       10       15       20       25       30       40       50       60       Wing instruction</td><td>ation uctions on</td><td>1 2 3 4 5 10 15 20 25 30 40 50 60 50 60</td><td></td></tr<>	Status alignment Status	Not used Dewatering 'Monitoring ning of Well Supply ement Well le ge Well ation and/or ing Hole on uction) ned, Poor Yuality ned, Poor Yuality ned, Poor Yuality ned, other, pecify ier Diameter (myn) 12	Pump intake s Pump intake s Pumping rate Duration of pu hrs + Final water lev If flowing give i Recommende ( <i>l/min / GPM</i> ) Well productio Disinfected? Yes Please provid	et at (m/ft) (l/min / GPM) mping min et end of pumping (m/ rate (l/min / GPM) d pump depth (m/ft) d pump rate n (l/min / GPM) No Map of V SEE ACT	1       2       3       4       5       10       15       20       25       30       40       50       60       Wing instruction	ation uctions on	1 2 3 4 5 10 15 20 25 30 40 50 60 50 60	
S. \       Metif       □ Cable To       \Lambda Cable To	A.6         hod of Co         ol         conventional         Reverse)         sssion         pcgr         Co         Open Hol         (Galvaniz         Concrete         PLA*         dat Depth         /ft)         Gas         dat Depth         /ft)         Gas         dat Depth         /ft)         Gas         CMTT I         1011 I	# 2       #         Image: Construction       Image: Construction         Im		blic meestic restock gation tustrial her, specify	Well Us           Comme           Municip           Test Ho           Cooling           Image: Cooling	Se al al al al ble Status Status Water S Replace Test Hol Recharg Observer Monitori Alteratio (Construent Abandou Specify Other, sy tole Diamett th (m) To To Construent Abandou Specify Construent Abandou Sectify Construent Abandou Specify Construent Abandou Specify Construent Abandou Specify Construent Abandou Specify Construent Abandou Specify Construent Abandou Specify Construent Abandou Specify Construent Construent Abandou Specify Construent Construent Construent Abandou Specify Construent	Not used Dewatering 'Monitoring ning of Well Supply ement Well le ge Well ation and/or ing Hole on uction) ned, poor builty ned, Poor builty ned, other, ent Supply ned, other, ent Supply ned, other, ent Supply ned, other, ing Hole on uction) ned, poor builty ned, other, ent Supply ned, other, ing Hole on uction) ned, poor builty ned, other, is ent Supply ned, other, is ent Supply ned, other, is ent Supply ned, other, is ent Supply ned, other, is ent Supply is ent Supply ned, other, is ent Supply is ent Supply is ent Supply ing Hole on uction) ned, poor builty ned, other, is ent Supply is ent Suppl	Pump intake s Pump intake s Pumping rate Duration of punrs +	et at (m/ti) (l/min / GPM) mping min el end of pumping (m/ rate (l/min / GPM) d pump depth (m/ti) d pump rate n (l/min / GPM) No SEE ATT	1 2 3 4 5 10 15 20 25 30 40 50 60 Well Loc	ation D L/P	1       2       3       4       5       10       15       20       25       30       40       50       60	
S. \     Mett     Cable To     Cable T	P.60         hod of Co         color         conventional         Reverse)         ussion         perfy         Co         Open Hol         (Galvaniz)         Concrete,         PLAS         dat Depth         vft)         Gas         dat Depth         vft)         Gas         dat Depth         vft)         Gas         CMT I         IO11 I II         Optore:	# 2       2         Image: Construction       Diamone         Diamone       Digging         Image: Construction R       1         Image: Constres       1 <td< td=""><td></td><td>blic mestic gation Justrial her, specify sing Depti From C een Depti From C Untested Untested Untested Licco Junit 1, chlocol</td><td>Well Us           Comme           Municipation           Test Ho           Cooling           (mm)           To           6.1           (mm)           To           6.1           To           6.1           To           7.6           Prom           Co           From           Co           St. Clo           Comments</td><td>Image: Construction of the second of the</td><td>Not used Dewatering 'Monitoring ning of Well Supply ment Well le ge Well ring Well ation and/or ing Hole on uction) ned, Poor Quality ned, Poor Quality ned, other, Diameter comin) (2</td><td>Pump intake s Pumping rate Duration of puns + Final water lev If flowing give I Recommende Recommende (//min / GPM) Well productio Disinfected?Yes Please provid Comments:</td><td>et at (m/ti) (//min / GPM) mping min el end of pumping (m/ rate (//min / GPM) d pump depth (m/ti) d pump rate n (//min / GPM) No Map of N e a map below follow SEE ATT</td><td>1       2       3       4       5       10       15       20       25       30       40       50       60</td><td>ation uctions on</td><td>1 2 3 4 5 10 15 20 25 30 40 50 60</td><td></td></td<>		blic mestic gation Justrial her, specify sing Depti From C een Depti From C Untested Untested Untested Licco Junit 1, chlocol	Well Us           Comme           Municipation           Test Ho           Cooling           (mm)           To           6.1           (mm)           To           6.1           To           6.1           To           7.6           Prom           Co           From           Co           St. Clo           Comments	Image: Construction of the second of the	Not used Dewatering 'Monitoring ning of Well Supply ment Well le ge Well ring Well ation and/or ing Hole on uction) ned, Poor Quality ned, Poor Quality ned, other, Diameter comin) (2	Pump intake s Pumping rate Duration of puns + Final water lev If flowing give I Recommende Recommende (//min / GPM) Well productio Disinfected?Yes Please provid Comments:	et at (m/ti) (//min / GPM) mping min el end of pumping (m/ rate (//min / GPM) d pump depth (m/ti) d pump rate n (//min / GPM) No Map of N e a map below follow SEE ATT	1       2       3       4       5       10       15       20       25       30       40       50       60	ation uctions on	1 2 3 4 5 10 15 20 25 30 40 50 60	
S. \     Mett     Gable To     Ar percu     Diarneter     ()     Gifted     Gifted	A.6         hod of Co         coventional         coventional         Reverse)         sssion         pc/pastic         Co         Open Hol         (Galvaniz         Concrete         PLAS         dat Depth         //f)         Gas         dat Depth         //f)         Gas         dat Depth         //f)         Gas         dat Depth         //f)         Gas         COTT I         1011 Ir         Ontario         510	# 2       2         onstruction       Diamone         Diamone       Diamone         Material       Biterial         Internal       Internal         Internal       Internal <td></td> <td>blic mestic estock gation fustrial her, specify brig Depti From 6. \ Untested Untested Untested Untested Licco Init 1, cblack Black</td> <td>Well Us           Comme           Municip           Test Ho           Cooling           (mm)           To           (6.1)           (7.6)           (7.6)           Prom           Cooling           Cooling           (7.6)           Prom           Cooling           Cooling           St. Clo           (20)           Chris</td> <td>3e         al         al</td> <td>Not used Dewatering 'Monitoring ning of Well Supply ement Well le ge Well ation and/or ing Hole on uction) ned, Poor buality ned, Poor buality ned, Poor buality ned, other, pecify ter Diameter cm/n) t 2_</td> <td>Pump intake s Pump intake s Pumping rate Duration of punrs + Final water lev If flowing give i Recommende (//min / GPM) Well productio Disinfected?Yes Please provid Comments: Well owner's information</td> <td>et at (m/ti) (l/min / GPM) mping min el end of pumping (m/ rate (l/min / GPM) d pump depth (m/ti) d pump rate n (l/min / GPM) No SEE ACTO</td> <td>1       2       3       4       5       10       15       20       25       30       40       50       60       Well Loc       Wing instruction</td> <td>intiana and a second se</td> <td>1       2       3       4       5       10       15       20       25       30       40       50       60</td> <td></td>		blic mestic estock gation fustrial her, specify brig Depti From 6. \ Untested Untested Untested Untested Licco Init 1, cblack Black	Well Us           Comme           Municip           Test Ho           Cooling           (mm)           To           (6.1)           (7.6)           (7.6)           Prom           Cooling           Cooling           (7.6)           Prom           Cooling           Cooling           St. Clo           (20)           Chris	3e         al	Not used Dewatering 'Monitoring ning of Well Supply ement Well le ge Well ation and/or ing Hole on uction) ned, Poor buality ned, Poor buality ned, Poor buality ned, other, pecify ter Diameter cm/n) t 2_	Pump intake s Pump intake s Pumping rate Duration of punrs + Final water lev If flowing give i Recommende (//min / GPM) Well productio Disinfected?Yes Please provid Comments: Well owner's information	et at (m/ti) (l/min / GPM) mping min el end of pumping (m/ rate (l/min / GPM) d pump depth (m/ti) d pump rate n (l/min / GPM) No SEE ACTO	1       2       3       4       5       10       15       20       25       30       40       50       60       Well Loc       Wing instruction	intiana and a second se	1       2       3       4       5       10       15       20       25       30       40       50       60	

•

.





Appendix B

**Stormwater Management Calculations** 

	Project:	Ninth Line					
	Task:	CN Number S	ummary			Prepared by:	T.R.
Burnside	Date:	10-May-23				Project no.:	3000044049
	Land Cover	Crops	Gravel	Lawn	Paved	SWM Pond	
	Soil Group	C/D	C / D	C / D	C / D	C / D	
	CN Number	89.0	96	81.5	98.0	98.0	
Catchment	Total Area	Crops	Gravel	Lawn	Paved	SWM Pond	CN Number
101	3.72	3.72	0.00	0.00	0.00	0.00	89.0
102	0.21	0.21	0.00	0.00	0.00	0.00	89.0
201	0.42	0.00	0.00	0.33	0.09	0.00	85.0
202	3.50	0.00	0.06	1.35	1.85	0.24	91.6



#### Airport Method for Time to Peak Calculations

Natural Area Watershed Information

	r	1					
					Calculated Time of	I ime of Concentration	
	Area	Length	С	Slope	Concentration	Used in Modelling*	Time to Peak
WS	(ha)	(m)		(%)	(min) *	(min) *	(hrs)
EXISTING							
101	3.72	137	0.25	4.90	19.20	19.20	0.19
102	0.21	9.3	0.25	28.00	2.81	15.00	0.15
POST-DEVE	LOPMENT						
201	0.42	10	0.32	25.00	2.78	15.00	0.15

\* Minimum Tc = 15 min as per City standards

NOTE: Time to Peak = 0.60Tc

NOTE: Airport method was selected to calculate the watershed time of concentration as per the MOE Drainage Management Manual (for RC less than 0.4) - see below

#### **Airport Formula**

For watersheds where the runoff coefficient, C, is less than 0.40, the Airport formula gives a better estimate of  $t_c$ . This method was developed for airfields and is expressed as follows:

$$t_{c} = \frac{3.26 * (1.1 - C) * L^{0.5}}{S_{w}^{0.33}}$$
(8.16)

where:

 $t_c$  = time of concentration, min

C = runoff coefficient

 $S_w$  = watershed slope, %

L = watershed length, m

When a watershed length is made up of widely differing surfaces (e.g. grass and concrete),  $t_c$ , can be calculated for each surface, and the individual values summed to give the overall value.

Project:Ninth LineFile:300044049Designed by:T.RosboroughChecked by:S.RoordaDate:10-May-23



### IMPERVIOUS CALCULATIONS - Pre-Development (Catchment 101)

Drainage Area =	37200 m2	or	3.72 ha	
Impervious (m2) 5995 Gravel			Landscaped Areas (m2) 31205 Landscape	
Total Area=0.TIMP90XIMP70	60 ha Area <mark>%</mark> 0.54 ha <mark>%</mark> 0.42 ha		Total Area=3.1TIMP109XIMP59	2 ha Area <u>%</u> 0.31 ha <u>%</u> 0.16 ha
IMPERVIOUSNESS				
TOTAL Modelled Area=	3.72 ha		TOTAL Pervious Area=	2.87 ha
OVERALL TIMP OVERALL XIMP	0.229 0.155		OVERALL Runoff Coefficient	0.26
IMPERVIOUS CALCULATIONS - Pre	-Development (Cate	chment 10	02)	

Drainage Area =	=	2100 m2	or	0.21 ha		
Impervious (m2	:)			Landscaped Are	eas (m2)	
0	Gravel			2100	Landscape	
		-				
		-				
		-				
		-				
	0.00	0 h -		T-4-1 A	0.04 h -	
Total Area =	0.00	J na		Total Area =	0.21 na	•
<b>T</b> 11 (D	0.00	Area		711.45	100/	Area
TIMP	90%	0.00 ha		TIMP	10%	0.00 ha
XIMP	70%	6 0.00 ha		XIMP	5%	0.00 ha
<b></b>						
IMPERVIOUS	IESS					
TOTAL Modell	ed Area=	0.21 ha		TOTAL Perviou	us Area=	0.19 ha
		0.21 /10				011 <b>0</b> 110
		0 400			off Coofficient	0.44
OVERALL TIM		0.100		OVERALL RUN	on coencient	0.14
OVERALL XIM	IP	0.050				

Project:Ninth LineFile:300044049Designed by:T.RosboroughChecked by:S.RoordaDate:10-May-23



#### IMPERVIOUS CALCULATIONS - Post Development Uncontrolled to Ninth Line ROW (Catchment 201)

Drainage Area =	<mark>4247</mark> m2	or	0.42	ha	
Impervious (m2)			Landscaped Are	as (m2)	
958 Asphalt			3289	Landscape	
Total Area= 0.10	ha		Total Area=	0.3289 ha	
	Area				Area
TIMP 90%	0.09 ha		TIMP	10%	0.03 ha
XIMP 70%	0.07 ha		XIMP	5%	0.02 ha
IMPERVIOUSNESS					
TOTAL Modelled Area=	0.42 ha		TOTAL Perviou	is Area=	0.31 ha
OVERALL TIMP OVERALL XIMP	0.280 0.197		OVERALL Run	off Coefficient	0.30

Project:Ninth LineFile:300044049Designed by:T.RosboroughChecked by:S.RoordaDate:10-May-23



### IMPERVIOUS CALCULATIONS - Post Development (Catchment 202)

Pond Drainage	Area =		35022 m2	or	3.50	ha	
Impervious (m2	)				Landscaped Are	eas (m2)	
19083	Roof / Roads / Walkwa	vs			4633	Septic Area	
		Ť			8908	Landscape	
		-					
		-					
		-					
		-					
Total Area=	1.91	ha			Total Area=	1.35 ha	l
		_	Area				Area
TIMP	90%	•	1.72 ha		TIMP	10%	0.14 ha
XIMP	70%	,	1.34 ha		XIMP	5%	0.07 ha
		_					
			z				
SWM Block (m2	)	-					
2399	Pond						
-							
Total Area =	0.24	ha			Total Area =	0.00 ha	1
			Area				Area
TIMP	50%	]	0.12 ha		TIMP	80%	0.19 ha
XIMP	50%		0.12 ha		XIMP	60%	0.14 ha
		1	0.12 114			0070	0.14 114
IMPERVIOUSN	ESS						
TOTAL Model	d Aroa=		3.50 ha		TOTAL Parvio	is Aroa=	1 53 ba
I GTAL WOULD			5.50 Ha		I GTAL PEIVIOU		1.55 114
OVERALL TIM	P		0.563		OVERALL Run	off Coefficient	0.56
	P		0 435				
			0.400				

### Water Quality Design Sheet:

Project Name:Ninth LineProject Number:300044049Date:5/10/2023Completed by:T.Rosborough



## Water Quality and Extended Detention Storage - Catchment 202

Summary of Land Uses			Area =		Imperviousness =	
Roof / Road / Walkways			1.91	ha	90%	
Landscaped Areas			1.35	ha	10%	
SWM Pond			0.24	ha	50%	
TOTAL			3.50	ha	56.3%	
Protection Level	1	Type "1" fo	or Enhance	d, "2" for Normal, "3"	for Basic	Table 3.2 Code
Pond Type	Wetpond	Choose In	filtration, W	/etpond, Wetland, or H	lybrid	3
Imperviousness %	56.3				-	
MOE 2003 Table 3.2 Volume	154.6	m³/ha				

Type of SWM	Protection	Water Quality	Extended Detentio	Estimated Peak	
Facility	Level	Volume	MOE Guideline (40m <sup>3</sup> /ha)	25mm Storm Runoff	Release Rate
		(m <sup>3</sup> )	(m <sup>3</sup> )	(m <sup>3</sup> )	(m³/s)
Wetpond	1	541	140	493	0.0086

- **NOTE:** \* The greater of the MOE Guideline (40m<sup>3</sup>/ha) and the 25mm Storm Runoff Volume is used as the Extended Detention Volume.
  - The Estimated Peak Release Rate is based on the Extended Detention Volume divided by 24hrs divided by 3600sec multiplied by 1.5.
  - The constant of 1.5 is used to determine the approx. peak release rate from the average release rate.

### 5mm On-Site Retention Volume

PROJECT:Ninth LinePROJECT #:300044049DATE:10-May-23MUNICIPALITY:City of Mississauga

Catchment	Area (ha)	Area Impervious (ha) Level		Drawdown Time (hrs)	Required Detention Volume (m <sup>3</sup> )	
201*	0.24	0.28	5.00	24	3.4	
202	3.50	0.56	5.00	24	98.0	
Total	3.75	0.54			101.4	

\*Uncontrolled Area of 0.44 ha minus 0.18 ha conveyed to the City.

#### SWM Facility Storage Design Sheet:

Project Name: Ninth Line Project Number: 300044049 Date: 5/10/2023 Completed by: T.R.



#### **SWM Pond - Storage Calculations**

#### INPUT AREA

Base:	178.00	
NWL	179.20	
Required Water Quality Volume:	564 (	m³
Provided Water Quality Volume:	676 (	m³
Required 100-Year Storage Volume	1704 ו	m <sup>3</sup>
100-Year Storage Volume Provided	2218	m <sup>3</sup>

#### ELEVATION / STORAGE INFORMATION

	Elevation	Stage	Area 1	Area 2	Total Area	Avg. Area	Incremental Storage	Cumulative Storage	Cumulative Storage above Permanent Pool
	(m)	(m)	(m2)	(m2)	(m2)	(m2)	(m3)	(m3)	(m3)
Base	178.00	0.00	200	0	200				
	178.50	0.50	376	178	554	377	189	189	0
	179.00	1.00	591	143	734	644	322	511	0
NWL	179.20	1.20	922		922	828	166	676	0
	179.50	1.50	1,153		1,153	1,038	311	987	311
	180.00	2.00	1,528		1,528	1,341	670	1,658	982
	180.50	2.50	1,867		1,867	1,698	849	2,506	1,830
Freeboard	180.70	2.70	2,009		2,009	1,938	388	2,894	2,218
	181.00	3.00	2,231		2,231	2,120	636	3,530	2,854

Stage-Dis	scharge-	Storage	Operation										
Wet-Pond	d Facility												
Ninth Line													
Project # 3000	044049												
1 10ject # 3000	044043												
Input:													
Control	Control	Inv. Elev.	D or L	Lip Elev.	Des	cription							
used		(m)	(mm or m)	(m)									
Y	Orifice 1	179.20	80	179.20	ED								
Y	Orifice 2	179.20	170	179.80	100-Year								
N	Orifice X	500	500	500.00		not used							
Y	Weir A	180.70	10.0	180.70	Emergency								
			Orifice: Q=CA(2	gΗ) <sup>^0.5</sup>				Weir: Q	=Cd*(L-0.06	h)*H^3/2			
Pond W/S	Orifi	co 1	Orifice	2	Or	ifico 3		Moir "A"		Total	Pond	Tailwater	Design
Fond WS			Office	2	01					Controlled	Fond	Taliwalei	Design
Elev	Head	Outflow	Head	Outflow	Head	Outflow	Head	Discharge	Outflow	Outflow	Storage	Elev	Storm
(m)	(m)	(m <sup>3</sup> /s)	(m)	(m <sup>3</sup> /s)	(m)	(m <sup>3</sup> /s)	(m)	Coefficient	(m <sup>3</sup> /s)	(m <sup>3</sup> /s)	(m <sup>3</sup> )	(m)	
									0				
179.20	na	0.000	na	0.000	na	0.00	0.00	1.84	0.00	0.000	-	0.00	
179.30	0.06	0.003	na	0.000	na	0.00	0.00	1.84	0.00	0.003	104	0.00	
179.40	0.16	0.006	na	0.000	na	0.00	0.00	1.84	0.00	0.006	208	0.00	
179.50	0.26	0.007	na	0.000	na	0.00	0.00	1.84	0.00	0.007	311	0.00	
179.60	0.36	0.008	na	0.000	na	0.00	0.00	1.84	0.00	0.008	445	0.00	
179.70	0.46	0.009	na	0.000	na	0.00	0.00	1.84	0.00	0.009	579	0.00	
179.80	0.56	0.010	na	0.000	na	0.00	0.00	1.84	0.00	0.010	713	0.00	ED
179.90	0.66	0.011	0.61	0.049	na	0.00	0.00	1.84	0.00	0.060	847	0.00	
180.00	0.76	0.012	0.71	0.053	na	0.00	0.00	1.84	0.00	0.065	982	0.00	
180.10	0.86	0.013	0.81	0.056	na	0.00	0.00	1.84	0.00	0.069	1,151	0.00	
180.20	0.96	0.014	0.91	0.060	na	0.00	0.00	1.84	0.00	0.073	1,321	0.00	
100.20	1.06	0.014	1 01	0.063	na	0.00	0.00	1.8/	0.00	0 077	1 491	0.00	

0.00

0.00

0.00

0.00

0.00

0.00

0.00

0.00

0.00

0.00

0.00

0.10

0.20

0.30

1.84

1.84

1.84

1.84

1.84

1.84

1.84

0.00

0.00

0.00

0.00

0.58

1.64

3.01

0.015

0.015

0.016

0.017

0.017

0.018

0.018

1.11

1.21

1.31

1.41

1.51

1.61

1.71

0.066

0.069

0.071

0.074

0.077

0.079

0.082

na

na

na

na

na

na

na

1.16

1.26

1.36

1.46

1.56

1.66

1.76

180.40

180.50

180.60

180.70

180.80

180.90

181.00

1,660

1,830

2,024

2,218

2,430

2,642

2,854

0.00

0.00

0.00

0.00

0.00

0.00

0.00

100-Year

0.081

0.084

0.088

0.091

0.675

1.738

3.113

#### STORM SEWER DESIGN SHEET: (10 Year Storm)

PROPOSED SEWER SYSTEM NINTH LINE, CITY OF MISSISSAUGA



[THE DIFFERENCE IS OUR PEOPLE]

Project : Date Designer Checker	#: 300044049.( e: 10-May-23 d: TR d: SR	0000				Min. Ma Sta Factor	Diameter = nnings 'n'= arting Tc = of Safety =	250 0.013 15 10	mm min %	Rainfall I	ntensity = A = B = C =	A (Tc+B)^c 820 4.6 0.78	where T	c is in minutes				1	NOMINAL PIPE S	SIZE USED
DESCRIPTION	FROM MH	то мн	AREA (ha)	RUNOFF COEFFICIENT "R"	'AR'	ACCUM. 'AR'	RAINFALL INTENSITY (mm/hr)	FLOW (m3/s)	CONSTANT FLOW (m3/s)	ACCUM. CONSTANT FLOW (m3/s)	TOTAL FLOW (m3/s)	LENGTH (m)	SLOPE (%)	PIPE DIAMETER (mm)	FULL FLOW CAPACITY (m3/s)	FULL FLOW VELOCITY (m/s)	INITIAL Tc (min)	TIME OF CONCENTRATION (min)	ACC. TIME OF CONCENTRATION (min)	PERCENT FULL (%)
		r - r		1		1	1		1			1	1	1	1	1 1		1		
	DCBMH11	MH10	0.26	0.81	0.22	0.22	80.5	0.048			0.048	23.2	0.40	300	0.061	0.87	15.00	0.45	15.45	70%
	MH10	CBMH09	0.20	0.01	0.22	0.22	79.1	0.040			0.040	54.8	0.40	300	0.061	0.87	15.00	1.06	16.50	77%
		O D III IOO				0.22	10.1	0.011			0.011	01.0	0.10	000	0.001	0.01			10.00	
	RD01	CBMH09	0.50	0.90	0.45	0.45	80.5	0.101			0.101	30.0	2.00	300	0.137	1.93	15.00	0.26	15.26	74%
	CBMH09	DCBMH07	0.24	0.73	0.17	0.84	76.0	0.177			0.177	76.3	0.40	525	0.272	1.26	16.50	1.01	17.51	65%
	DCBMH07	DCBMH06	0.25	0.69	0.17	1.01	73.3	0.206			0.206	20.5	0.30	525	0.236	1.09	17.51	0.31	17.83	87%
	DCBMH06	DCBMH03	0.16	0.80	0.13	1.14	72.5	0.230			0.230	40.6	0.30	600	0.336	1.19	17.83	0.57	18.40	68%
	DODMUSS	00041104	0.00	0.05	0.07	0.07	00.5	0.000			0.000	00.7	0.00	075	0.000	0.07	45.00	0.45	45.45	000/
	DCBMH05	CBMH04	0.32	0.85	0.27	0.27	80.5	0.060			0.060	23.7	0.30	375	0.096	0.87	15.00	0.45	15.45	62%
	CBIVIH04	DCBIVINUS	0.22	0.01	0.10	0.45	79.1	0.099			0.099	47.4	0.30	450	0.150	0.90	10.40	0.80	10.20	0376
	DCBMH03	DCBMH02	0.18	0.87	0.16	1 75	71.1	0.345			0.345	17.4	0.30	675	0.460	1 29	18 40	0.23	18.62	75%
	Bobiiiiioo	DODINIOL	0.10	0.07	0.10			0.010			0.010		0.00	0.0	0.100	1.20	10.10	0.20	10.02	
	DICB03	MH12	0.35	0.25	0.09	0.09	80.5	0.019			0.019	20.1	0.40	250	0.038	0.77	15.00	0.44	15.44	52%
	MH12	DCBMH02				0.09	79.1	0.019			0.019	59.2	0.40	250	0.038	0.77	15.44	1.29	16.72	51%
	DCBMH02	CHAMBER	0.19	0.76	0.14	1.98	70.5	0.387			0.387	3.5	0.30	675	0.460	1.29	18.62	0.05	18.67	84%
	CHAMBER	MH35				1.98	70.4	0.386			0.386	5.2	0.30	675	0.460	1.29	18.67	0.07	18.74	84%
	MH35	MH34				1.98	70.3	0.386			0.386	26.7	0.30	675	0.460	1.29	18.74	0.35	19.08	84%
	MH34	MH33				1.98	69.5	0.381			0.381	31.9	0.30	675	0.460	1.29	19.08	0.41	19.49	83%
	DICB02	MH33	0.20	0.25	0.07	0.07	80.5	0.016			0.016	20.2	0.50	250	0.042	0.86	15.00	0.30	15 30	38%
	DICBUZ	1011 100	0.29	0.25	0.07	0.07	00.0	0.010	+		0.010	20.2	0.00	200	0.042	0.00	15.00	0.39	15.59	50%
	MH33	HW01				2.05	68.5	0.390	1		0.390	9.2	0.30	675	0.460	1.29	19.49	0.12	19.61	85%
																	-			



Appendix C

Watermain Calculations

## **Connection Single Use Demand Table**

#### WATER CONNECTION

Connection point <sup>3)</sup>							
Ninth Line, ~400m south of Burnhamtho	orpe Road						
Pressure zone of connection point Zone 4							
Total equivalent population to be ser	1104	Persons					
Total lands to be serviced	3.93	Hectares					
Hydrant flow Test							
Hydrant flow test location							
	Pressure (kPa)	Flow (in I/s)	Time				
Minimum Water Pressure							
Maximum Water Pressure							

No.	Water demands										
	Demand type	Demand	Units								
1	Average day flow	1.79	l/s								
2	Maximum day flow	2.50	l/s								
3	Peak hour flow	5.37	l/s								
4	Fire flow <sup>2)</sup>	178.50	l/s								
Analysis											
5	Maximum day plus fire flow	181.00	l/s								

#### WASTEWATER CONNECTION

Сог	nnection point <sup>4)</sup>	Septic		
Tot	al equivalent population to be serviced <sup>1)</sup>	1104		
Tot	al lands to be serviced	3.93 ha.		
6	Wastewater sewer effluent (in I/s)	N/A		

<sup>1)</sup> The calculations should be based on the development estimated population (employment or residential).

<sup>2)</sup> Please reference the Fire Underwriters Survey Document

<sup>3)</sup> Please specify the connection point ID

<sup>4)</sup> Please specify the connection point (wastewater line or manhole ID) Also, the "total equivalent population to be serviced" and the "total lands to be serviced" should reference the connection point. (The FSR should contain one copy of Site Servicing Plan)

Please include the graphs associated with the hydrant flow test information table Please provide Professional Engineer's signature and stamp on the demand table All required calculations must be submitted with the demand table submission.

## **Connection Single Use Demand Table**

#### WATER CONNECTION

Connection point <sup>3)</sup>			
Ninth Line, ~400m south of Burnhamtho	orpe Road		
_			
Pressure zone of connection point		Zone	e 4
Total equivalent population to be ser	2371	Persons	
Total lands to be serviced	3.93	Hectares	
Hydrant flow Test			
Hydrant flow test location			
	Pressure (kPa)	Flow (in I/s)	Time
Minimum Water Pressure			
Maximum Water Pressure			

No.	Water demands										
	Demand type	Demand	Units								
1	Average day flow	3.84	l/s								
2	Maximum day flow	5.38	l/s								
3	Peak hour flow	11.53	l/s								
4	Fire flow <sup>2)</sup>	255.71	l/s								
Analysis											
5	Maximum day plus fire flow	261.09	l/s								

#### WASTEWATER CONNECTION

Соі	nnection point <sup>4)</sup>	Septic		
Tot	al equivalent population to be serviced <sup>1)</sup>	N/A		
Tot	al lands to be serviced	3.93 ha.		
6	Wastewater sewer effluent (in I/s)	N/A		

<sup>1)</sup> The calculations should be based on the development estimated population (employment or residential).

<sup>2)</sup> Please reference the Fire Underwriters Survey Document

<sup>3)</sup> Please specify the connection point ID

<sup>4)</sup> Please specify the connection point (wastewater line or manhole ID) Also, the "total equivalent population to be serviced" and the "total lands to be serviced" should reference the connection point. (The FSR should contain one copy of Site Servicing Plan)

Please include the graphs associated with the hydrant flow test information table Please provide Professional Engineer's signature and stamp on the demand table All required calculations must be submitted with the demand table submission.

Sniatenchuk, Bernadette <bernadette.sniatenchuk@peelregion.ca></bernadette.sniatenchuk@peelregion.ca>
Monday, April 22, 2019 10:36 AM
Daniel Nagel
Steven Roorda; Ambrico, Angelo
RE: East Side of Ninth Line, Mississauga - Attached Water Demand Tables for two possible scenarios

Hi Daniel, the modeling indicated that the existing watermain cannot meet the maximum day demand and fire flow for phase 1, which is the Church only.

Let me know if you have any other questions. Bernadette Sniatenchuk, B.Sc. Facilitator – Development Engineering

Development Services, Public Works, Region of Peel 10 Peel Centre Drive, Suite B, 4th Floor Brampton, On L6T 4B9 e-mail: <u>bernadette.sniatenchuk@peelregion.ca</u> Phone: 905-791-7800, ext.8589 Fax: 905-791-1442

This e-mail is for the sole use of the intended recipient and may contain confidential or privileged information. Unauthorized use of its contents is prohibited. If you have received this e-mail in error, please notify sender immediately via return e-mail and then delete the original e-mail.

From: Daniel Nagel <<u>Daniel.Nagel@rjburnside.com</u>>
Sent: April 8, 2019 1:54 PM
To: Sniatenchuk, Bernadette <<u>bernadette.sniatenchuk@peelregion.ca</u>>
Cc: Steven Roorda <<u>Steven.Roorda@rjburnside.com</u>>; Ambrico, Angelo
<<u>angelo.ambrico@peelregion.ca</u>>
Cotiente D5: Sect Side of Nickh Line Missionene Attended Misser December 2019

**Subject:** RE: East Side of Ninth Line, Mississauga - Attached Water Demand Tables for two possible scenarios

Hey Bernadette,

Thanks for the analysis, I just wanted to confirm one more thing concerning the analysis results. Is the existing 200mm inadequate for both Phases (Phase #1 and/or #2)? It would be great if could confirm this for us! Thanks again for your help!

Cheers, Daniel

> **Daniel Nagel, P.Eng.** Senior Project Engineer

R.J. Burnside & Associates Limited | www.rjburnside.com Office: +1 800-265-9662 Direct: +1 226-486-1544

From: Sniatenchuk, Bernadette <<u>bernadette.sniatenchuk@peelregion.ca</u>>
Sent: Monday, April 08, 2019 7:46 AM
To: Daniel Nagel <<u>Daniel.Nagel@rjburnside.com</u>>
Cc: Steven Roorda <<u>Steven.Roorda@rjburnside.com</u>>; Ambrico, Angelo
<angelo.ambrico@peelregion.ca>

**Subject:** RE: East Side of Ninth Line, Mississauga - Attached Water Demand Tables for two possible scenarios

Hi Daniel, The results of the analysis showed that the existing 200mm watermain on Ninth line cannot adequately meet your fire flow requirements and there may be a negative impact to existing customers using this watermain. In order for your proposal to have adequate water for fire protection the 200mm watermain will require an upgrade to a minimum 300mm watermain.

If you have any more questions, let me know. Thanks,

**Bernadette Sniatenchuk, B.Sc.** Facilitator – Development Engineering

Development Services, Public Works, Region of Peel 10 Peel Centre Drive, Suite B, 4th Floor Brampton, On L6T 4B9 e-mail: <u>bernadette.sniatenchuk@peelregion.ca</u> Phone: 905-791-7800, ext.8589 Fax: 905-791-1442

This e-mail is for the sole use of the intended recipient and may contain confidential or privileged information. Unauthorized use of its contents is prohibited. If you have received this e-mail in error, please notify sender immediately via return e-mail and then delete the original e-mail.

From: Sniatenchuk, Bernadette
Sent: April 4, 2019 5:19 PM
To: 'Daniel Nagel' <<u>Daniel.Nagel@rjburnside.com</u>>
Cc: Steven Roorda <<u>Steven.Roorda@rjburnside.com</u>>; Ambrico, Angelo
<<u>angelo.ambrico@peelregion.ca</u>>
Subject: RE: East Side of Ninth Line, Mississauga - Attached Water Demand Tables for two possible
scenarios

Hi Daniel, I just got your voicemail. I actually just received the modeling results today. One point that was raised was the proposed population growth. I recommend that you speak with Planning at the City of Mississauga as the proposed population is higher than the projected growth for this area. The City will be able to provide guidance on the Planning data and population forecasts.

I reviewed the analysis and I had some questions for the modeller before I forward you the information. I'm just waiting to hear back. Thanks,

**Bernadette Sniatenchuk, B.Sc.** Facilitator – Development Engineering

Development Services, Public Works, Region of Peel 10 Peel Centre Drive, Suite B, 4th Floor Brampton, On L6T 4B9 e-mail: <u>bernadette.sniatenchuk@peelregion.ca</u> Phone: 905-791-7800, ext.8589 Fax: 905-791-1442 This e-mail is for the sole use of the intended recipient and may contain confidential or privileged information. Unauthorized use of its contents is prohibited. If you have received this e-mail in error, please notify sender immediately via return e-mail and then delete the original e-mail.

From: Daniel Nagel <<u>Daniel.Nagel@rjburnside.com</u>>
Sent: March 19, 2019 12:36 PM
To: Sniatenchuk, Bernadette <<u>bernadette.sniatenchuk@peelregion.ca</u>>
Cc: Steven Roorda <<u>Steven.Roorda@rjburnside.com</u>>
Subject: RE: East Side of Ninth Line, Mississauga - Attached Water Demand Tables for two possible scenarios

Hey Bernadette,

I attached a Scenario Plan to this email, showing the usage for the church only representing Scenario #1 (excluding Red Hatched Areas), as well as the additional services required within Scenario #2 (including Red Hatch Areas). Please let me know if there are any additional questions from your end.

Cheers, Daniel

> **Daniel Nagel, P.Eng.** Senior Project Engineer

R.J. Burnside & Associates Limited | www.rjburnside.com Office: +1 800-265-9662 Direct: +1 226-486-1544

From: Sniatenchuk, Bernadette < <u>bernadette.sniatenchuk@peelregion.ca</u>>

Sent: Monday, March 18, 2019 11:31 AM

To: Daniel Nagel <<u>Daniel.Nagel@rjburnside.com</u>>

Cc: Steven Roorda <<u>Steven.Roorda@rjburnside.com</u>>

Subject: RE: East Side of Ninth Line, Mississauga - Attached Water Demand Tables for two possible scenarios

Hi Daniel,

For Scenario #2 what would the other uses be on the site besides the Church?

Thanks, Bernadette Sniatenchuk, B.Sc. Facilitator – Development Engineering

Development Services, Public Works, Region of Peel 10 Peel Centre Drive, Suite B, 4th Floor Brampton, On L6T 4B9 e-mail: <u>bernadette.sniatenchuk@peelregion.ca</u> Phone: 905-791-7800, ext.8589 Fax: 905-791-1442

This e-mail is for the sole use of the intended recipient and may contain confidential or privileged information. Unauthorized use of its contents is prohibited. If you have received this e-mail in error, please notify sender immediately via return e-mail and then delete the original e-mail.

From: Daniel Nagel <<u>Daniel.Nagel@rjburnside.com</u>>
Sent: March 4, 2019 3:00 PM
To: Sniatenchuk, Bernadette <<u>bernadette.sniatenchuk@peelregion.ca</u>>
Cc: Steven Roorda <<u>Steven.Roorda@rjburnside.com</u>>
Subject: East Side of Ninth Line, Mississauga - Attached Water Demand Tables for two possible scenarios

#### Hey Bernadette,

It was great talking to you over the phone today, concerning the water modeling for our project on Ninth Line, Mississauga. As discussed we did a two scenario approach for the water demand, which are attached to this email. Scenario #1 only includes the church, where as Scenario #2 would be the entire site. We hope that the attached demand tables are useful to complete the water modeling from your end. In the case of any possible questions, please feel free to get in contact with me at any time. Thanks again for everything and I am looking forward to hear from you soon.

Cheers, Daniel



Senior Project Engineer

R.J. Burnside & Associates Limited 292 Speedvale Avenue West, Unit 20, Guelph, Ontario N1H 1C4 Office: +1 800-265-9662 Direct: +1 226-486-1544 www.rjburnside.com

\*\*\*\* CONFIDENTIALITY NOTICE \*\*\*\*

This electronic transmission and any accompanying attachments may contain privileged or confidential information intended only for the use of the individual or organization named above. Any distribution, copying or action taken in reliance on the contents of this communication by anyone other than the intended recipient(s) is STRICTLY PROHIBITED.

If you have received this communication in error please notify the sender at the above email address and delete this email immediately. Thank you.

\*\*\*\*\*\*

R.J. Burnside & Associates Limited