

# **Tributary of Fletcher's Creek Fluvial Geomorphological Assessment**

# **DeZen Lands Development**

7140 Hurontario Street, Mississauga



# Prepared for:

DeZen Realty 128 Queen Street South Mississauga, Ontario L5M 1K8

# Submitted:

September 12, 2025

GEO Morphix Project No. 25102









Ver.	Purpose/Change	Authored by	Approved by	Date
1.0	First Submission	Rachel Abbott, B.Sc, G.I.T. Rachel Sun,	Paul Villard, Ph.D., P.Geo., CAN- CISEC, EP, CERP	September 12, 2025

# **Disclaimer**

This report presents professional opinions and findings of a scientific and technical nature based on the knowledge and information available at the time of preparation. This document is prepared solely for the Client, and the data, interpretations, suggestions, recommendations, and opinions expressed in the report pertains only to the project being completed for the Client.

# **Table of Contents**

1	Intro	duction		1
2	Back	ground	Review	1
	2.1	Backgı	round Reports	2
	2.2	Surfici	al Geology	3
	2.3	Histori	cal Assessment	3
3	Wate	rcourse	Characteristics	4
	3.1	Reach	Delineation	4
	3.2	Genera	al Reach Observations	5
	3.3	Recon	naissance-level Assessments	6
	3.4	Detaile	ed Geomorphological Assessment	7
4	Erosi	on Haza	ard Assessment	7
	4.1	Meand	ler Belt Width Delineation	8
	4.2	Toe Er	osion Allowance	9
5	Corri	dor Cros	ssing Recommendations	.10
6	Outfa	ıll Erosio	on Assessment and Design	.11
	6.1	Outfall	Erosion	.11
	6.2	Storm	water Outfall Treatment Design	.11
		6.2.1	Hydraulic Substrate Sizing	.12
		6.2.2	Construction Timing	.14
		6.2.3	Best Management Practices	.14
		6.2.4	Post-construction Monitoring	.15
7	Sumr	mary an	d Recommendations	.15
8	Refer	ences		.17
l ist	of T	ables		
				_
			azard Assessment results (Parish, 2011)	
		_	eomorphic assessment results	
			of modelled meander belt widths for watercourse reaches for existing conditions	
		-	of recommended toe erosion allowances for confined valley reaches	
			vidth and proposed crossing widths	
			sizes for the stone core wetland stone lining, based on a range of techniques	
Table	7: Va	riables	and values associated with the stone core wetland stone sizing	.13

# **Appendices**

Appendix A: Erosion Hazard Mapping



Appendix B: Historical Aerial Imagery
Appendix C: Photographic Field Record

Appendix D: Field Observations

Appendix E: Detailed Assessment Summaries

Appendix F: Outfall Design Drawings



#### 1 Introduction

GEO Morphix Ltd. was retained to provide a geomorphological assessment for the proposed DeZen Lands Development located at 7140 Hurontario Street in the City of Mississauga, Ontario. Two watercourses are located within or adjacent to the subject lands, Fletcher's Creek and a small tributary of Fletcher's hereafter referred to as Tributary 1. The geomorphological assessment provides guidance in addressing and delineating erosion hazards and supporting erosion mitigation strategies for the stormwater management plan.

To fulfill erosion hazard delineation requirements, a toe erosion allowance was determined to support the slope stability assessment completed by Soil Engineers Ltd for Fletcher's Creek and Tributary 1. A short section of channel within Tributary 1 was identified as being unconfined as such, a meander belt width was also calculated for this reach. The meander belt width previously delineated for Fletchers Creek by Parish (2011) was also reviewed and further refined.

To support erosion mitigation, a crossing assessment and conceptual outfall design has been completed and integrated into this report. The location of the proposed outfall and crossing location were assessed in the field to support the assessment and conceptual design, respectively.

The following activities were completed as part of the geomorphological assessment in support of the development plan:

- Background review of reports and mapping for the subject lands (i.e., watershed/subwatershed studies, geology, topography, conceptual development plans, past environmental reports)
- Delineate watercourse reaches based on a desktop assessment of available data and confirmed through field reconnaissance
- Review of historical and recent aerial photographs to assess alterations in channel planform and location of the toe of slope over time
- Reach-level rapid geomorphological field assessments following standard protocols (e.g., RGA, RSAT) to evaluate instream and riparian conditions, and overall stability of the channel
- Delineate or refine limits of the meander belt width/erosion hazard on a reach basis using results of the desktop and field assessments
- A detailed geomorphic assessment including a longitudinal survey of the channel center line, 8
  channel cross-section surveys, and Wolman pebble counts to determine grain size and material
  type for channel bed and banks
- Provide technical input and recommendations for the watercourse crossing. This includes input on watercourse crossing size and location as well as any setback limits in support of erosion mitigation
- Provide technical support for the assessment of any outlet locations to assess local erosion
- Provide support in development of a conceptual outfall design

# 2 Background Review

The subject lands are situated within the Fletchers Creek Subwatershed of the overall Credit River Watershed. The Fletchers Creek and associated tributary are present within or adjacent to the subject lands. Land use within the watershed is dominated by approximately 35% of natural land cover, 31% urban land cover, and 34 % agricultural and open space. The natural areas include forests, wetlands, meadows, and riparian areas (Credit Valley Conservation). The subject lands are generally comprised of agricultural lands with Tributary 1 flowing south through the subject lands and Fletchers Creek flowing in a southern direction south of the site. Fletchers Creek is also noted as occupied Redside dace habitat.



# 2.1 Background Reports

A detailed review of the documents below was conducted to understand relevant information associated with the watercourses for current or future assessments. The studies provide insight into past historical information, rapid assessment information and overall erosion potential information.

DRAFT DeZen: Fletchers Creek Hazard Assessment – Parish Geomorphic (2011)

An erosion hazard assessment was completed to support the study area which consisted of background review, desktop assessment, rapid assessments, meander belt width delineation, and channel migration analysis for Fletchers Creek and its tributary. Reaches were assessed through field verified rapid assessments completed using RGA and RSAT tools and all reaches were reported to be in transition with the dominant process of widening.

A preliminary meander belt width was delineated along Reaches **FC-1**, **FC-2**, **FC-3**, **FCT-1**, and **FCT-2** (Tributary) using the Leopold and Wolman Method (1960). The method involves measuring the widest meander amplitudes along the reach to determine the meander belt width. Empirically modelling was also completed to estimate the meander belt widths including Williams (1986), Ward (2002), PARISH Geomorphic Ltd. (2004a) and Annable (1996). Ultimately, the meander belt widths determined by the Leopold & Wolman method was determined to be the most appropriate. An erosion analysis and channel migration rate was also completed along the main branch which studied rates at which the channel is migrating over time through historical aerial photograph review. The tributary was densely vegetated and as such, migration rates were not calculated. The 100-year erosion migration rate was determined to be 8 metres. Ultimately, the erosion hazard was determined by the meander belt width due to the inherent error in the migration rate measurements, field observations, and as a conservative approach given the meander belt width was equal to or slightly higher than the estimated 100-year erosion rate.

The results of the erosion hazard assessment are summarized as follows:

**Table 1: Erosion Hazard Assessment results (Parish, 2011)** 

Reach Names	Preliminary Meander Belt Widths*	Erosion Migration Rate (m per 100 yrs)
FC-1	72	8
FC-2	108	8
FC-3	120	8
Tributary (FCT-1 & FCT-2)	22	n/a

<sup>\*</sup>Including a FOS of 20%

> Detailed Geomorphic Assessment - Fletchers Creek - Geomorphic Solutions (2012)

A detailed geomorphic survey was completed along a portion of Fletchers Creek downstream of the tributary in support of Redside Dace habitat delineation. The detailed geomorphic survey extended 278 m downstream of the tributary confluence with an average bankfull width and depth of 8.5 m and 0.7 m respectively. This assessment supported the assessment that the tributary is not contributing Redside Dace habitat as the average bankfull width downstream of the tributary confluence are more 7.5 m wide as discussed in the EIS (GEI, 2025).

> Environmental Impact Study (EIS) - 7140 Hurontario Street, Mississauga - GEI Consultants Canada Ltd. (February, 2025)

An EIS was completed and submitted as part of the resubmission for the draft plan of subdivision and zoning by-law amendment. The study was comprised of existing condition characterization of the natural environmental features, constraint delineation, identification of potential impacts of the development, and mitigation recommendations with the input of multiple disciplines and consultants.

With respect to fluvial geomorphology, the erosion hazard was one component of the constraint mapping which was based on the meander belt width previously delineated by Parish (2011) and the toe erosion



allowance recommended by GEO Morphix Ltd as discussed in **Section 4.2**. The classification of Redside Dace habitat was also discussed within EIS as previously noted.

➤ Functional Servicing Report (FSR) – 7140 Hurontario Street, Mississauga – Skira and Consultants Ltd. (February, 2025)

An FSR was completed and submitted as part of the resubmission for the draft plan of subdivision and zoning by-law amendment. The study was comprised of existing site condition characterization, grading plans, stormwater management plan, servicing requirements, and erosion and sediment controls.

The site will be developed in two Phases with the lands east of the tributary developed in Phase 1 and the lands west of the tributary will be developed in Phase 2. The Tributary to Fletchers Creek will continue to receive flows from approximately 12 ha of drainage area north of the subject lands in the post development scenarios. In Phase 1, flows will be conveyed to the existing storm sewer on Vicksburg Drive, which discharges to SWM Pond 4402B. In Phase 2 flows will generally be piped and conveyed to an outfall to the main branch of Fletchers Creek. A treatment train approach will be utilized to retain the first 5 mm of rainfall and for quality control.

Geotechnical Investigation for Slope Stability Study – Soil Engineers Ltd. (2008)

Supplementary Slope Stability Study Letter Report - Soil Engineers Ltd. (2016)

Supplementary Slope Stability Study Letter Report - Soil Engineers Ltd. (2020)

A slope stability assessment was completed in 2008 and subsequently updated in 2016 and 2020 after receiving comments from agencies. The initial assessment provided characterization of the subsurface conditions and groundwater conditions, and slope stability analysis. It was determined that the site was generally comprised of silty clay till soils with a localized layer of very dense sandy silt till in the areas of the Fletchers Creek Tributary (BH1 and BH2). All boreholes remained dry upon completion of the investigation and the groundwater regime was inferred to lie in the grey saturated soils. A long-term stable slope was delineated which incorporated a 5 m development setback and an 8 m toe erosion setback.

In 2016, the cross sections were updated to reflect an updated topographic survey. In 2020, the tributary to Fletchers Creek was also added to the slope study. Additionally, the long-term stable slope was updated to incorporate the recommended toe erosion setbacks and meander belt widths determined by GEO Morphix Ltd. as discussed in **Section 4**.

# 2.2 Surficial Geology

Channel morphology and planform are largely governed by the flow regime and the availability and type of sediments (i.e., surficial geology) within the stream corridor. Physiography, riparian vegetation, and land use also physically influence the channel. These factors provide insight into existing conditions and the potential future changes as they relate to a proposed activity.

Local surficial geology along the Tributary to Fletcher's Creek is fine-textured till composed of silt and clay derived from glaciolacustrine deposits (OGS, 2010). The study area is located within the Peel Plain physiographic region, a bevelled till plain which is characterized by gently undulating to rolling topography with layers of thick till deposits on bedrock (Chapman and Putnam, 1984). Understanding the surficial geology of the study area is important for determining the toe erosion allowance and assessing the erosion hazard, as stability of the channel banks and valley slope is dependent on soil composition and structure (MNRF, 2001).

#### 2.3 Historical Assessment

A series of historical aerial photographs were reviewed to determine changes to the channel and surrounding land use/cover. This information, in part, provides an understanding of the historical factors that have contributed to current channel morphodynamics. For this exercise, the 1954, 1977 and 1989 photographs were retrieved from the National Air Photo Library, and the 2002, 2018, 2023 images were



retrieved from Google Earth Pro. Cropped aerial photographs, showing Fletcher's Creek, Tributary 1 and surrounding area are provided in **Appendix B**.

In 1954 land use within the vicinity of Fletcher's Creek and Tributary 1 was almost exclusively agricultural. A riparian buffer for the tributary was absent, while adjacent to Fletcher's Creek some patches of mature trees particularly along the west side of the channel within the valley were noted. Tributary 1 was observed to originate at a small agricultural pond located on the north side of an eastwest road which transects the subject property. The tributary appears to have been straightened until reaching the valley corridor, at which point the channel follows the south westerly valley trend before forming a confluence with Fletcher's Creek. The planform of Fletcher's Creek nearby to the subject site is best described as irregular meanders within a confined valley. Nearby to the confluence of Tributary 1 with Fletcher's Creek, on the opposite bank, a cut-off channel can be observed, possible evidence of planform adjustments.

In 1977 land use nearby to the subject site has remained predominantly agricultural, with the exception of the lands south of Fletcher's Creek opposite to Tributary 1 which is now occupied by a golf course. The construction of the golf course included the removal of the cut off channel noted in the 1955 aerial photograph. The only significant change related to Tributary 1 is the removal of the east-west road noted to transect previously noted to cross the tributary.

The 1989 aerial photo indicates minimal changes to land use nearby to the subject site, although it is known that lands upstream in the Fletcher's Creek catchment have become significantly urbanized by this time. For Tributary 1, the watercourse appears to be recovering from previous channelization to have a small degree of sinuosity upstream of the confined segment. Within the confined segment, the channel has maintained its irregular meanders and more woody vegetation has become established. For the mainstem of Fletcher's Creek, a meander previously located upstream of the eastward valley trend turn is no longer present. As well, a historic channel is apparent north of the first meander bend located where Fletcher's Creek conveys flow eastward towards the tributary.

By 2002 land use in the vicinity of the DeZen Property has shifted to predominantly residential and commercial, although the property itself and the adjacent lands have remained agricultural. both channels, the presence of woody riparian vegetation has increased. The only notable change to Tributary 1 is that the pond located at the upstream extent no longer holds standing water but rather exists as a wetland feature.

In 2018 the trend towards residential and commercial development has persisted, with construction of commercial properties on the west side of Hurontario and the west side of Fletcher's Creek. Riparian conditions along both channels have continued to establish, with a dense canopy now apparent within the confined section of the tributary, and a significant quantity of mature trees within the corridor of the mainstem of Fletcher's Creek. For both channels, no planform changes were apparent.

Between 2018 and 2023, the subject lands east of Tributary 1 undergo some industrial development as well. Changes along Tributary 1 and Fletcher's Creek were not observed.

#### 3 Watercourse Characteristics

# 3.1 Reach Delineation

Reaches are homogeneous segments of channels used in geomorphological investigations. Reaches are divided as such because they are expected to have similar inputs and outputs in terms of sediments and discharge. They are also expected to react similarly throughout to flow events and other stressors. They are studied semi-independently as each is expected to function in a manner that is at least slightly different from adjoining reaches. This allows for a meaningful characterization of a watercourse as the aggregate of reaches, or an understanding of a particular reach, for example, as it relates to a proposed activity.

Reaches are delineated based on changes in the following:

• Channel planform



- Channel gradient
- Physiography
- Land cover (land use or vegetation)
- Flow, due to tributary inputs
- Soil type and surficial geology
- Certain types of anthropogenic channel modifications

Reach delineation follows scientifically defensible methodology proposed by Montgomery and Buffington (1997), Richards et al. (1997), and the Toronto and Region Conservation Authority (2004) as well as others.

Reaches on and adjacent to the subject lands were delineated by a desktop exercise and were subsequently verified in the field. Reach **FC-2** was delineated along the main branch of Fletchers Creek and Reaches **FCT-1**, **FCT-2**, and **FCT-3** were delineated along the Fletcher's Creek tributary (Tributary 1) based on changes in gradient, land use, land cover, geology, and various flow or tributary inputs. Our reach delineation is graphically presented in **Appendix A**.

The upstream extent of Reach **FCT-1** was located at the northern edge of the forest patch within the subject property between two agricultural fields. The reach conveyed flow south for approximately 200 m towards Fletcher's Creek. Reach **FCT-1** was defined by deciduous trees in the riparian zone and valley confinement on both sides of the creek. Upstream of the forest patch, Reach **FCT-2** was a short, poorly defined channel which conveyed flows southwards through the vegetated corridor separating the two agricultural fields, upstream of Reach **FCT-1**. The channel was partially confined and generally had herbaceous vegetation and grasses occupying the riparian buffer. Reach **FCT1-3** was an undefined feature which conveyed flows from the old farm pond location to the top of **FCT-2**.

## 3.2 General Reach Observations

Field investigations were completed on November 1, 2018, and updated on July 18, 2025, and included the following reach-by-reach observations:

- Descriptions of riparian conditions
- Estimates of bankfull channel dimensions.
- Determination of bed and bank material composition and structure
- Observations of erosion, scour, or deposition
- Collection of photographs to document the watercourses, riparian areas and/or valley, surrounding land use, and channel disturbances such as crossing structures

These observations and measurements are summarized below. The descriptions are supplemented and supported with representative photographs, which are included in **Appendix C**. Field sheets, including reach summaries and rapid assessments, are provided in **Appendix D**.

Reach **FC-2** is a meandering channel within a well-defined confined valley system. The channel has a wide continuous riparian buffer zone consisting of predominately deciduous trees. The average bankfull width and depth were 8.04 m and 1.01 m, respectively. Erosion was observed throughout the reach with some areas of valley wall contact and with undercuts measured up to 0.86 m. Bed materials ranged from gravel to boulders in riffles, and clay, silt to cobbles in pools. A range of bank materials were observed due to the presence of a suspended armour layer. A high density of woody debris was also observed.

Reach **FCT-1** is a mixed-load sinuous channel with a steep gradient that occupies a confined valley. The channel was well defined but appeared to be slightly more incised in the upstream portion. The channel has a continuous riparian buffer zone that contained predominately deciduous trees with some encroached by vegetation. The average bankfull width and depth in Reach **FCT-1** were 1.21 m and 0.30 m. Erosion was noted along this reach with undercuts measured being up to 0.45 m. Bed and bank materials fairly uniform ranging from clay/silt to cobbles in riffles and in pools.

Reach **FCT-2** was a partially confined, sinuous channel with a continuous riparian buffer similar to the downstream extent. It was noted that the channel definition was observed to decrease further upstream.



The channel had no riffle-pool sequence, a moderate gradient and bed and bank material which was homogeneously composed of a range of materials from clay to cobbles. The channel was moderately encroached by riparian vegetation, and lots of woody debris was observed. Average bankfull width and depth for the reach were 1.06 m, and 0.19 m, respectively. Bank angles ranged from 30-90 degrees, and shallow undercuts were observed up to 0.14 m deep.

Reach **FCT-3** was a poorly defined feature which was predominately dry throughout. The majority of the channel was heavily encroached with herbaceous vegetation and grasses. Phragmites and cattails were observed in the upstream portion of the feature as well. The feature had no riffle-pool sequence, a low gradient and bed and bank material which was homogeneously composed of a clay-silt, sand, gravel mixture. Generally, the feature was poorly defined however bankfull measurements were collected in the portions that were defined. Average bankfull width and depth for the defined portion were 0.79 m, and 0.12 m, respectively.

#### 3.3 Reconnaissance-level Assessments

Channel stability and susceptibility to erosion were objectively assessed through the application of the Ontario Ministry of the Environment's (2003) Rapid Geomorphic Assessment (RGA). The RGA evaluates degradation, aggradation, widening, and planimetric form adjustment at the reach scale. The end result of the RGA is to produce a score, or stability index, which evaluates the degree to which a stream has departed from its equilibrium condition. A stream with a score of less than 0.20 is in regime, indicating minimal changes to its shape or processes over time. A score of 0.21 to 0.40 indicates that a stream is in transition or stressed and is experiencing major changes to process and form outside the natural range of variability. A score of greater than 0.41 indicates that a stream is in extreme adjustment, exhibiting a new stream type, or in the process of adjusting to a new equilibrium (MOE, 2003; VANR, 2007).

The Rapid Stream Assessment Technique (RSAT) was also employed to provide a broader view of the system and consider the ecological functioning of the watercourse (Galli, 1996). Observations were made of channel stability, channel scouring or sediment deposition, instream and riparian habitats, and water quality. The RSAT score ranks the channel as maintaining a poor (<13), fair (13-24), good (25-34), or excellent (35-42) degree of stream health.

The reaches were also classified according to a modified Downs (1995) Channel Evolution Model and the River Styles Framework (Brierley and Fryirs, 2005). The Downs' Model describes successional stages of a channel as a result of a perturbation, namely hydromodification. Understanding the current stage of the system is beneficial as this allows one to predict how the channel will continue to evolve or respond to an alteration to the system. The River Styles Framework (Brierley and Fryirs, 2005) provides a geomorphological approach to examining river character, behaviour, condition, and recovery potential.

Reach **FC-2** was identified as primarily widening according to the RGA, as evidenced by the occurrence of fallen and leaning trees, large organic debris, exposed tree roots, and basal scour throughout more than 50% of the reach. Overall, the reach was assigned a stability index of 0.34 and classified as "in transition". The RSAT resulted in a *Good* ranking with a score of 27, with the limiting factor being channel stability, as evidenced by the frequently observed bank erosion also noted by the RGA. Using Downs' Model of Channel Evolution, the channel was determined to be U – undercutting, as evidenced by erosion and undercutting along the banks.

Reach **FCT-1** was identified as primarily widening with some degradation according to the RGA, as evidenced by the fallen and leaning trees, exposed tree roots, and suspended armour layer. Overall, the reach was assigned a stability index of 0.37 and classified as "in transition". The RSAT resulted in a *good* ranking with a score of 27, with the limiting factor being physical instream habitat and channel stability, as evidenced by the lack of diverse geomorphological units and bank erosion also noted by the RGA. Using Downs' Model of Channel Evolution, the channel was determined to be e - Enlarging, as evidenced by erosion along both banks and a scoured bed.

Reach **FCT-2** was identified by the RGA as being "In transition", with the score of 0.21, with the primary process being degradation and widening. This was evidenced by the suspended armour layer and leaning and fallen trees, and exposed roots. The RSAT resulted in a *fair* ranking with a score of 21, with the



limiting factor being physical instream habitat, as evidenced by the lack of diverse geomorphological units. Using Downs' Model of Channel Evolution, the channel was determined to be e - Enlarging, as evidenced by erosion along both banks.

Reach **FCT-3** was generally described as a poorly defined swale that vegetation controlled throughout the reach. As such, the RGA and RSAT tools are not applicable. According to Downs' model of Channel Evolution, the reach was classified as stable given there were almost no observations of ongoing geomorphic change.

# 3.4 Detailed Geomorphological Assessment

A detailed geomorphic assessment was completed within the downstream section of Reach **FCT-1**. The survey was completed on November 1, 2018. Activities completed for the detailed assessment included the following:

- Longitudinal profile of the channel bed to determine slope
- Eight representative cross-sectional surveys of the watercourse to determine average channel dimensions
- Detailed instream measurements at each cross-section including bankfull channel geometry, riparian conditions, bank materials, bank height/angle, and bank root density
- Bed material sampling at each cross-section
- Monumented geo-referenced photographs taken at each cross-section

The results of the detailed assessments are provided in **Table 2**, and a summary is included in **Appendix E**.

**Table 2: Detailed geomorphic assessment results** 

Channel parameter		
Measured		
Average bankfull channel width (m)	2.25	
Average bankfull channel depth (m)	0.50	
Channel bed gradient (%)	2.55	
D <sub>50</sub> (mm)	3.2	
D <sub>84</sub> (mm)	15.0	
Manning's n roughness coefficient	0.040	
Computed		
Bankfull discharge (m³/s)	3.29	
Average bankfull velocity (m/s)	2.89	
Unit stream power at bankfull (W/m²)	474.20	
Tractive force at bankfull (N/m²)	164.37	

# 4 Erosion Hazard Assessment

Most watercourses in southern Ontario have a natural tendency to develop and maintain a meandering planform, provided there are no spatial constraints. A meander belt width or erosion hazard assessment estimates the lateral extent that a meandering channel has historically occupied and will likely occupy in the future. This assessment is therefore useful for determining the potential hazard to proposed activities in the vicinity of a watercourse.

When defining the erosion hazard for a watercourse, Ministry of Natural Resources (MNR, 2002) guidelines treat unconfined and confined systems differently. Unconfined systems are those with poorly



defined valleys or slopes well outside where the channel could realistically migrate. Unconfined systems are generally found within glaciated plains with flat or gently rolling topography. Confined systems are those where the watercourse is contained within a defined valley, where valley wall contact is possible.

In unconfined systems, at minimum, a meander belt width can be applied based on 20 times the bankfull channel width. Alternatively, the limit of the erosion hazard and migration potential can be delineated based on the meander amplitude through a detailed geomorphological study. Meander amplitude is defined by Leopold et al. (1964) as the lateral distance between tangential lines drawn to the center channel of two successive meander bends. This differs from meander belt, which is measured for a reach between lines drawn tangentially to the outside bends of the laterally extreme meander bends (TRCA, 2004). Both the meander belt width and amplitude quantify the lateral extent of a river's occupation on the floodplain (TRCA, 2004).

In confined systems, the MNR outlines an approach for establishing the erosion hazard where valley walls confine watercourses. The approach defines a toe erosion allowance or setback where the channel is within 15 m of the toe of slope. There are several ways to define the toe erosion allowance or setback: using an average annual recession rate; applying a generic and minimum 15 m toe erosion allowance in areas where the channel is within 15 m of the slope's toe; or using soil information and field observations of geomorphic processes (MNRF, 2002) for areas where average annual recession rates cannot be determined.

Based on field reconnaissance and desktop information, it was determined that Reach FCT-2 was partially confined, requiring a meander belt width on the eastern bank. The main branch of Fletchers Creek (Reach FC-2) and Tributary 1 (Reach FCT-1, FCT-2) flow within a confined or partially valley systems requiring a toe erosion allowance to address the erosion hazard. Despite being a confined valley system, a meander belt width was also delineated for Reach FC-2 to support Redside Dace habitat delineation.

# 4.1 Meander Belt Width Delineation

A review of recent and historical aerial imagery was completed but due to the low resolution and a densely vegetated riparian corridor, the watercourse in Reach **FCT-2** was not traceable for historical overlay analysis. As such, a suite of empirical equations was therefore used to delineate existing condition meander belt widths.

Meander belt widths were calculated using several empirical models for comparison purposes. The bankfull channel dimensions observed during field reconnaissance were used to inform both the Williams (1986) and Ward (2002) models outlined below.

The empirical relations from Williams (1986) were modified to include channel width, and applied using the bankfull channel dimensions such that:

$$B_w = 18A^{0.65} + W_b$$
 [Eq. 1]

$$B_w = 4.3W_h^{1.12} + W_h$$
 [Eq. 2]

where Bw is meander belt width (m), A is bankfull cross-sectional area (m<sup>2</sup>), and  $W_b$  is bankfull channel width (m). An additional 20% buffer, or factor of safety, was applied to the computed belt width values. This addresses issues of under prediction.

The Ward et al. (2002) bankfull width model was also used to determine a meander belt width (ft), Bw:

$$B_{\rm w} = 6W_{\rm h}^{1.12}$$
 [Eq. 3]

The resulting value was then converted to the metric system (m). An additional 20% buffer, or factor of safety, was applied to the computed belt width values.

Empirical modelling results are summarized in **Table 3**, below. The extents of all meander belt widths are illustrated in **Appendix A**. For **Reach FCT-2** the calculated meander belt widths range from 5 m to 10 m. The meander belt width of **10 m** was recommended for **Reach FCT-2** based on values determined



using the William Area model which includes a 20% factor of safety (FOS). The value is considered conservative given the recommended meander belt width is slightly larger than the modelled meander belt widths. Additionally, there is limited erosion potential along this reach, particularly given the feature has predominantly clay bed and banks mixed with coarse material due to a suspended armour layer present.

GEO Morphix Ltd. also reviewed and refined the meander belt width previously delineated by Parish (2011) to support the Redside Dace habitat delineation. Based on their assessment a meander belt width of **108 m** was delineated along Reach **FC-2** which was adjacent to the development. The meander belt width was defined by 90 m and an erosion setback of 9 m on each side. This meander belt width was delineated based on Leopold et al. (1964) method which measure the largest meander amplitudes. GEO Morphix Ltd. updated the meander belt width to be truncated along the delineated toe of valley slope in any areas where the reach is confined by adjacent valley slopes (i.e. the meander belt width crosses the toe of slope). This is shown in **Appendix A**, in these locations, the channel cannot realistically migrate further as it is restricted by the valley slope.

As such, the recommended meander belt width for both reaches is considered to appropriately address the potential erosion hazard and Redside Dace habitat delineation.

Table 3: Summary of modelled meander belt widths for watercourse reaches for existing conditions

	Modelled Meander Belt Widths			Recommended
Reach	Modified Williams (1986) Area*	Modified Williams (1986) Width*	Ward Width (2002)*	Meander Belt Width (m)
FCT-2	9	5	9	10

<sup>\*</sup> Includes 20% factor of safety

# 4.2 Toe Erosion Allowance

When defining an erosion hazard for a confined or partially confined valley system, a toe erosion allowance is provided where the channel is within 15 m of the toe of slope. Field observations indicated that **Reach FC-2** and **Reach FCT-1** was confined and **Reach FCT-2** was partially confined.

Generally, the watercourse occupied a confined valley, and the valley walls were often located further than 15 m from the channel in **Reach FC-2**. Average annual recession rates are determined through meander migration analysis using historic and recent aerial photographs. An annual recession rate of approximately 8 m per 100 years was previously determined by Parish (2011) however, due to inherent error in the migration rate measurements and updated field observations we have recommended a toe erosion allowance of 5 m. Additionally, some of the aerial photographs were densely vegetated and banks were poorly visible.

**Reaches FCT-1** and **FCT-2** observed on-site were densely vegetated and poorly visible through aerial photograph interpretation. Given the poor aerial coverage and limited channel definition observed in the historical and recent aerials, meander migration analysis was not possible to determine an average annual recession rate.

As such, we have developed recommendations below for an appropriate toe erosion allowance based on a combination of reach-level observations of existing geomorphic conditions and guidance outlined by MNRF in the technical guide for defining riverine erosion hazards (MNR, 2002). The recommended toe erosion allowances for each confined reach are provided in **Table 4.** 



Table 4: Summary of recommended toe erosion allowances for confined valley reaches

Reach	Range of Acceptable Toe Erosion Allowances (m)*	Final Recommended Toe Erosion Allowances (m)**
FC-2	5 – 8	5
FCT-1	5 – 8	5
FCT-2	5 – 8	5

<sup>\*</sup> Range based on MNR, 2002 guidelines

The valley slopes were investigated by Soil Engineers Ltd. (2016), which found the material to be predominantly hard silty clay till and very dense sandy silt till. In accordance with the MNRF's Erosion Hazard Technical Guidelines, a minimum toe erosion allowance of 5 m is required for the watercourse based on both the valley material and the presence of active erosion within the watercourse. The toe erosion allowance informed the long-term stable slope and is depicted in the Supplementary Slope Stability Study Letter Report – Soil Engineers Ltd. (2020).

Bank materials were consistent in all three of the confined reaches. It was observed to consist primarily of clay and silt; however, a suspended amour layer was present as well which resulted in coarse materials in the banks as well. All three reaches were well vegetated and had active erosion present. Reach FCT-2 was classified as a partially confined small channel based on field observations, with a valley slope only present on the west side of the Fletcher's Creek Tributary. The upstream portion of the reach had limited definition. Reach FCT-1 was a small channel that was confined and well defined however, the downstream portion of the channel was observed to be smaller than the upstream portion. Reach FC-2 was a confined channel along the main branch of Fletchers Creek. Active erosion was observed; however, erosion was not exacerbated beyond how a watercourse of its size normally functions over time. Additionally, the majority of Reach FC-2 was not within 15 metres of the toe of slope and as such, the toe erosion allowance was limited to the downstream portion of this reach.

# **5 Corridor Crossing Recommendations**

One crossing over Tributary 1 (**Reach FCT-3**) associated with the extension of the proposed Vicksburgh Drive. The proposed crossing will require an opening to accommodate the current feature. To accommodate potential channel adjustments, the future crossing should generally span at least three times the bankfull channel width however, this is only one consideration when assessing future channel crossing sizes. Other requirements including flood conveyance or structural requirements may require a different opening and size requirement. Additionally, it should be noted that this feature is poorly defined, vegetation controlled and lacks erosion. As such, the minimum crossing widths provided below should be considered in conjunction with other requirements.

Bankfull channel widths were collected in the field while completing the rapid assessments. Bankfull widths and proposed crossing dimensions are provided in **Table 5.** 

Table 5: Bankfull width and proposed crossing widths

	Average Bankfull Width (m)	*Minimum Recommended Crossing Width (m)
FCT-3 (Vicksburgh Street Extension)	0.79	2.37

A mix of river stone and granular 'B' is proposed throughout the crossing structures to provide for a stable bed and a level of sorting. A layer of native material is also proposed to cover the bed substrate. Hydraulic sizing of all materials should be completed as a part of detailed design activities to confirm that materials are stable under a range of conditions.

<sup>\*\*</sup> Final toe erosion allowance based on field observations and best judgement



# 6 Outfall Erosion Assessment and Design

### **6.1 Outfall Erosion**

According to the most recent draft plan, drainage from 7.75 ha located west of Tributary 1 is proposed to be discharged into Fletcher's Creek southwest of the DeZen Lands. At this location, the Ontario Flow Assessment Tool (OFAT) measures the drainage area of Fletcher's creek as approximately 3,328 ha (33.28 km²). Given the minor drainage contributions from the site relative to the Fletcher's Creek watershed, no exacerbated rates of erosion are expected within the watercourse as a consequence of inputs from the development.

In order to address potential local erosion resulting from site discharge, survey mapping, historical imagery was reviewed and field verified to determine a suitable location for an outfall. This review identified a historic channel located southwest of the DeZen lands which currently exists as a shallow depression. This location is considered ideal given the proximity to Fletcher's Creek, a lack of mature wooded vegetation which could be disturbed during construction and its generally stable existing condition. Erosion was not observed along the historical channel or along the valley wall in the outfall location.

# 6.2 Stormwater Outfall Treatment Design

A stone core naturalized energy dissipater (SCONED) with a level spreader is proposed for the SWM outlet adjacent to Fletcher's Creek. The SCONED will receive flows from the outfall, dissipating energy and providing opportunities for retention, filtration, and infiltration before water disperses through the level spreader to the historic channel. In addition to mitigating any erosion between the outlet and the receiving feature, the treatment train will provide habitat and water quality benefits. The proposed design will act as a polishing feature to further improve water quality by capturing fine sediments at the outlet. Benefits of the SCONED and level spreader system include organic inputs, temperature regulation through shade from overhanging vegetation, polishing, energy dissipation, and dispersion of flows. Additionally, the feature would provide enhanced opportunities for stormwater infiltration, evapotranspiration, and detention.

The primary objectives of the design, therefore, are to:

- Mitigate any erosion between the outlet and receiving features by dissipating energy
- Enhance the function of the SWM by providing additional water polishing
- Provide opportunities for stormwater infiltration, evapotranspiration, and detention before water reaches the receiving features
- Provide additional habitat by installing woody and herbaceous plantings around the features

The proposed SCONED should be constructed as an over-excavated depression, lined with a mix of soil and granular materials to provide depressional and subsurface storage (within the interstitial space of the sediment and soil). A stone core will be installed in the SCONED consisting of hydraulically sized rounded stone to provide additional subsurface stability at the headwall. A layer of topsoil will cover the base layer and will be seeded with the proposed wet meadow seed mix.

The level spreader proposed in conjunction with the SCONED will consist of wattles (i.e., live cuttings) and a silt sock that will be live-staked and overlain with 100% biodegradable erosion control matting. The wattles and silt sock will provide additional protection by reducing velocities and spreading flow over a wider area, promoting sheet flow to minimize any potential erosion between the SCONED and Fletcher's Creek. Wattles can withstand velocities up to 2.5 m/s, which will likely be overly sufficient to



provide stability between the SCONED and receiving feature, as the SCONED will dissipate flows from the outlets before flows pass over the level spreader (Fischenich, 2001).

An aggressive landscape restoration plan is proposed around the SCONED to provide shading over the feature. Live staking around the periphery will provide thermal mitigation through shade, create additional stability in the feature and wattles, and will also provide a source of coarse organic matter. The incorporation of a native seed mix within the wetland will promote polishing of flows once the vegetation has established.

#### 6.2.1 Hydraulic Substrate Sizing

The proposed SWM outlet treatment should provide long-term stability and be suitably robust to withstand the anticipated flow condition. As such, the anticipated 10-year flow of  $0.323~\text{m}^3/\text{s}$  and associated velocity of 2.71~m/s as provided by SKIRA & ASSOCIATES LTD. (2025) was used to inform the design. The stone core is expected to be stable under the predicted flow conditions in the SCONED. A layer of topsoil will be installed over the stone core to improve vegetation establishment. A substrate mix of 60% 300 mm – 400 mm diameter riverstone with 20% granular 'b' and 20% native material is proposed for the stone core at the base of the outfall. Granular 'B' consists of a mix of stone where approximately 20% - 50% of the stone is greater than 0.005~m in diameter, but nothing larger than 0.15~m in diameter.

The stone core was hydraulically sized to limit entrainment. A range of techniques was utilized to determine the appropriate stone sizing, as summarized in the National Engineering Handbook (NRCS, 2007). These techniques are provided in **Table 6**. The anticipated peak flow velocity of 2.71 m/s, provided by SKIRA & ASSOCIATES LTD (2025) was used to determine the appropriate stone size for the material. The stone size includes a factor of safety to provide additional stability. The larger stone size offers stability while allowing storage and infiltration at lower flows.

Table 6: Substrate sizes for the stone core wetland stone lining, based on a range of techniques

Model	Formula	Velocity (m/s)	Stone Size* (mm)
	SCONED Core Substrate		
Isbash Method (Isbash, 1936)	$D_{50} = \left(\frac{V_c}{C * \left(2 * g * \frac{\gamma_s - \gamma_w}{\gamma_w}\right)^{0.5}}\right)^2$	2.71	368
USBR Method (Peterka, 1958)	$D_{50} = 0.0122 * V^{2.06}$	2.71	402
Maynord's Method (Maynord, 1988)	$= C_S * C_v * C_T * d * \left[ \left( \frac{\gamma_W}{\gamma_S - \gamma_W} \right)^{0.5} * \frac{V}{\sqrt{K_1 * g * d}} \right]^{2.5}$	2.71	300

<sup>\*</sup>Includes 20% factor of safety

The Isbash method (Isbash, 1936) was developed for the construction of dams by placing rock into moving water. This model predicts the median stone size ( $D_{50}$ ; ft) under the given flow conditions, given by:

$$D_{50} = (\frac{V_c}{C*(2*g*^{VS-YW})^{0.5}})^2$$
 [Eq.1]

Where:

 $V_c$  = critical velocity (ft/s)



C = Isbash constant (dimensionless)

g = gravity (ft/s)

 $\gamma_s$  = stone density (lb/ft<sup>3</sup>)

 $\gamma_w = \text{water density (lb/ft}^3)$ 

The USBR Method (Peterka, 1958) was developed for sizing riprap below a stilling basin. This model predicts the median stone size ( $D_{50}$ ; ft) under the given flow conditions, given by:

$$D_{50} = 0.0122 * V^{2.06}$$
 [Eq.2]

Where:

V = average channel velocity (ft/s)

Maynord's Method (Maynord, 1988) was developed for sizing riprap in open channel flows. This model predicts the largest stone size ( $D_{100}$ ; ft) under the given flow conditions, given by:

$$D_{100} = C_{s} * C_{v} * C_{T} * d * \left[ \left( \frac{\gamma_{w}}{\gamma_{s} - \gamma_{w}} \right)^{0.5} * \frac{V}{\sqrt{K_{1} * g * d}} \right]^{2.5}$$
 [Eq.3]

Where:

d = water depth (ft)

 $C_s$  = stability coefficient

 $C_v$  = velocity distribution coefficient

 $C_T$  = thickness coefficient

 $\gamma_s$  = stone density (lb/ft<sup>3</sup>)

 $\gamma_w$  = water density (lb/ft<sup>3</sup>)

V = velocity (ft/s)

g = gravity (ft/s)

 $K_1$  = side slope correction, calculated by:

$$K_1 = \sqrt{1 - \frac{\sin^2 \theta}{\sin^2 \theta}}$$
 [Eq.4]

Where:

 $\theta$ = angle of rock from the horizontal

 $\emptyset$  = angle of repose (typically 40°)

The values used for each variable in the Isbash method, USBR method, and Maynord's method are provided in **Table 7.** 

Table 7: Variables and values associated with the stone core wetland stone sizing

Variable	HW 1			
Isbash Method				
Critical velocity $(V_c)$ (ft/s)	8.89			
Isbash constant (C) (unitless)	0.86			
Gravity (g) (ft/s²)	32.2			
Stone density ( $\gamma_s$ ) (lb/ft <sup>3</sup> )	165.43			
Water density $(\gamma_w)$ (lb/ft <sup>3</sup> )	62.43			



Variable	HW 1			
USBR Method				
Velocity (V) (ft/s)	8.89			
Maynord M	ethod			
Water depth $(d)$ (ft)	1.64			
Stability coefficient $(C_s)$ (unitless)	0.3			
Velocity distribution coefficient $(C_{\nu})$ (unitless)	1			
Thickness coefficient $(C_T)$ (unitless)	1.5			
Stone density ( $\gamma_s$ ) (lb/ft <sup>3</sup> )	165.43			
Water density $(\gamma_w)$ (lb/ft <sup>3</sup> )	62.43			
Velocity (V) (ft/s)	8.89			
Gravity $(g)$ (ft/s <sup>2</sup> )	32.2			
Side slope correction $(K_1)$ (unitless)	1			
Θ (°)	20			
Ø (°)	40			

Newly constructed features can be vulnerable to erosion. This is particularly true before vegetation has been established. While low-flow events should not intensify erosion, the concern for erosion occurs when high flows or precipitation events occur during construction or prior to vegetation establishment. A 100% biodegradable erosion control blanket, native seed, and live stakes are to be installed along the level spreader and wetland perimeter for immediate erosion protection. Over time, the blanket will biodegrade, while the live stakes and native seed species will establish to provide long-term soil stability.

#### **6.2.2 Construction Timing**

Based on resident fish species and their respective life cycles, in-stream work will be regulated by the fisheries warmwater timing window (July 15<sup>th</sup> to March 15<sup>th</sup>), unless otherwise directed by the Ministry of Natural Resources (MNR).

Vegetation removals associated with clearing, site access and staging should occur outside the key breeding bird period identified by Environment Canada for migratory birds to ensure compliance with the *Migratory Birds Convention Act, 1994* (MBCA) and *Migratory Bird Regulations*. The breeding season for migratory birds in this part of the country typically extends from as early as March 1<sup>st</sup> to as late as September 15<sup>th</sup>. Should tree removals be required during key breeding bird season, a qualified biologist should inspect those trees to ensure they do not contain nesting birds. It is understood that the MBCA is not limited to cutting woody vegetation, but also applies to topsoil stripping and grubbing activities, as there are ground nesting bird species that are protected under the Act.

# **6.2.3 Best Management Practices**

The design elements are unique and as such, the designer or representative should be part of construction supervision to ensure proper installation and function of the design elements. The designer should confirm materials are appropriate prior to installation. This will ensure the feature functions as



intended. On-site supervision will ensure a rapid response to construction issues. The constructed feature should be deemed stable by the designer, prior to flow introduction.

All works should be isolated from the surrounding natural areas in order to mitigate potential impacts, such as sediment loading. The perimeter of the constructed feature should be stabilized using the prescribed combination of biodegradable erosion control blankets, live staking, and seed. If required, unwatering discharge should be pumped at least 30 m from the existing feature through a filter bag prior to release. The water should be dispersed across the area through straw bales or Filtrexx $\otimes$  SiltSoxx $^{\text{\tiny TM}}$ .

All materials and equipment will be stored and operated in such a manner that prevents any deleterious substances from entering the water. Vehicle and equipment refuelling and/or maintenance will be conducted away from the watercourse and be free of fluid leaks and externally cleaned/degreased to prevent the release of deleterious substances. Machinery should arrive on site in a clean condition (including free of mud/soil/dirt from other locations; including clean wheels/tires/tracks) and should be maintained free of fluid leaks. To reduce the spread of invasive species, equipment should be cleaned before being brought onsite and before leaving site. For guidance in this regard, please refer to the Clean Equipment Protocol for Industry available online: (https://www.ontarioinvasiveplants.ca/wp-content/uploads/2016/07/Clean-Equipment-Protocol\_June2016\_D3\_WEB-1.pdf).

# **6.2.4 Post-construction Monitoring**

A post-construction monitoring program is recommended to assess the performance of the implemented design. Monitoring observations can also be used to determine the need for remedial works, if required. Inspections and monitoring should take place for three full calendar years post-construction. The following monitoring and reporting activities are suggested for the outfall treatment:

- General observations of the outlet treatment should be documented after construction and after the first large flow event to identify any potential areas of erosion concern
- Collect a detailed photographic record of site conditions, including monumented and georeferenced photographs at the treatment location
- A general vegetation survey at the outfall locations in the spring of each year
- A yearly report for the first two years, with a final report at the end of the three-year period
- · Monitoring activities should be undertaken by a qualified fluvial geomorphologist
- Sites should be reviewed annually to identify natural variability of the system. Reporting should be provided annually, with a summary report at the end of each year

# **7 Summary and Recommendations**

A hazard assessment completed for both Tributary 1 of Fletcher's Creek and Fletcher's Creek itself determined that a 5 m toe erosion allowance was appropriate given the findings of Soil Engineering Ltd.'s 2020 study and our field observations. This toe erosion allowance was applied wherever the watercourses were within 15 m of the valley wall, in accordance with MOE (2003) guidelines. The final erosion hazard linework for the confined systems is based on the results of a geotechnical slope stability study by Soil Engineers Ltd.

For the short section of channel at the upstream extent of Tributary 1, **Reach FCT-2**, which lacked a valley wall, a meander belt width of 10 m was calculated using a Modified Williams Area Model (1986). Additionally, the meander belt width previously delineated by Parish (2011) along the main branch of Fletcher's Creek (**Reach FC-2**) was refined to be truncated at the toe of slope for Redside Dace habitat delineation. These hazard limits are graphically displayed in **Appendix A**.



For Fletcher's Creek, a desktop assessment identified the ideal location for an outfall location, and an outfall design was provided to mitigate the potential for localized erosion at this site. In terms of potential systemic erosion impacts to Fletcher's Creek resulting from the proposed development, it was determined that given the drainage area of the watercourse relative to the contributing drainage that no exacerbated erosion is expected.

Additionally, the crossing location was also assessed through field verification. The location of the crossing (**Reach FCT-3**) is proposed to cross a poorly defined and vegetation-controlled feature that lacks erosion. A crossing requirement of 2.37 m was recommended however, the minimum crossing width provided below should be considered in conjunction with other requirements.

We trust this report meets your requirements. Should you have any questions please contact the undersigned.

Respectfully submitted,

Paul Villard Ph.D., P.Geo., CAN-CISEC Director, Principal Geomorphologist

Rachel Abbott, B.Sc., G.I.T

Environmental Scientist, Project Lead

bl allat

Rachel Sun, M.Sc.

Red Su

Restoration Design Technician



#### 8 References

Acrement, G. J., & Schneider, V. R. 1989. Guide for selecting Manning's roughness coefficients for natural channels and flood plains.

Brierley, G. J. and Fryirs, K. A. 2005. Geomorphology and River Management: Applications of the River Styles Framework. Blackwell Publishing, Oxford, UK, 398pp. ISBN 1-4051-1516-5.

Chapman, L.J. and Putnam, D.F. 1984. The Physiography of Southern Ontario. Ontario Geological Survey, Special Volume 2, Map 226.

Credit Valley Conservation (CVC). 2012. Stormwater Management Criteria.

Downs, P.W. 1995. Estimating the probability of river channel adjustment. Earth Surface Processes and Landforms, 20: 687-705.

Fischenich, C. 2001. Stability Thresholds for Stream Restoration Materials. EMRRP Technical Notes Collection (ERDC TN-EMRRP-SR-29), U.S. Army Engineer Research and Development Center, Vicksburg, MS.

Galli, J. 1996. Rapid Stream Assessment Technique, Field Methods. Metropolitan Washington Council of Governments.

GEI Consultants Canada Ltd. 2025. Environmental Impact Study – 7140 Hurontario Street, Mississauga, Ontario

Geomorphic Solutions. 2012. Detail Geomorphic Assessment – Fletchers Creek: FINAL. DeZen Industrial Lands

Isbash, S.V. 1936. Construction of dams by depositing rock in running water. Transactions, Second Congress on Large Dams. Washington, D.C.

Maynord, S.T. 1988. Stable Riprap size for open channel flows. Technical Report HL-88-4. U.S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi.

Ministry of Environment (MOE). 2003. Ontario Ministry of Environment. Stormwater Management Guidelines.

Ministry of Natural Resources (MNR). 2002. Technical Guide – River & Stream Systems: Erosion Hazard Limit.

Montgomery, D.R. and J.M. Buffington. 1997. Channel-reach morphology in mountain drainage basins. Geological Society of America Bulletin, 109 (5): 596-611.

Natural Resources Conservation Service (NRCS). 2007. Stone Sizing Criteria, Technical Supplement 14C, Part 654, National Engineering Handbook. U.S. Department of Agriculture.

Ontario Geological Survey (OGS). 2010. Surficial geology of Southern Ontario. Ontario Geological Survey. Miscellaneous Release – Data 128-REV.

Parish Geomorphic. 2011. DRAFT DeZen: Fletcher's Creek Hazard Assessment

Peterka, A.J. 1958. Hydraulic Design of Stilling Basins and Bucket Energy Dissipators. USBR Engineering Monograph 25. U.S. Department of the Interior, Bureau of Reclamation, Denver.

Richards, C., Haro, R.J., Johnson, L.B. and Host, G.E. 1997. Catchment and reach-scale properties as indicators of macroinvertebrate species traits. Freshwater Biology, 37: 219-230.

Skira & Associates Ltd. 2025. Functional Servicing Report – DeZen Industrial Lands



Soil Engineers Ltd. 2008. Geotechnical Investigation for Slope Stability Study – Southwest Quadrant of Highway 407 and Hurontario Street

Soil Engineers Ltd. 2016. Supplementary Slope Stability Study Letter Report – Proposed Employment Lands – DeZen Industrial – Phase 2

Soil Engineers Ltd. 2020. Supplementary Slope Stability Study Letter Report – Proposed Employment Lands – DeZen Industrial – Phase 2

Toronto and Region Conservation Authority. 2004. Belt Width Delineation Procedures.

Vermont Agency of Natural Resources (VANR). 2007. Step 7: Rapid Geomorphic Assessment (RGA). Phase 2 Stream Geomorphic Assessment.


Ward, A. D. Mecklenberg, J. Mathews, and D. Farver. 2002. Sizing Stream Setbacks to Help Maintain Stream Stability. Paper Number: 022239. 2002 ASAE Annual International Meeting. Chicago, IL, USA. July 28-July 31, 2002

Wentworth, C. 1922. A Scale of Grade and Class Terms for Clastic Sediments. The Journal of Geology, 30(5), 377-392.

Williams, G.P. 1986. River meanders and channel size. Journal of Hydrology, 88 (1-2): 147-164.

Wolman, M.G. 1954. A method of sampling coarse riverbed material. Transactions of the American Geophysical Union, 35 (6): 951 – 956

Appendix A: Erosion Hazard Mapping



Appendix B: Historical Aerial Imagery




**Location:** Hurontario Street, Mississauga, Ontario **Year:** 1954

**Source:** National Air Photo Library Yellow Point: Hurontario Street



**Location:** Hurontario Street, Mississauga, Ontario **Year:** 1977

**Source:** National Air Photo Library Yellow Point: Hurontario Street



Location: Hurontario Street, Mississauga, Ontario

**Year:** 1989

**Source:** National Air Photo Library **Yellow Point:** Hurontario Street



**Location:** Hurontario Street, Mississauga, Ontario **Year:** 2002

Source: Google Earth Pro Yellow Point: Hurontario Street



**Location:** Hurontario Street, Mississauga, Ontario **Year:** 2002

Source: Google Earth Pro Yellow Point: Hurontario Street



Location: Hurontario Street, Mississauga, Ontario

**Year:** 2018

**Source:** Google Earth Pro **Yellow Point:** Hurontario Street



**Location:** Hurontario Street, Mississauga, Ontario **Year:** 2023

**Source:** Google Earth Pro **Yellow Point:** Hurontario Street

Appendix C: Photographic Field Record

Photo 1
Outlet Headwall Location, 7140 Hurontario Street,
Mississauga, ON



Photograph of staked headwall location facing the direction of the tie-in location.





Photograph of the valley wall behind the headwall location. The slope is well vegetated and showed a lack of erosion at the time of assessment.

i



Photograph showing the confluence between the historic channel and **Reach FC-2**. The confluence was located at an outer meander bend along **Reach FC-2**.



Photograph of **Reach FC-2** facing upstream. Leaning trees and woody debris jams that impacted flow were common throughout the reach.



Coarse material was commonly observed along the channel bed. A suspended armour layer was observed in the channel banks as well. The bank materials consisted of clay, silt materials with some coarse materials due to the suspended armour layer.





Photograph of **Reach FCT-1** facing upstream. The channel was confined and had low flow conditions at the time of assessment. Exposed roots and undercutting were commonly observed. The bed was also eroded into parent material (till) in a localized portion of the reach upstream.





Photograph of **Reach FCT-1**. Active erosion was noted along this reach however; the channel banks were observed to be well vegetated. Some fallen and leaning trees were also observed, indicating some widening along the reach.





Photograph of **Reach FCT-2** facing upstream. The reach was partially confined and had a high density of woody debris and exposed roots.

Photo 9
Reach FCT-2, 7140 Hurontario Street, Mississauga, ON



Photograph of **Reach FCT-2** located at the upstream extent. Note that banks are less defined as the channel moved upstream towards **FCT-3**.

Photo 10
Reach FCT-3, 7140 Hurontario Street, Mississauga, ON



Photograph of **Reach FCT-3** facing upstream towards the pond. Though dry at the time of assessment, much of the reach was comprised of an online wetland containing cattails and phragmites.

Photo 11
FCT-3 Approx. Crossing Location, 7140 Hurontario Street, Mississauga, ON



The proposed water crossing location is situated across **Reach FCT-3.** The location's topography was unconfined, flat, and the feature was poorly defined. Herbaceous plants and tall grasses dominated the area.

**Appendix D: Field Observations** 

	erai Site Cha			ect Number:	216 C		
Date:		2015-0	7-18	Stream:		Hetches's	reek
Time:		9:09		Reach:		FC-2	
Weath	er:	24°6, Sun		Location:		Derry Cocs	st Vs.
Field 9	Staff:	NHCM 1	144	Watershed/Subwaters	hed:	/	
Featur	es	Monitoring	Site	Sketch ( )	9 57	-51-54	Compass
Featur	Reach break Station location Cross-section Flow direction Riffle Pool Sediment bar Eroded bank/slope Undercut bank Bank stabilization Leaning tree Fence Culvert/outfall Swamp/wetland Grasses Tree Instream log/tree Woody debris Beaver dam Vegetated island ype Standing water H1. Scarcely perceptible Smooth surface flow Upwelling Rippled Unbroken standing wave Chute Free fall H9/ ate Silt Sand Gravel Small cobble Large cobble  Benchmark Backsight	Monumented XS Monumented photo Monumented photo direction Sediment sampling Erosion pins Scour chains Additional Symbols  A Back water flow  Se Small boulder ST Large boulder SR Bimodal SP Bedrock/till  EP Erosion pin RB Rebar				-31-54  DEXPOSED TO	density
DS WDJ	Downstream Woody debris jam	US Upstream		16			
VWC	Woody debris jam Valley wall contact	TR Terrace FC Flood chute		MARAN			
BOS			7				
	Bottom of slope	FP Flood plain	Photo				
TOS	Top of slope	KP Knick point	Note	s:			

Version #4 Last edited: 21/02/2023

Senior staff sign-off (if required): \_\_\_\_\_ Checked by: \_\_\_\_ Completed by:

General Site Characteristics Project Number: 75107

Date:		2025-07-18	Stream	•	Fletcher's Craek
Time:		9.30	Reach:		F/-2
Weatl	her:	ZYPL SUN	Locatio	n:	Derry Crest Dr.
Field	Staff:	NA CM	Waters	hed/Subwatershed:	1000170
Featur	'es	Monitoring			dox buil bed
	Reach break Station location Cross-section Flow direction Riffle Pool Sediment bar Eroded bank/slope	Monitoring  Long-profile  Monumented XS  Monumented photo  Monumented photo  direction  Sediment sampling  Erosion pins  Scour chains  Additional Symbols	Site Sketch		Compass  Fortunation  Source  Since
***  Flow T  H1  H2  H3  H4  H5	Grasses Tree Instream log/tree Woody debris Beaver dam Vegetated island		Course	WD = 0.16 m BFD = 0.42 BFW=7.02 V=0.48 mb	of & Slowe
H6 H7 H8 H9		The state of the s	Golf o		sosal scour on both
\$1 \$2 \$3 \$4 \$5 Other	Silt Sand Gravel Small cobble Large cobble	\$6 Small boulder \$7 Large boulder \$8 Bimodal \$9 Bedrock/till	S2- 37		bounks  = 15.2m  of Slowk
BM BS DS WDJ VWC BOS	Benchmark Backsight Downstream Woody debris jam Valley wall contact Bottom of slope Top of slope	EP Erosion pin  RB Rebar  US Upstream  TR Terrace  FC Flood chute  FP Flood plain  KP Knick point	Photos: Notes:	The state of the s	50 00

Version #4

Last edited: 21/02/2023

Senior staff sign-off (if required): \_\_\_\_\_ Checked by: \_\_\_\_ Completed by: \_\_\_\_ Page \_\_ of \_\_\_

Project Number: 25107 **General Site Characteristics** Date: Stream: Time: Reach: ZYCL, Sun Weather: Location: Field Staff: Watershed/Subwatershed: **Features** Monitoring Site Sketch Compass Reach break Station location Monumented XS Cross-section 0 Monumented photo Flow direction Monumented photo Riffle direction Pool Sediment sampling Erosion pins WILLIAM . Sediment bar 8 Eroded bank/slope Scour chains Undercut bank **Additional Symbols** Bank stabilization ->>> Leaning tree PD=0.37m X----X Fence Culvert/outfall Swamp/wetland WWW Grasses Tree Instream log/tree \* \* \* Woody debris WWW. Beaver dam WV Vegetated island Flow Type H1 Standing water H1A Back water X55 H2 Scarcely perceptible flow WW=7.25m **H3** Smooth surface flow BFW=8.51 **H4** Upwelling H5 Rippled BFD=1.3m Unbroken standing wave **H6** V=0.14m H7 Broken standing wave UC=0-11m **H8** Chute H9 Free fall H9A Dissipates below free fall Substrate **S1** Silt 56 Small boulder **S2** Sand **S7** Large boulder **S**3 Gravel **S8** Bimodal **S4** Small cobble Bedrock/till **S5** Large cobble Other BM Benchmark EP Erosion pin BS Backsight RB Rebar DS Downstream US Upstream 52 WDJ Woody debris jam TR Terrace on OB smar **VWC** Valley wall contact

Version	#4
---------	----

BOS

TOS

Last edited: 21/02/2023

Bottom of slope

Top of slope

FC

FP

KP

Flood chute

Flood plain

Knick point

Senior staff sign-off (if required): \_\_\_\_\_ Checked by: \_

Photos:

Notes:

Completed by:

for woode

Project Number: 75102 **General Site Characteristics** 2025-07 Date: Stream: Time: Reach: Weather: Location: Field Staff: Watershed/Subwatershed: **Features** Monitoring Site Sketch -o--o- Long-profile Reach break Station location Monumented XS Cross-section Monumented photo 0 Flow direction Monumented photo 0.42m Riffle direction Pool Sediment sampling шш Erosion pins WILLIAM . Sediment bar 8 HHHHHH Eroded bank/slope Scour chains **Additional Symbols** Undercut bank XXXXXX Bank stabilization ->>> Leaning tree x---x---x Fence Culvert/outfall Swamp/wetland PD WWW Grasses 0.41 **3** Tree Instream log/tree \*\*\* Woody debris RL= 17.0 m \*\*\*\*\*\*\* Beaver dam W Vegetated island Flow Type Standing water H1A Back water H1 **H2** Scarcely perceptible flow **H3** Smooth surface flow Upwelling **H4 H5** Rippled panic **H6** Unbroken standing wave **H7** Broken standing wave H8 Chute **H9** Free fall H9A Dissipates below free fall Substrate \$1 Silt Small boulder 56 **S2** Sand **S7** Large boulder **S3** Gravel **S8** Bimodal XS4 BFW=836m UF0.25 **S4** Small cobble 59 Bedrock/till **S5** Large cobble BFD=1.01m Other WD=0.71m ВМ Benchmark EP Erosion pin WW=7.35m 115-BS Backsight RB Rebar V = 0.04m/s 0.09ml DS Downstream US Upstream

Version #4

WDJ

**VWC** 

BOS

TOS

Last edited: 21/02/2023

Woody debris jam

Valley wall contact

Bottom of slope

Top of slope

TR

FC

FP

KP

Terrace

Flood chute

Flood plain

Knick point

Senior staff sign-off (if required): \_\_\_\_\_ Checked by: \_

Photos:

Notes:

Completed by: \_\_\_\_



General Site Characteristics

Project Number: ZSIO7

ocheral bice	Gildi de Celi Seles	roject Hamber of	
Date:	2025-07-18	Stream:	Flethers Creek
Time:	11:00	Reach:	FC-2
Weather:	74°C. Sym	Location:	Derry Crest Dr.
Field Staff:	NHZMI	Watershed/Subwatershed:	

Field S	Staff:		HCN1
Featur	es	Monito	oring
	Reach break	-0-0-0-	Long-profile
只	Station location	<b>  </b>	Monumented XS
XX	Cross-section	0	Monumented photo
	Flow direction		Monumented photo
~~	Riffle	*	direction
$\bigcirc$	Pool		Sediment sampling
WILLIAM .	Sediment bar	<u> </u>	Erosion pins
<del>                                     </del>	Eroded bank/slope	8	Scour chains
	Undercut bank	Additi	onal Symbols
XXXXXX	Bank stabilization		
->>>	Leaning tree		
XX	Fence		
	Culvert/outfall		
	Swamp/wetland		
AAA	Grasses		
	Tree		
	Instream log/tree		
***	Woody debris		
*******	Beaver dam		
(VV)	Vegetated island		
Flow T			
H1 H2	Standing water H1		water
H3	Scarcely perceptible Smooth surface flow		
H4	Upwelling		
H5	Rippled		
Н6	Unbroken standing v	wave	
H7	Broken standing way		
Н8	Chute	• •	
Н9	Free fall H9	A Diss	ipates below free fall
Substr	ate		
S1	Silt	S6	Small boulder
S2	Sand	<b>S7</b>	Large boulder
S3	Gravel	S8	Bimodal
S4	Small cobble	S9	Bedrock/till
S5	Large cobble		
Other			
вм	Benchmark	EP	Erosion pin
BS	Backsight	RB	Rebar
DS	Downstream	US	Upstream
WDJ	Mondy dobrio inno	TR	Terrace
	Woody debris jam		
VWC	Valley wall contact	FC	Flood chute
VWC BOS	,		Flood chute Flood plain

	Watershed/Subwatershed:	
Site	Sketch	Compass
1	Roach Break	
	T 61 3 01	
	Billi	
	Billing	
	R. I (I/V)	
	8.5.	
	B& ( )// me al	
	1 SZ- mixed mixed	(1/
V	V XXX 9803	1/
	00 see 18 54-55 \\\\\\	/\/
. 1	00000 1 8 5450 11 11	<i>\</i> \
V	11 (18 9)	
8	V JUC=0.37m	
	54.56	1.06m
	- 0+ PD=	1.06W
	O.Ilm \	X - 10 - 10 - 10 - 10 - 10 - 10 - 10 - 1
	a.lim	R
	W The survey of	
	Y	
hoto		

Version #4 Last edited: 21/02/2023

Senior staff sign-off (if required): \_\_\_\_\_ Checked by: \_\_\_\_\_ Completed by:



Rapid Stream Assessment Technique Project Number: ZSQZ Date: 2015-02-Stream: Time: Reach: Weather: Location: Field Staff: Watershed/Subwatershed: Category Poor Fair Good Excellent < 50% of bank network</li> 50-70% of bank network · 71-80% of bank network > 80% of bank network stable stable stable stable Recent bank sloughing, Recent signs of bank Infrequent signs of bank · No evidence of bank slumping or failure sloughing, slumping or sloughing, slumping or sloughing, slumping or frequently observed failure fairly common failure failure Stream bend areas highly Stream bend areas Stream bend areas stable Stream bend areas very unstable unstable Outer bank height 0.6-0.9 stable Outer bank height 0.9-Outer bank height 1.2 m m above stream bank (1.2-Height < 0.6 m above above stream bank 1.2 m above stream 1.5 m above stream bank stream (< 1.2 m above (2.1 m above stream bank stream bank for large for large mainstem areas) bank for large mainstem (1.5-2.1 m above stream Bank overhang 0.6-0.8 m mainstem areas) bank for large mainstem areas) Bank overhang < 0.6 m Bank overhang > 0.8-1.0 areas) Bank overhang 0.8-0.9m Channel Stability Young exposed tree roots Young exposed tree roots Exposed tree roots Exposed tree roots old, abundant common predominantly old and large and woody > 6 recent large tree falls 4-5 recent large tree falls large, smaller young roots Generally 0-1 recent large per stream mile per stream mile scarce tree falls per stream mile 2-3 recent large tree falls per stream mile Bottom 1/3 of bank is generally highly erodible highly erodible material generally highly resistant generally highly resistant Plant/soil matrix severely material plant/soil matrix or material plant/soil matrix or material compromised Plant/soil matrix Clay/Silcompromised Channel cross-section is Channel cross-section is Channel cross-section is · Channel cross-section is generally trapezoidallygenerally trapezoidallygenerally V- or U-shaped generally V- or U-shaped shaped shaped Point range 0 0 1 0 2 Z 3 0 4 0 5 0 6 0 7 0 8 □ 9 □ 10 □ 11 > 75% embedded (> • Riffle embeddedness < 50-75% embedded (60-25-49% embedded (35-85% embedded for large 85% embedded for large 59% embedded for large 25% sand-silt (< 35% mainstem areas) mainstem areas) mainstem areas) embedded for large mainstem areas) · Few, if any, deep pools · Low to moderate number Moderate number of deep · High number of deep pools Pool substrate of deep pools (> 61 cm deep) composition >81% sand-Pool substrate Pool substrate composition (> 122 cm deep for large silt composition 30-59% sand-silt mainstem areas) 60-80% sand-silt Pool substrate composition <30% sand-silt Streambed streak marks Streambed streak marks Streambed streak marks Streambed streak marks Channel and/or "banana"-shaped and/or "banana"-shaped and/or "banana"-shaped and/or "banana"-shaped Scouring/ sediment deposits sediment deposits sediment deposits sediment deposits absent Sediment common common uncommon Deposition · Fresh, large sand · Fresh, large sand Fresh, large sand deposits Fresh, large sand deposits deposits very common in deposits common in uncommon in channel rare or absent from channel channel channel Small localized areas of No evidence of fresh Moderate to heavy sand Small localized areas of fresh sand deposits along sediment deposition on deposition along major fresh sand deposits along top of low banks overbank portion of overbank area top of low banks · Point bars present at Point bars common, Point bars small and stable, Point bars few, small and most stream bends, moderate to large and well-vegetated and/or stable, well-vegetated moderate to large and unstable with high armoured with little or no and/or armoured with little unstable with high

Point range Version #2

Last edited: 10/02/2023

amount of fresh sand

Senior staff sign-off (if required): Checked by:

amount of fresh sand

□ 3 □ 4

□ 5 □ 6

fresh sand

Completed by: NH

or no fresh sand

Ø 7 0 8



Date: 20	125-07-18	PN: 25102	Location:	
Category	Poor	Fair	Good	Excellent
6	Wetted perimeter < 40%     of bottom channel width     (< 45% for large     mainstem areas)	Wetted perimeter 40- 60% of bottom channel width (45-65% for large mainstem areas)	Wetted perimeter 61-85% of bottom channel width (66-90% for large mainstem areas)	Wetted perimeter > 85% of bottom channel width (> 90% for large mainstem areas)
	Dominated by one habitat type (usually runs) and by one velocity and depth condition (slow and shallow) (for large mainstem areas, few riffles present, runs and pools dominant, velocity and depth diversity low)	<ul> <li>Few pools present, riffles and runs dominant.</li> <li>Velocity and depth generally slow and shallow (for large mainstem areas, runs and pools dominant, velocity and depth diversity intermediate)</li> </ul>	<ul> <li>Good mix between riffles, runs and pools</li> <li>Relatively diverse velocity and depth of flow</li> </ul>	Riffles, runs and pool habitat present     Diverse velocity and depth of flow present (i.e., slow, fast, shallow and deep water)
Physical Instream	Riffle substrate composition: predominantly gravel with high amount of sand     < 5% cobble	<ul> <li>Riffle substrate composition: predominantly small cobble, gravel and sand</li> <li>5-24% cobble</li> </ul>	Riffle substrate composition: good mix of gravel, cobble, and rubble material     25-49% cobble	Riffle substrate composition: cobble, gravel, rubble, boulder mix with little sand > 50% cobble
Habitat	Riffle depth < 10 cm for large mainstem areas	Riffle depth 10-15 cm for large mainstem areas	large mainstem areas	Riffle depth > 20 cm for large mainstem areas
	Large pools generally <     30 cm deep (< 61 cm for large mainstem areas)     and devoid of overhead cover/structure	Large pools generally 30- 46 cm deep (61-91 cm for large mainstem areas) with little or no overhead cover/structure	Large pools generally 46-61 cm deep (91-122 cm for large mainstem areas) with some overhead cover/structure	Large pools generally > 61 cm deep (> 122 cm for large mainstem areas) with good overhead cover/structure
	Extensive channel alteration and/or point bar formation/enlargement	Moderate amount of channel alteration and/or moderate increase in point bar formation/enlargement	Slight amount of channel alteration and/or slight increase in point bar formation/enlargement	No channel alteration or significant point bar formation/enlargement
	• Riffle/Pool ratio 0.49:1 ; ≥1.51:1	• Riffle/Pool ratio 0.5- 0.69:1 ; 1.31-1.5:1	Riffle/Pool ratio 0.7-0.89 1 ; 1.11-1.3:1	• Riffle/Pool ratio 0.9-1.1:1
11 0 61	• Summer afternoon water temperature > 27°C	Summer afternoon water temperature 24-27°C	Summer afternoon water temperature 20-24°C	Summer afternoon water temperature < 20°C
Point range	0 0 1 0 2	□ 3 □ 4	□ 5 □ 6	7 0 8
antel ac	• Substrate fouling level: High (> 50%)	Substrate fouling level:     Moderate (21-50%)	• Substrate fouling level: Very light (11-20%)	Substrate fouling level:     Rock underside (0-10%)
Water Quality	Brown colour     TDS: > 150 mg/L	• Grey colour • TDS: 101-150 mg/L	• Slightly grey colour • TDS: 50-100 mg/L	• Clear flow • TDS: < 50 mg/L
Water Quality	Objects visible to depth     < 0.15m below surface	Objects visible to depth 0.15-0.5m below surface	Objects visible to depth     0.5-1.0m below surface	Objects visible to depth > 1.0m below surface
107	Moderate to strong organic odour	Slight to moderate organic odour	Slight organic odour	• No odour
Point range	0 0 1 0 2	0304	D 5 🕅 6	□ 7 □ 8
Riparian Habitat	Narrow riparian area of mostly non-woody vegetation	Riparian area predominantly wooded but with major localized gaps	Forested buffer generally     31 m wide along major     portion of both banks	Wide (> 60 m) mature forested buffer along both banks
Conditions	Canopy coverage:     <50% shading (30% for large mainstem areas)	Canopy coverage: 50- 60% shading (30-44% for large mainstem areas)	60-79% shading (45-59% for large mainstem areas)	Canopy coverage:     >80% shading (> 60% for large mainstem areas)
Point range	□ 0 □ 1	□ 2 □ 3	<b>№ 4 □ 5</b>	□ 6 □ 7
otal overall s	score (0-42) =	Poor (<13) F	air (13-24) Good (25-	34) Excellent (>35)

Version #2 Last edited: 10/02/2023

Senior staff sign-off (if required): \_\_\_\_\_ Checked by: \_\_\_

Completed by: \_

Reach Characteristics	tics Project Number:	1 810%				M O R P H - X "
Date:	2025-07-18	Field Staff:	CM NH	Watershed/Subwatershed:	ershed:	
Time:	9:00	Stream:	Futaner's a	VEEL UTM (Upstream):		
Weather:	No 200	Reach:	FC-2	UTM (Downstream):		
A	Valley Type 🥏 Channel Type	Q	Channel Zone		roundwater Location	<b>フト</b> 〉 + + > -
<u> </u>	0	C	L	years	E ENIGETICE OF GLOGIED MATER FOCATION:	Photo:
Riparian Vegetation			Aquatic & Instream Vegetation	getation	Water Quality	
Dominant Type (Table 6)	Coverage Channel Widths	Age (yrs)	Type Woody (Table 8)	Woody Debris WD Density  Prin Cutbank   Low   WDJ/50m:	Odour (Table 16)	Turbidity (Table 17)
Encroachment	nented (	☐ Established (5-30)	N,			
(Table 7)	☐ Continuous ☐ > 10	Mature (>30)	0,0	□ Not Present 和 High	-	
<b>Channel Characteristics</b>	tics					
Sinuosity Type 2	Sinuosity Degree (7able 10)	Bank Angle □ 0 - 30	Bank Erosion (Tab $\square < 5\%$	(Table 19) Clay/Silt Sand Gi	Gravel Cobble Boulder F	Parent Rootlets
Gradient (Table 11)	# of Channels	30 - 60	□ 5 - 30%	Riffle		
Entrenchment (Table 13)	Bank Failure 2,5,	Dundercut	60 – 100% Bed (If no riffle-pool,			
Down's Model (Table 15)	Bankfull Indicators 1,3 ≤ (Table 18)		Bankfull Width 7.25	8.36 Wetted	Wetted Width (m) 7,40	7,35
Sed Sorting MOD (Table 20)	Sediment Transport □ Ye Observed?	☐ Yes X No ☐ Not Visible	Bankfull Depth 0.72	1.3 1.01 Wetted	Wetted Depth (m) 0.34	0.3
Transport Mode (Table 21)	% of Bed Active		Undercuts (m)	0.86 0.11 Veloc	Velocity (m/s) △。 2	2004
Geomorphic 4-8	Mass Movement (73)		Pool Depth oils	0.93 0.42 Velocit	Velocity Estimate WB N	E E
Riffle-Pool Spacing (m):	% Riffles: 35	% Pools: 35	Riffle Length (m) 6,35	15.2 17.0 Meander Amplitude (m)	Amplitude (m)	
tes:		5	100 m			33
O VWC observed	en d	SA KS	sughout reach	OUT ON WOW ICE		Co (Legistra)
· Copylor	meanders presen	されていて、こ	Crate Ped Spiles	ex amply tude	could not be acc	accurately measur
Underch	/basal scour	the sea	o thed	inside of been	nuderch	
· Mass ratation	short suches/s	rosdo samil	who are poth	COMMES.	468	
Photos: Large	observed through	cousing bac	T Watering CA	427100 Floor F0		
more C3	(market	5 84	6 -	Cook		
#4 ted: 04/0			Senior staff sign	(if required):	Checked by:Comp	Completed by: (M)



Project Number: 25102 **Rapid Geomorphic Assessment** Date: 2025-07-18 Stream: Fletcher's Creek Time: 11:28 Reach: 24 Weather: Sun Location: Field Staff: NH cm Watershed/Subwatershed: Geomorphological Indicator Present? Factor Process No. Description Value Yes No 1 Lobate bar 2 Coarse materials in riffles embedded Siltation in pools 3 Evidence of Aggradation 4 Medial bars 200 course materials (AI) 5 Accretion on point bars 6 Poor longitudinal sorting of bed materials 7 Deposition in the overbank zone - 1 area US of WDJ Sum of indices = 0.29 1 Exposed bridge footing(s) 2 Exposed sanitary / storm sewer / pipeline / etc. 3 Elevated storm sewer outfall(s) 4 Undermined gabion baskets / concrete aprons / etc. Evidence of 5 Scour pools downstream of culverts / storm sewer outlets Degradation Cut face on bar forms 6 (DI) 7 Head cutting due to knickpoint migration 8 Terrace cut through older bar material 9 Suspended armour layer visible in bank 10 Channel worn into undisturbed overburden / bedrock - | ave a 2 0.32 Sum of indices = 1 Fallen / leaning trees / fence posts / etc. 2 Occurrence of large organic debris 3 Exposed tree roots 4 Basal scour on inside meander bends Evidence of 5 Basal scour on both sides of channel through riffle Widening 6 Outflanked gabion baskets / concrete walls / etc. (WI) 7 Length of basal scour >50% through subject reach 8 Exposed length of previously buried pipe / cable / etc. 9 Fracture lines along top of bank 10 Exposed building foundation NIV Sum of indices = Formation of chute(s) - \ 1 dry chute 2 Single thread channel to multiple channel Evidence of Evolution of pool-riffle form to low bed relief form 3 Planimetric Form 4 Cut-off channel(s) Adjustment 5 Formation of island(s) (PI) Thalweg alignment out of phase with meander form 6 Bar forms poorly formed / reworked / removed 7 Sum of indices = Notes: High dunsity of fallen thees exposed roots Stability Index (SI) = (AI+DI+WI+PI)/4 = 0.34In Transition/Stress In Adjustment In Regime □ 0.00 - 0.20 both banks 0.21 - 0.40 □ 0.41 Slumping more common in extent Senior staff sign-off (if required): \_\_\_\_\_ Checked by: \_\_\_\_ Completed by: \_\_\_\_

Version #3

Last edited: 10/02/2023



Project Number: 25/02

		1 0 -	istics	
Date:		10	25-07-18	Stream: Fletcher's (seek
Time:		17:	45	Reach:
Weath	er:	74	°C, Sunn	Location: Destributed Dr.
Field Staff:		UCM	Watershed/Subwatershed:	
			1 67	Site Sketch Compass
Featur		Monitor	ong-profile	Site Sketch Compass
只	Reach break Station location	l .	lonumented XS	-suspended 1
××	Cross-section		Ionumented photo	armor layer
	Flow direction			31:-0.45
~	Riffle		Ionumented photo irection	
	Pool	*********	ediment sampling	53-55-/8-VWC
	Sediment bar	Linear Company	rosion pins	
<del>           </del>	Eroded bank/slope	0	cour chains	2 1-exposed
	Undercut bank		nal Symbols	1 Posts
XXXXXX	Bank stabilization	Addition	iai oyiiibolo	01://
<b>≫</b>	Leaning tree		- a	
//// xx				Deposition on
	Culvert/outfall			overbank BEW: 12 0.27
	Swamp/wetland			167+841 20000
WWW	Grasses			V Chry 194 1 X - Exposed root "
	Tree			Field Velocity:
	Instream log/tree			O. 19 Deposition
***	Woody debris			001 - (5220
**************************************	Beaver dam			
VV	Vegetated island			Gully 1207
Flow 1		1		1/5151
H1	Standing water H1	A Back w	vater	153/19.27 UC
H2	Scarcely perceptible			
нз	Smooth surface flow			Ris. on
Н4	Upwelling			2615000 /
Н5	Rippled			BFW. 0.92, 75
Н6	Unbroken standing	wave		BFD10 4 51 100 52111
H7	Broken standing wa	ve		WANG OZYM XEETX
Н8	Chute			WW: 0.246.12 X
Н9/	Free fall H9	A Dissip	ates below free fall	19
Substi	ate			
S1	Silt	S6	Small boulder	19494
S2	Sand	<b>S7</b>	Large boulder	10 × 2.0
S3	Gravel	<b>S8</b>	Bimodal	1/53/44
S4	Small cobble	<b>S9</b>	Bedrock/till	0.4 ( *** *** *** *** *** *** *** *** ***
S5	Large cobble	· · · · · · · · · · · · · · · · · · ·		1 V
Other				Banks: Frexposed Roots Ctay Sand 57:44
ВМ	Benchmark	EP	Erosion pin	Ctayosand SZSY
BS	Backsight	RB	Rebar	(**)
DS	Downstream	US	Upstream	
WDJ	Woody debris jam	TR	Terrace	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\
VWC	Valley wall contact	FC	Flood chute	V
BOS	Bottom of slope	FP	Flood plain	Photos:
	Top of slope	KP ·	Knick point	Notes:

Version #4	Senior staff sign-off (if required):	Checked by:	Completed b
Last edited: 21/02/2023			



Project Number: 25/02 **General Site Characteristics** Date: Stream: Time: Reach: Weather: Location: Field Staff: Watershed/Subwatershed: **Features** Monitoring Site Sketch Compass -o-o-o- Long-profile Reach break Station location → Monumented XS Cross-section Monumented photo 0 Flow direction Monumented photo direction Riffle Pool Sediment sampling Erosion pins CHANN Sediment bar 8 HHHHHH Eroded bank/slope Scour chains Undercut bank **Additional Symbols** XXXXXX Bank stabilization Leaning tree Fence Culvert/outfall Swamp/wetland WWW Grasses **3** Tree Instream log/tree \* \* \* Woody debris \*XXXXX Beaver dam WV Vegetated island Flow Type H1 Standing water H1A Back water H2 Scarcely perceptible flow Smooth surface flow НЗ **H4** Upwelling **H5** Rippled H6 Unbroken standing wave H7 Broken standing wave H8 Chute **H9** Free fall **H9A** Dissipates below free fall Substrate S1 Silt **S6** Small boulder **S2** Sand **S7** Large boulder \$3 Gravel **S8** Bimodal **S4** Small cobble 59 Bedrock/till **S5** Large cobble Other BM Benchmark EP Erosion pin BS Backsight RB Rebar DS Downstream US Upstream WDJ Woody debris jam TR Terrace **VWC** Valley wall contact FC Flood chute BOS Bottom of slope FP Flood plain Photos: TOS Top of slope KP Knick point Notes:

Version #4 Last edited: 21/02/2023 Senior staff sign-off (if required): \_\_\_\_\_ Checked by: \_\_\_\_ Completed by: \_\_\_\_



Page Z of Z



Rapid Stream Assessment Technique Project Number: 25102

Date:	2025-07-19	Stream:		Fletcher	er's Creek	
Time:	12:45	Reach:	1208	FTC-1		
Weather:	Sun 25°	Location:	printed had	Berny crest Dr.		
ield Staff:	NH CM	Watershed/Subwate				
Category	Poor	Fair	T	Good	Excellent	
et ley and deptin ht (he., slow, and deep	stable	50-70% of bank network stable Recent signs of bank sloughing, slumping or failure fairly common	stable • Infrequ	of bank network ent signs of bank ng, slumping or	<ul> <li>&gt; 80% of bank network stable</li> <li>No evidence of bank sloughing, slumping or failure</li> </ul>	
Channel	Stream bend areas highly unstable Outer bank height 1.2 m above stream bank (2.1 m above stream bank for large mainstem areas) Bank overhang > 0.8-1.0		Outer b m abov 1.5 m a for large	bend areas stable bank height 0.6-0.9 e stream bank (1.2- above stream bank e mainstem areas) verhang 0.6-0.8 m	Stream bend areas very stable Height < 0.6 m above stream (< 1.2 m above stream bank for large mainstem areas) Bank overhang < 0.6 m	
Stability	abundant  > > 6 recent large tree falls per stream mile	Young exposed tree roots common 4-5 recent large tree falls per stream mile	predom large, s scarce • 2-3 rece	d tree roots inantly old and maller young roots ent large tree falls eam mile	Exposed tree roots old, large and woody     Generally 0-1 recent large tree falls per stream mile	
	Plant/soil matrix severely	Bottom 1/3 of bank is generally highly erodible material Plant/soil matrix compromised	Bottom 1/3 of bank is generally highly resistant plant/soil matrix or material		Bottom 1/3 of bank is generally highly resistant plant/soil matrix or material	
F11 J-8.0 on	Channel cross-section is generally trapezoidally- shaped	Channel cross-section is generally trapezoidally-shaped		l cross-section is ly V- or U-shaped	Channel cross-section is generally V- or U-shaped	
Point range		□ 3 🛛 4 □ 5	□ 6	0708	□ 9 □ 10 □ 11	
	85% embedded for large mainstem areas)	50-75% embedded (60- 85% embedded for large mainstem areas)	59% en	embedded (35- nbedded for large em areas)	Biffle embeddedness < 25% sand-silt (< 35% embedded for large mainstem areas)	
e ilig in cy	Pool substrate composition >81% sand-silt	Low to moderate number of deep pools Pool substrate composition 60-80% sand-silt	pools Pool sub	te number of deep ostrate composition o sand-silt	High number of deep pool     (> 61 cm deep)     (> 122 cm deep for large     mainstem areas)     Pool substrate composition     <30% sand-silt	
Channel Scouring/ Sediment Deposition	and/or "banana"-shaped sediment deposits common	Streambed streak marks and/or "banana"-shaped sediment deposits common	and/or "	ped streak marks banana"-shaped nt deposits non	Streambed streak marks and/or "banana"-shaped sediment deposits absent	
rage: ng (> 68% fo em arcar)	deposits very common in channel  Moderate to heavy sand  o	Fresh, large sand deposits common in channel Small localized areas of fresh sand deposits along top of low banks	Fresh, large sand deposits uncommon in channel Small localized areas of fresh sand deposits along top of low banks		Fresh, large sand deposits rare or absent from channel No evidence of fresh sediment deposition on overbank	
T D	most stream bends, moderate to large and	Point bars common, moderate to large and unstable with high amount of fresh sand	well-veg	rs small and stable letated and/or ed with little or no nd	<ul> <li>Point bars few, small and stable, well-vegetated and/or armoured with little or no fresh sand</li> </ul>	
Point range		□ 3 □ 4	П	15 0 6	□ 7 □ 8	



Date: 2			La Maria de la Maria dela Maria dela Maria dela Maria dela Maria de la Maria dela M	
Category	Poor	Fair	Good	Excellent
C	Wetted perimeter < 40%     of bottom channel width     (< 45% for large     mainstem areas)	<ul> <li>Wetted perimeter 40- 60% of bottom channel width (45-65% for large mainstem areas)</li> </ul>	<ul> <li>Wetted perimeter 61-85% of bottom channel width (66-90% for large mainstem areas)</li> </ul>	<ul> <li>Wetted perimeter &gt; 85% of bottom channel width (&gt; 90% for large mainstem areas)</li> </ul>
	Dominated by one habitat type (usually runs) and by one velocity and depth condition (slow and shallow) (for large mainstem areas, few riffles present, runs and pools dominant, velocity and depth diversity low)	<ul> <li>Few pools present, riffles and runs dominant.</li> <li>Velocity and depth generally slow and shallow (for large mainstem areas, runs and pools dominant, velocity and depth diversity intermediate)</li> </ul>	Good mix between riffles, runs and pools     Relatively diverse velocity and depth of flow	<ul> <li>Riffles, runs and pool habitat present</li> <li>Diverse velocity and depth of flow present (i.e., slow, fast, shallow and deep water)</li> </ul>
Physical Instream	Riffle substrate composition: predominantly gravel with high amount of sand     < 5% cobble	Riffle substrate composition: predominantly small cobble, gravel and sand 5-24% cobble	<ul> <li>Riffle substrate composition: good mix of gravel, cobble, and rubble material</li> <li>25-49% cobble</li> </ul>	<ul> <li>Riffle substrate composition: cobble, gravel, rubble, boulder mix with little sand</li> <li>&gt; 50% cobble</li> </ul>
Habitat	Riffle depth < 10 cm for large mainstem areas	Riffle depth 10-15 cm for large mainstem areas	Riffle depth 15-20 cm for large mainstem areas	Riffle depth > 20 cm for large mainstem areas
	Large pools generally < 30 cm deep (< 61 cm for large mainstem areas) and devoid of overhead cover/structure	Large pools generally 30- 46 cm deep (61-91 cm for large mainstem areas) with little or no overhead cover/structure	<ul> <li>Large pools generally 46-61 cm deep (91-122 cm for large mainstem areas) with some overhead cover/structure</li> </ul>	Large pools generally > 61 cm deep (> 122 cm for large mainstem areas) with good overhead cover/structure
	Extensive channel alteration and/or point bar formation/enlargement	Moderate amount of channel alteration and/or moderate increase in point bar formation/enlargement	Slight amount of channel alteration and/or slight increase in point bar formation/enlargement	No channel alteration or significant point bar formation/enlargement
	• Riffle/Pool ratio 0.49:1 ; ≥1.51:1	• Riffle/Pool ratio 0.5- 0.69:1 ; 1.31-1.5:1	• Riffle/Pool ratio 0.7-0.89:1 ; 1.11-1.3:1	• Riffle/Pool ratio 0.9-1.1:1
11 7 01	• Summer afternoon water temperature > 27°C	• Summer afternoon water temperature 24-27°C	Summer afternoon water temperature 20-24°C	• Summer afternoon water temperature < 20°C
Point range	0 0 1 0 2	≥ 3 □ 4	□ 5 □ 6	□ 7 □ 8
	Substrate fouling level:     High (> 50%)	Substrate fouling level:     Moderate (21-50%)	Substrate fouling level:     Very light (11-20%)	Substrate fouling level:     Rock underside (0-10%)
Mood days you	Brown colour     TDS: > 150 mg/L	<ul><li> Grey colour</li><li> TDS: 101-150 mg/L</li></ul>	Slightly grey colour     TDS: 50-100 mg/L	• Clear flow • TDS: < 50 mg/L
Water Quality	Objects visible to depth     < 0.15m below surface	Objects visible to depth     0.15-0.5m below surface	0.5-1.0m below surface	Objects visible to depth     1.0m below surface
Illa	Moderate to strong organic odour	Slight to moderate organic odour	Slight organic odour	No odour
Point range	□ 0 □ 1 □ 2	□ 3 □ 4	□ 5 □ 6	□ 7 45.8
Riparian	Narrow riparian area of mostly non-woody vegetation	Riparian area     predominantly wooded     but with major localized     gaps	Forested buffer generally     31 m wide along major     portion of both banks	Wide (> 60 m) mature forested buffer along both banks
Habitat Conditions	Canopy coverage:     <50% shading (30% for large mainstem areas)	Canopy coverage: 50- 60% shading (30-44% for large mainstem areas)	Canopy coverage:     60-79% shading (45-59% for large mainstem areas)	Canopy coverage:     >80% shading (> 60% for large mainstem areas)
Point range	□ 0 □ 1	□ 2 □ 3	□ 4 □ 5	6 0 7
Total overall	score (0-42) = 27	Poor (<13)	Fair (13-24) Good (25-	34) Excellent (>35)

Version #2 Last edited: 10/02/2023

Senior staff sign-off (if required): \_\_\_\_\_ Checked by: \_\_\_\_ Completed by: \_\_\_\_

Reach Characteristics	cterist		25102						MORPHUX
Date:		2025-07-18	Field Staff:	NT CM		Watershe	Watershed/Subwatershed:	ed:	
Time:		12:45	Stream:	Flaterow's	CIREK	UTM (Upstream):	tream):		
Weather:		Sun 25	Reach:	ナンナー		UTM (Dow	UTM (Downstream):		
Land Use $(7able 1)$	1,3,6 Va	Valley Type  Channel Type (Table 2)	10	Channel Zone Z Flo (Table 4)	Flow Type (Table 5)		Evidence of Groundwater Location:	water Location:	Photo:
Riparian Vegetation	tation			Aquatic & Instream Vegetation	Vegetatio	<b>-</b>	^	Water Quality	
Dominant Type	_	ge Channel Widths	Age (yrs)	Type N/A Woo	Woody Debris	WD Density		Odour	Turbidity
(Table 6)	-	□ 1 - 4	□ Immature (<5)	1,/		□ Low	WDJ/50m:	(Table 16)	(Table 17)
Encroachment (Table 7)	7	☐ Fragmented ☐ 4 - 10 ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐	□ Established (5-30) ☑Mature (>30)	Reach Coverage % □ N	☑ In Channel ☐	Mod Mod			
Channel Characteristics	cteristi	S)							
Sinuosity Type (Table 9)		Sinuosity Degree (Table 10)	Bank Angle	<b>Bank Erosion</b> (T □ < 5%	(Table 19) Bank	Clay/Silt	Sand Gravel	Cobble Boulder	Parent Rootlets
Gradient (Table 11)	4	# of Channels (Table 12)	D 30 - 60 D 60 - 90	□ 5 – 30% □ 30 – 60%	Riffle Pool				
Entrenchment (Table 13)		Bank Failure (Table 14)	□ Undercut	(if n	Bed (if no riffle-pool morphology)				
Down's Model (Table 15)	0	Bankfull Indicators (13.7)	. ^	Bankfull Width 042	1.12	1000	Wetted Width (m)	0.24	1,04 0.32
Sed Sorting (Table 20)	Poor	Sediment Transport	☐ Yes ☐ No ☐ Not Visible	Bankfull Depth (m)	15°0	14.0	Wetted Depth (m)	0.02	1000
Transport Mode (Table 21)	23	% of Bed Active		Undercuts (m)	5.0	0.0	Velocity (m/s)	n/s) (2,1)	13 0.02
Geomorphic Gounts (Table 22)	5,6,9	Mass Movement (Table 23)		Pool Depth (m)	0.07	040	Velocity E	stimate WB WR	3
Riffle-Pool Spacing (m):	4 2	% Riffles:	% Pools:	Riffle Length (m)			Meander Amplitude (m)	tude N/A NA (m)	4 1
		Divining the state of the state							
o Low water	. 0	Levels, Small wette	and periment	at Make Mac	SAIS	200	f s		
		ding from fi	eld an RB	undercut,	900	1.7	a conserved	DS OF	confluence
Co.		S young and	100						
Meander	an am	Vitude not me	asomal ack	20 02 CK	want	ma	nders		
Photos:	303	Contact or	Cot par						

Version #4 Last edited: 04/04/2023

Senior staff sign-off (if required): \_\_

Completed by:

Checked by:



25/02 **Rapid Geomorphic Assessment Project Number:** 2025-07-18 Date: Stream: Fletcher's Creek Time: 12: 45 Reach: Weather: Sun 250 Location: Derry crest Dr. Field Staff: cm Watershed/Subwatershed: Geomorphological Indicator Present? Factor Process No. Description Value Yes No 1 Lobate bar 2 Coarse materials in riffles embedded 3 Siltation in pools Evidence of Aggradation Medial bars - Single 4 (AI) 5 Accretion on point bars 6 Poor longitudinal sorting of bed materials 7 Deposition in the overbank zone - NOT Sum of indices = 1 Exposed bridge footing(s) 2 Exposed sanitary / storm sewer / pipeline / etc. 3 Elevated storm sewer outfall(s) 4 Undermined gabion baskets / concrete aprons / etc. Evidence of Scour pools downstream of culverts / storm sewer outlets 5 Degradation 6 (DI) Cut face on bar forms 7 Head cutting due to knickpoint migration 8 Terrace cut through older bar material 9 Suspended armour layer visible in bank Channel worn into undisturbed overburden / bedrock - New FETC Free 10 Sum of indices = 3 0.6 1 Fallen / leaning trees / fence posts / etc. 2 Occurrence of large organic debris 3 Exposed tree roots 4 Basal scour on inside meander bends Evidence of 5 Basal scour on both sides of channel through riffle Widening Outflanked gabion baskets / concrete walls / etc. 6 (WI) MA 7 Length of basal scour >50% through subject reach 8 Exposed length of previously buried pipe / cable / etc. 9 Fracture lines along top of bank 10 Exposed building foundation Sum of indices = Formation of chute(s) 1 2 Single thread channel to multiple channel Evidence of 3 Evolution of pool-riffle form to low bed relief form Planimetric Form 4 Cut-off channel(s) Adjustment 5 Formation of island(s) (PI) 6 Thalweg alignment out of phase with meander form Bar forms poorly formed / reworked / removed 7 Sum of indices = Notes: Stability Index (SI) = (AI+DI+WI+PI)/4 = 0.3In Regime In Transition/Stress In Adjustment □ 0.00 - 0.20 0.21 - 0.40 □ 0.41 feeds into Hrib

Senior staff sign-off (if required): \_\_\_\_\_ Checked by: \_\_\_\_ Completed by: \_\_\_\_\_

Version #3

Last edited: 10/02/2023



Date		7025-07-10	Stream:	kel w
Time		K.09	Reach:	Thes's (seek
Weat		7401		C-2
		CTC, Svnny	Location: De	rsylocst XI.
Field	Staff:	NHCM	Watershed/Subwatershed:	
Featu	res	Monitoring	Site Sketch	Compass Compass
	Flow direction Riffle Pool Sediment bar Froded bank/slope Undercut bank Bank stabilization Leaning tree Fence Culvert/outfall Swamp/wetland Grasses Tree	Monumented XS Monumented photo Monumented photo direction Sediment sampling Erosion pins Scour chains Additional Symbols	Rootlets  On head Ship  On Sed Ship  Bed:	Clay 51,523 (1)  X B F M; 0.16 n  BFW: 1.0 n  BFW: 1.5 n  BFW: 1.5 n  WD: 0.33
*** *** ***	Instream log/tree Woody debris Beaver dam Vegetated island		Send/Sitt/Ory /-/	WD e 03 WW 0.64 Velocity: 0/Standar
H1 H2 H3 H4 H5 H6 H7	Standing water H1 Scarcely perceptible Smooth surface flow Upwelling Rippled Unbroken standing way Broken standing way Chute	flow vave		he bank total of slope
Н9	Free fall H9	A Dissipates below free fall	71 950	mit to of Shore
\$1 \$2 \$3 \$4 \$5	rate Silt Sand Gravel Small cobble Large cobble	S6 Small boulder S7 Large boulder S8 Bimodal S9 Bedrock/till	Velocity: 0.07 XXXX BFV: 2.08 XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	Roots
Other		,	Vepa Vepa	sition, 53-54
BM BS DS WDJ VWC	Benchmark Backsight Downstream Woody debris jam Valley wall contact	RB Rebar US Upstream TR Terrace FC Flood chute	LBIRB Bank Matrow DAY SEX pos Sit Clas XXX	red PM
BOS	Bottom of slope	FP Flood plain	Photos:	
TOS	Top of slope	KP Knick point	Notes:	

Version #4 Last edited: 21/02/2023

Senior staff sign-off (if required): \_\_\_\_\_ Checked by: \_\_\_\_ Completed by: \_\_\_\_\_



Page  $\bot$  of  $\overline{Z}$ 



Date:		7107	S-07-10	C	tream:	ITTALL	1
Time		Later Con-	-112			Fletcher's	Creek
		1	77		each:	117-6	
Weat		Sun	74°C	Lo	ocation:	Derry (	rest Pr.
Field	Staff:	NH	(11)	W	atershed/Subwatershed:	/	
Featu	res	Monitori	ing	Site SI	cetch		Compass
	Reach break	-0-0-0- La	ong-profile				
只	Station location	M	onumented XS				
(X	Cross-section	(O) M	onumented photo				
	Flow direction	M	onumented photo				
<b>~</b>	Riffle		rection				
$\bigcirc$	Pool	Se Se	ediment sampling		9 -		
	Sediment bar	Er	rosion pins				
***************************************	Eroded bank/slope	8 s	cour chains				
	Undercut bank	Addition	al Symbols				
XXXXX	Bank stabilization						
***	Leaning tree						
<b>⟨</b> ×	Fence						
	Culvert/outfall						
	Swamp/wetland						
VVV	Grasses						
<b>3</b>	Tree						
	Instream log/tree						
× *	Woody debris						
******	Beaver dam						
VV	Vegetated island						
low 1							
H1	Standing water H1	A Back wa	ater		1 1 1 1 1 1 1 1		
H2	Scarcely perceptible						
НЗ	Smooth surface flow				7-15		
H4	Upwelling			Read	N.		
H5	Rippled			15	16-3 - 5 - 0/40/		
Н6	Unbroken standing v	vave		1,	BFW.0.180	BFW. C. 43	Sp-1
H7	Broken standing way				BED: 0.07×	-X BFD: 009	5009
Н8	Chute			1	Change	Pr. 100	PCD: A AFT D
Н9	Free fall H9.	A Dissipat	tes below free fall		lasts definitions	L Dr. 0.40'	Drv.O.O.+, VI
ubstr					D. F. C.	BFW. Q. 45 * BFP: 009 BFW: 0,80, ~ D: 0.013 WW: 0.12	Standing water
S1	Silt	S6	Small boulder	11011	(00)	ww. 0.12	
S2	Sand		Large boulder	Ewon. G	Se ( - Ix	BEW, 0.82 BFH:0.13	
<b>S</b> 3	Gravel		Bimodal	Knick f	POINT T	BFH:0.13	
<b>S4</b>	Small cobble		Bedrock/till	mose'	WEREWILLS XXXXX		
<b>S</b> 5	Large cobble	-	7		8511-2020	c 1	
ther					BTH = 0.15 x	Bed Sand Sitt, (	low
М	Benchmark	EP	Erosion pin		19	6-1-	/
s	Backsight		Rebar		BFHIO.12x	M D ( DM	
S	Downstream		Upstream		BFHIO.ICX	R L \	
DJ	Woody debris jam		Terrace		I Just of	20013	
WC	Valley wall contact		Flood chute		and a cloud		
os	Bottom of slope		Flood plain	DI :	0119m com 001		
				Photos:			
OS	Top of slope	KP	Knick point	Notes:			

Version #4 Last edited: 21/02/2023

Senior staff sign-off (if required): \_\_\_\_\_ Checked by: \_\_

\_\_ Completed by: \_\_\_\_\_\_\_



Rapid Stream Assessment Technique

Project Number: 25/07 2025-07-10 Date: Stream: Time: Reach: Weather: Location: Field Staff: Watershed/Subwatershed: Category Poor Fair Good Excellent < 50% of bank network</li> · 50-70% of bank network 71-80% of bank network > 80% of bank network stable stable stable stable · Recent bank sloughing, Recent signs of bank Infrequent signs of bank No evidence of bank slumping or failure sloughing, slumping or sloughing, slumping or sloughing, slumping or frequently observed failure fairly common failure failure Stream bend areas highly Stream bend areas Stream bend areas stable Stream bend areas very unstable unstable Outer bank height 0.6-0.9 stable Outer bank height 1.2 m Outer bank height 0.9-Height < 0.6 m above m above stream bank (1.2above stream bank 1.2 m above stream 1.5 m above stream bank stream (< 1.2 m above (2.1 m above stream bank for large mainstem areas) stream bank for large bank for large mainstem (1.5-2.1 m above stream Bank overhang 0.6-0.8 m mainstem areas) areas) bank for large mainstem Bank overhang < 0.6 m Bank overhang > 0.8-1.0 areas) m Bank overhang 0.8-0.9m Channel Stability · Young exposed tree roots Young exposed tree roots Exposed tree roots Exposed tree roots old, abundant common predominantly old and large and woody > 6 recent large tree falls 4-5 recent large tree falls large, smaller young roots Generally 0-1 recent large per stream mile per stream mile scarce tree falls per stream mile 2-3 recent large tree falls per stream mile · Bottom 1/3 of bank is · Bottom 1/3 of bank is Bottom 1/3 of bank is Bottom 1/3 of bank is highly erodible material generally highly erodible generally highly resistant generally highly resistant Plant/soil matrix severely material plant/soil matrix or material plant/soil matrix or material compromised Plant/soil matrix compromised Channel cross-section is Channel cross-section is · Channel cross-section is · Channel cross-section is generally trapezoidallygenerally trapezoidally generally V- or U-shaped generally V- or U-shaped shaped shaped Point range **1** □ 2 B 6 0 7 0 4 □ 8 □ 9 □ 10 0 11 > 75% embedded (> 50-75% embedded (60-25-49% embedded (35-Riffle embeddedness < 85% embedded for large 85% embedded for large 59% embedded for large 25% sand-silt (< 35% mainstem areas) mainstem areas) mainstem areas) embedded for large mainstem areas) Few, if any, deep pools Low to moderate number Moderate number of deep High number of deep pools Pool substrate of deep pools pools (> 61 cm deep) composition >81% sand-Pool substrate Pool substrate composition (> 122 cm deep for large silt composition 30-59% sand-silt mainstem areas) 60-80% sand-silt Pool substrate composition <30% sand-silt Streambed streak marks Streambed streak marks Streambed streak marks Streambed streak marks Channel and/or "banana"-shaped and/or "banana"-shaped and/or "banana"-shaped and/or "banana"-shaped Scouring/ sediment deposits sediment deposits sediment deposits sediment deposits absent Sediment common common uncommon Deposition Fresh, large sand · Fresh, large sand Fresh, large sand deposits Fresh, large sand deposits deposits very common in deposits common in uncommon in channel are or absent from channel channel channel Small localized areas of No evidence of fresh Moderate to heavy sand Small localized areas of fresh sand deposits along sediment deposition on deposition along major fresh sand deposits along top of low banks overbank portion of overbank area top of low banks Point bars present at · Point bars common, Point bars few, small and Point bars small and stable, most stream bends. moderate to large and well-vegetated and/or stable, well-vegetated moderate to large and unstable with high armoured with little or no and/or armoured with little unstable with high amount of fresh sand fresh sand or no fresh sand amount of fresh sand

Point range Version #2

Last edited: 10/02/2023

□ 2

Senior staff sign-off (if required): \_\_\_\_\_ Checked by:

□ 3 □ 4

**A** 6

**5** 

Completed by:

**P** 7

□ 8



Location: Date: PN: Fair Good **Excellent** Category Poor Wetted perimeter 61-85% Wetted perimeter < 40% Wetted perimeter 40- Wetted perimeter > 85% of of bottom channel width 60% of bottom channel of bottom channel width bottom channel width (> width (45-65% for large (66-90% for large 90% for large mainstem (< 45% for large mainstem areas) mainstem areas) mainstem areas) areas) · Riffles, runs and pool Good mix between riffles, Dominated by one habitat Few pools present, riffles type (usually runs) and and runs dominant. runs and pools habitat present Relatively diverse velocity Diverse velocity and depth by one velocity and depth Velocity and depth and depth of flow of flow present (i.e., slow, condition (slow and generally slow and fast, shallow and deep shallow) (for large shallow (for large mainstem areas, few mainstem areas, runs water) riffles present, runs and and pools dominant, pools dominant, velocity velocity and depth and depth diversity low) diversity intermediate). Riffle substrate Riffle substrate Riffle substrate Riffle substrate composition: composition: cobble, composition: composition: good mix of gravel, rubble, boulder mix predominantly gravel predominantly small gravel, cobble, and rubble with high amount of sand cobble, gravel and sand material with little sand Physical > 50% cobble Instream < 5% cobble</p> 5-24% cobble 25-49% cobble Habitat • Riffle depth > 20 cm for · Riffle depth 15-20 cm for • Riffle depth < 10 cm for Riffle depth 10-15 cm for large mainstem areas large mainstem areas large mainstem areas large mainstem areas Large pools generally > 61 Large pools generally 46-61 Large pools generally < Large pools generally 30-46 cm deep (61-91 cm / cm deep (> 122 cm for cm deep (91-122 cm for 30 cm deep (< 61 cm for large mainstem areas) with large mainstem areas) with large mainstem areas) for large mainstem areas) with little or no some overhead good overhead and devoid of overhead overhead cover/structure cover/structure cover/structure cover/structure Slight amount of channel No channel alteration or Extensive channel Moderate amount of channel alteration and/or alteration and/or slight significant point bar alteration and/or point formation/enlargement increase in point bar moderate increase in formation/enlargement point bar formation/enlargement formation/enlargement Riffle/Pool ratio 0.7-0.89:1 Riffle/Pool ratio 0.9-1.1:1 Riffle/Pool ratio 0.5- Riffle/Pool ratio 0.49:1; ; 1.11-1.3:1 0.69:1; 1.31-1.5:1 ≥1.51:1 Summer afternoon water Summer afternoon water Summer afternoon water Summer afternoon water temperature 20-24°C temperature 24-27°C temperature < 20°C temperature > 27°C □ 7 □ 8 D 3 D 4 □ 5 □ 6 □ 0 □ 1 0 2 Point range · Substrate fouling level: Substrate fouling level: Substrate fouling level: Substrate fouling level: Rock underside (0-10%) Very light (11-20%) High (> 50%) Moderate (21-50%) · Clear flow Slightly grey colour · Brown colour · Grey colour TDS: < 50 mg/L</li> TDS: 50-100 mg/k TDS: 101-150 mg/L TDS: > 150 mg/L Water Quality · Objects visible to depth 0.5-1.0m below surface > 1.0m below surface 0.15-0.5m below surface < 0.15m below surface water No odour Slight organic odour Moderate to strong Slight to moderate organic odour organic odour □ 3 □ 4 □ 5 □ 6 □ 7 □ 8 0 0 1 2 2 Point range Wide (> 60 m) mature Forested buffer generally Riparian area Narrow riparian area of 31 m wide along major forested buffer along both predominantly wooded mostly non-woody but with major localized banks portion of both banks vegetation Riparian gaps Habitat Canopy coverage: Canopy coverage: · Canopy coverage: 50-· Canopy coverage: Conditions >80% shading (> 60% for 60% shading (30-44% 60-79% shading (45-59% <50% shading (30% for

Point range  Total overall score (	0.42) - 5)	□ 2 □ 3  Poor (<13)	Fair (13-24)	Good (25-34)	Excellent (>35)	
Total overall score (	0-42) = 2	1001 (420)			C D St St. At Books lokel a	

Version #2 Last edited: 10/02/2023

Reach Characteristics	tics Project Number:	2502			A O E	× - I
Date:	2025-07-18	Field Staff:	CEO 22	Watershed/Subwatershed:	ed:	
Time:	13:09	Stream:	Flat cher's check	UTM (Upstream):		
Weather:	Sun 25	Reach:	FCT-2	UTM (Downstream):		
Land Use (Table 1) (T	Valley Type Channel 7 (Table 2)	Type Cha	Channel Zone Plow Type (Table 4) (Table 5)	2 🗆 Evidence of Groundwater Location:	dwater Location:Photo:	1
Riparian Vegetation			Aquatic & Instream Vegetation		Water Quality	
Dominant Type (Table 6)	Coverage Channel Widths A	Age (yrs)	Type N Woody Debris (Table 8)	WD Density ☐ Low WDJ/50m:	Odour Turbidity (Table 17)	
Encroachment (Table 7)	Fragmented #4 - 10 = AContinuous = 10	☐ Established (5-30) ☐ Mature (>30)	Reach	□ Mod 2	4	
Channel Characteristics	ics					
Sinuosity Type (Table 9)	Sinuosity Degree (Table 10)	Bank Angle	Bank Erosion(Table 19)□ < 5%Bank	Clay/Silt Sand Gravel	Cobble Boulder Parent Rootlets	w
Gradient (Table 11)	# of Channels (Table 12)	30 - 60	□ 5 – 30% Riffle Pool			
Entrenchment (Table 13)	Bank Failure 2, (C) (Table 14)	☐ Undercut	o (if no rifl morp)	A		
Down's Model (Table 15)	Bankfull Indicators 2,5		Bankfull Width (m) 1.50	0.66 Wetted Width (m)	h (m) 0 0.37	
Sed Sorting (Table 20)	Sediment Transport ☐ Yes ☐ Observed?	☐ Yes ☐ No ☐ Not Visible	Bankfull Depth (m) 0.16	O <sub>o</sub> (2) Wetted Depth (m)	h (m) h	
Transport 2 3	% of Bed Active		Undercuts (m)	Velocity (m/s)	(s/m	
Geomorphic Gulb	Mass Movement (Table 23)		Pool Depth	Velocity Estimate Method	stimate WB	
Riffle-Pool Spacing (m):	. % Riffles:	% Pools:	Riffle Length (m)	Meander Amplitude (m)	itude (m)	
Notes:	K @ Mach	prook to	FCT-1 is LISM &	from the af	Stope (partially	
> Dry dur	ing assessmen	ens in	US extent			
> Bon Ks	De to me Shalls	30	SS OLCINED MO	Meving US		
Photos:						
Version #4 Last edited: 04/04/2023			Senior staff sign-off (if required):	required): Checked by:	ed by: Completed by:	garana and

Version #4 Last edited: 04/04/2023



**Rapid Geomorphic Assessment** 25107 **Project Number:** Date: 2025-07-18 Stream: Fletcher's Cheek Time: Reach: Weather: Location: Sun Derrycrest Field Staff: NH Watershed/Subwatershed: Geomorphological Indicator Present? Factor **Process** Value No. Description Yes No 1 Lobate bar 2 Coarse materials in riffles embedded Siltation in pools 3 NA Evidence of 1-16 Aggradation 4 Medial bars - one occurance DS of confluence (AI) 5 Accretion on point bars 6 Poor longitudinal sorting of bed materials 7 Deposition in the overbank zone Sum of indices = 0.1 NA 1 Exposed bridge footing(s) NA 2 Exposed sanitary / storm sewer / pipeline / etc. 3 Elevated storm sewer outfall(s) NR 4 Undermined gabion baskets / concrete aprons / etc. NA Evidence of Scour pools downstream of culverts / storm sewer outlets 5 NA Degradation 6 Cut face on bar forms (DI) 7 Head cutting due to knickpoint migration 8 Terrace cut through older bar material 9 Suspended armour layer visible in bank 10 Channel worn into undisturbed overburden / bedrock Sum of indices = 1 Fallen / leaning trees / fence posts / etc. 2 Occurrence of large organic debris 3 Exposed tree roots 4 Basal scour on inside meander bends 3/1 Evidence of Basal scour on both sides of channel through riffle 5 Widening 6 Outflanked gabion baskets / concrete walls / etc. NA (WI) 7 Length of basal scour >50% through subject reach 8 Exposed length of previously buried pipe / cable / etc. NA. 9 Fracture lines along top of bank 10 Exposed building foundation NA Sum of indices = 1 Formation of chute(s) Single thread channel to multiple channel Evidence of 3 Evolution of pool-riffle form to low bed relief form Planimetric Form 4 Cut-off channel(s) Adjustment 5 Formation of island(s) (PI) 6 Thalweg alignment out of phase with meander form 7 Bar forms poorly formed / reworked / removed Sum of indices = Notes: Stability Index (SI) = (AI+DI+WI+PI)/4 = In Transition/Stress In Adjustment In Regime □ 0.00 - 0.20 0.21 - 0.40 □ 0.41

Senior staff sign-off (if required): \_\_\_\_\_ Checked by:

Version #3

Last edited: 10/02/2023

Project Number: 25102

Date:		1013-1	07-18	Stream:		Fletches's (s	cet
Time:		14:15		Reach:		FTC-3	
Weatl	her:	11/2/	ind	Location		Derry Crest.	Dr.
Field	Staff:	MHCV	n/	Watersho	ed/Subwatershed:	ond /	
Featur	res	Monitoring	Sit	e Sketch	T C	Comp	pass
	Reach break	-  -  -  -  -  -  -  -  -  -  -  -  -				hello	
只	Station location	Monumented	IXS				1)
××	Cross-section	Monumented	I photo				")
	Flow direction	Monumented	I photo		- September 1	ALL IN	
~~	Riffle	★ direction				919	
	Pool	Sediment sa	mpling				
CONTROL OF THE PARTY OF THE PAR	Sediment bar	Erosion pins	and the second			Management and rest of the second and second	1
HHHHHH	Eroded bank/slope	Scour chains	-		and the second Charles in some control to second Colores and additional institute in the	A Secretaria de la composición dela composición de la composición dela composición de la composición d	
	Undercut bank	Additional Symbol	S		1 revict	e crossing /	
KXXXXX	Bank stabilization	9				-100	
	Leaning tree	/ cathairs/	phras			RITI	
XX	Fence				1/4	011 1000	K.
	Culvert/outfall		7		Hall.	10 100,000	HON
	Swamp/wetland		fiel		catails chained	P no bani	, -
AAA	Grasses		- 5		chain ne	80	
	Tree		4		C+ 1000		
	Instream log/tree				- Common of the	receipts	
***	Woody debris		3		1000	(h)	
*****	Beaver dam		5		o Hill	471	
(VV)	Vegetated island		2		E	311	00
Flow 1			Agricultura	~	6	WW=C BFW=C BFD=C	700,
H2	Standing water H1		5	r	dry - (41)	MM=C	) • + 1
H3	Scarcely perceptible Smooth surface flow	now	- 5		Water	BEW-	0.83
H4	Upwelling		8		10:0.E	BFD=	0.19
H5	Rippled		T		00:01	2 02	
Н6	Unbroken standing w	rave			at XX	FD = 0.23	
H7	Broken standing way			class	sand XA TOP	FW= 1.0	
Н8	Chute	500		1	ised LO/	NW=0.62	
Н9	Free fall H9/	A Dissipates below f	ree fall	1 1		PO.0-0W	
Substr	ate			1 1	2 HI		
S1	Silt	<b>S6</b> Small bou	lder		41	1=0mB	
S2	Sand	\$7 Large bou	lder Ban	XST		FW=1.05 m	
S3	Gravel	S8 Bimodal	108	inea	XIDIXE	FD=0.12m	
S4	Small cobble	<b>S9</b> Bedrock/ti	11		- /UITW	JW=0.55m	
S5	Large cobble					10-0-04m	
Other	BI				3 A 1	FW=0.58	1
BM BS	Benchmark Backsight	EP Erosion pi	1 Veo	1	F	FD = 0.04	
DS	•	RB Rebar	1 4 4	J. Comment	N/II		
WDJ	Downstream	US Upstream	EMO	invel.	3 1 81	EW=0.5	
VWC	Woody debris jam Valley wall contact	TR Terrace	00	DV	h 1778	FD:0.05	
BOS		FC Flood chut		161 W/450			
	Bottom of slope	FP Flood plair					
TOS	Top of slope	KP Knick poin	t Note	s:		A	
7 Sr	nau extent	of reac	has det	fined	banks, but 1	s otherwise a	rass 11
Swa	le (DS) or	cattail/phrao	encupaci	hed u	retland (US)	J	7
Versio		Senior st	aff sign-off (if red	quired):	Checked by:	Completed by:	M
Last e	dited: 21/02/2023					Page	1

Reach Characteristics	stics Project Number:	25102							,	M O R P H I X"
Date:	2025-07-18	Field Staff:	CM NH		Watershed	Watershed/Subwatershed:	:shed:			
Time:	10	Stream:	Flest ciner's	Creek	UTM (Upstream):	ream):				
Weather:	240 Sunny	Reach:	FCT-3		UTM (Downstream):	nstream):				
Land Use 3,7 (Table 1)	Valley Type Channel Type (Table 2) (Table 3)	12	Channel Zone   FI (Table 4)	Flow Type (Table 5)	2 = Ev	idence of Gro	☐ Evidence of Groundwater Location:	ation:	Pho	Photo:
Riparian Vegetation			Aquatic & Instream	Instream Vegetation	_		Water Quality	ality		
Dominant Type (Table 6)	Coverage Channel Widths	Age (yrs)	Type WC (Table 8)	Woody Debris	WD Density	WDJ/50m:	Odour (Table 16)	I <b>r</b> 16)	Turb (Tabl	Turbidity (Table 17)
Encroachment (Table 7)	nented 124.4	☐ Established (5-30)	Reach Coverage %		□ Mod	0.2%				w
Channel Characteristics	tics									
Sinuosity Type (Table 9)	Sinuosity Degree (Table 10)	Bank Angle	Bank Erosion (□ < 5%	(Table 19) (Bank	clay/Silt	Sand Gravel	el Cobble	Boulder	Parent	Rootlets
Gradient	# of Channels	09 - 05	AC 5 - 30%	Riffle						
(Table 11)	(Table 12)	06 – 09 🗆	□ 30 – 60%	Pool						
Entrenchment (Table 13)	Bank Failure (Table 14)	□ Undercut	□ 60 – 100% (if	<b>Bed</b> (if no riffle-pool morphology)	A	Z				
Down's Model (Table 15)	Bankfull Indicators 1,3,5		Bankfull Width (m)	00	0.83	Wetted Width (m)	0	3	79.0	17.0
Sed Sorting Well (Table 20)	Sediment Transport	□ Yes 🖟 No 🗆 Not Visible	Bankfull Depth 0.05	5.0	6.0	Wetted Depth (m)	pth (m)	0	0	10,0
Transport Mode (Table 21)	% of Bed Active		Undercuts (m)			Velocity (m/s)	(s/m)/		0	0
Geomorphic Units (Table 22)	Mass Movement (Table 23)		Pool Depth (m)	0.0	10.0	Velocity Estimate Method	Stimate WB.			
Riffle-Pool Spacing (m):	% Riffles:	% Pools:	Riffle Length (m)	\	\	Meander Amplitude (m)	iplitude (m)			\
Notes:										
-> Sporadic	mant oudo	bot	Swin	3	5	2	2 6			10.1
57 450	ed bo	TO ORTINA	さん ひい のよ	AAMAI TO	1 8 8 0 V	3	ar or	2	X O	ハンキント
& Small soct	ion of		was not sv	X e	metlan	DAY D	l expo	540	2007	10
ALL CLINE CARCH	te present									
6										
Photos:										
Version #4			Senior staff sign-off (if required):	ign-off (if re	quired):	Chec	Checked by:	Com	Completed by:	CB

Version #4 Last edited: 04/04/2023

**Appendix E: Detailed Assessment Summaries** 



## **Detailed Geomorphological Assessment Summary**

Reach FCT-1

<b>Project Number:</b>	PN 18129	Date:	Nov 1, 2018
Client:	DeZen Realty	Length Surveyed (m):	82.6
Location:	Hurontario Street and Derry Road West	# of Cross-Sections:	8

Reach Characteristics

**Drainage Area:** 0.672 km<sup>2</sup> **Dominant Riparian Vegetation Type:** Herbaceous, trees

Geology/Soils: Till Extent of Riparian Cover: Continuous

Surrounding Land Use: Agricultural, commerical Width of Riparian Cover: 4 to 10 times channel width


 Valley Type:
 Confined
 Age Class of Riparian Vegetation:
 Established (5-10 yrs)

Dominant Instream Vegetation Type:NoneExtent of Encroachment into Channel:HeavyPortion of Reach with Vegetation:0Density of Woody Debris:High

Hydrology			
Measured Discharge (m³/s):	0.01	Calculated Bankfull Discharge (m³/s):	3.27
Modelled 2-year Discharge (m³/s):	Not modelled	Calculated Bankfull Velocity (m/s):	2.89
Modelled 2-year Velocity (m/s):	Not modelled		

Profile Characteristics	
Bankfull Gradient (%):	3.33
Channel Bed Gradient (%):	2.55
Riffle Gradient (%):	Not measured
Riffle Length (m):	Not measured
Riffle-Pool Spacing (m):	Not measured

Planform Characteristics	
Sinuosity:	1.10
Meander Belt Width (m):	Not measured
Radius of Curvature (m):	Not measured
Meander Amplitude (m):	Not measured
Meander wavelength (m):	Not measured



<b>Bank Characteristi</b>	cs						
	Minimum	Maximum	Average		Minimum	Maximum	Average
Bank Height (m):	0.2	1.30	0.91				
Bank Angle (deg):	25	90	72	Torvane Value (kg/cm²):	1	Not measured	
Root Depth (m):	0.00	0.45	0.22	Penetrometer Value (kg/cm <sup>3</sup> ):	1	Not measured	
Root Density (%):	0	10	6	Bank Material (range):		Clay to silt	
Bank Undercut (m):	0	0.4	0.10				


GEO Morphix Ltd. Page 1 of 3

	Minimum	Maximum	Average
Bankfull Width (m):	1.30	3.40	2.25
Average Bankfull Depth (m):	0.16	0.90	0.50
Bankfull Width/Depth (m/m):	2	8	5
Wetted Width (m):	0.55	1.30	0.93
Average Water Depth (m):	0.00	0.08	0.05
Wetted Width/Depth (m/m):	8	68	26
Entrenchment (m):		Not measured	
Entrenchment Ratio (m/m):		Not measured	
Maximum Water Depth (m):	0.03	0.14	0.07
Manning's <i>n</i> :		0.040	



Photograph at cross section 4 (looking downstream)

## **Representative Cross-Section 2**



Particle Size (mm)		:	Subpavement:	Till	
D <sub>10</sub> :	2.0	I	Particle shape:	Platy	
D <sub>50</sub> :	3.2	1	Embeddedness (%):	10 to 50	
D <sub>84</sub> :	15.0	1	Particle range (riffle):	Clay to cobble	
		1	Particle Range (pool):	Clay to gravel	
100 90 80		Cumulative Partic	le Size Distribution		
70					
60					


GEO Morphix Ltd. Page 2 of 3

Channel Thresholds					
Flow Competency (m/s):		Tractive Force at Bankfull (N/m <sup>2</sup> ):	164.37		
for D <sub>50</sub> :	0.34	Tractive Force at 2-year flow (N/m <sup>2</sup> ):	Not modelled		
for D <sub>84</sub> :	0.69	Critical Shear Stress (D <sub>50</sub> ) (N/m <sup>2</sup> ):	2.33		
Unit Stream Power at Bankfull (W/m²):	474.20				

### **General Field Observations**


### **Channel Description**

Reach FCT-1 was a mixed-load meandering channel, with a moderate gradient that sits within a confined valley. The channel flowed through a continuous riparian buffer zone that extended 4 to 10 times the channel width and contained predominately trees and herbaceous vegetation. The channel was heavily encroached by vegetation. High density of woody debris was observed in the channel. The average bankfull width and depth were 2.44 m and 0.50 m. The average wetted width and depth were 0.93 m and 0.05 m. Bank angles ranged from 25 to 90 degrees, with undercutting measured up to 0.4 m. Bed materials ranged from clay to cobbles in riffles, and clay to gravel in pools. Bank material consisted of clay and silt.




GEO Morphix Ltd. Page 3 of 3

Appendix F:
Outfall Design Drawings




# **PLANFORM** 1:250


<u>LEGEND</u> SCONED (SEE DWG GEO-1) SCONED (SEE DWG GEO-1) 100% BIODEGRADABLE EROSION CONTROL BLANKET AND LIVE STAKES (SEE DWG DET-1) LEVEL SPREADER (SEE DWG DET-1)



# **CROSS SECTION A-A'**



# **CROSS SECTION B-B'** 1:100




TOPSOIL

STONE CORE (SEE DWG GEO-1)

₩ 100% BIODEGRADABLE EROSION CONTROL BLANKET, WET MEADOW SEED AND LIVE STAKES (SEE DWG DET-1)

LEVEL SPREADER (SEE DWG DET-1)



1. THE ACCOMPANYING CHANNEL REALIGNMENT TECHNICAL DESIGN BRIEF PREPARED BY GEO MORPHIX LTD. (2025) PROVIDES ADDITIONAL DESIGN DETAILS AND DIRECTION FOR IMPLEMENTATION AND IS TO BE REVIEWED IN CONJUNCTION WITH THIS DRAWING SET.

- 2. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING
- CONSTRUCTION FOR REFERENCE.

  3. THE CONTRACTOR MUST NOTIFY THE DESIGNER AND CONTRACT ADMINISTRATOR OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
- 4. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES.
  5. LAYOUT MUST BE REVIEWED AND APPROVED BY THE DESIGNER / DESIGNER REPRESENTATIVE, DESIGNATED.
- ENGINEER, AND THE CONTRACT ADMINISTRATOR. CONSTRUCTION OBSERVATION IS TO BE PERFORMED BY A CERTIFIED FLUVIAL GEOMORPHOLOGIST OR EXPERIENCED ENVIRONMENTAL INSPECTOR UNDER DIRECTION FROM THE DESIGNER.
- 7. ON-SITE SUPPORT FROM PROJECT ENGINEER (E.G., GEOTECHNICAL, HYDROGEOLOGICAL, AND/OR WATER RESOURCES ENGINEER) REQUIRED TO ASSESS AND ENSURE FAVOURABLE SURFICIAL AND SUBSURFACE CONDITIONS TO SUPPORT CHANNEL REALIGNMENT CONSTRUCTION.
- 8. BE ADVISED THAT THE LOCAL REGULATORY BODY MAY, AT ANY TIME, WITHDRAW THIS PERMISSION, IF, IN THE OPINION OF THE AUTHORITY, THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVAL DOES NOT EXEMPT THE PROPERTY OWNER/APPLICANT/AGENT FROM THE PROVISIONS OF ANY OTHER FEDERAL, PROVINCIAL OF

## MUNICIPAL STATUTES, REGULATIONS OR BY-LAWS, OR ANY RIGHTS UNDER COMMON LAW. TIMING OF WORKS

WORKS SHALL BE COMPLETED DURING THE DESIGNATED IN-WATER WORKS WINDOW SET OUT BY MNR/DEO TREE CLEARING IS TO BE COMPLETED OUTSIDE THE BIRD NESTING SEASON (APRIL 1ST TO AUGUST 31ST) AND THE BAT ROOSTING WINDOW (APRIL 1ST TO SEPTEMBER 30TH) TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT AND THE PROVINCIAL ENDANGERED SPECIES ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE

OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST TO DETERMINE THE PRESENCE OF 3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS. 4. COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

### SITE AND MATERIAL MANAGEMENT

1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED STAGING/STORAGE 2. IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN

STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
 STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS

OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN.

- 5. MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE. ALL DISTURBED GROUND LEFT INACTIVE FOR MORE THAN 30 DAYS SHALL BE STABILIZED USING APPROPRIATE EROSION CONTROL MEASURES AND AN APPROPRIATE SEED
- MIX AS NOTED WITHIN THE FINAL APPROVED RESTORATION PLAN. 6. ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION
- 7. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED,
- UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.
- 8. AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ONSITE FOR EMERGENCIES. ALL THE PLANS SHOULD HAVE NAME AND CONTACT INFO OF THE PERSON RESPONSIBLE FOR ESC MEASURES.

## EROSION AND SEDIMENT CONTROL

- 1. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS. 2. FOLLOWING INSTALLATION OF THE PROPOSED ESC MEASURES, A QUALIFIED AGENT OF THE PROPONENT (E.G. CAN-CISEC CERTIFIED MONITOR) WILL CONDUCT REGULAR SITE VISITS TO MONITOR ALL WORKS. PARTICULARLY THE CONDITION OF THE ESC MEASURES, DEWATERING, AND IN- OR NEAR-WATER WORKS. SHOULD CONCERNS ARISE; THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, THE CONSERVATION AUTHORITY, AND ANY OTHER APPROPRIATE PARTIES
- 3. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE
- 4. EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER FUNCTION. 5. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
- 6. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATI
- REPAIRS AND/OR UPGRADES AS NEEDED.
  7. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE SITE 8. THE PROJECT PROPONENT OR THEIR REPRESENTATIVE IS ULTIMATELY RESPONSIBLE FOR CONTROLLING SEDIMENT
- AND EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION. 9. IF EXCESSIVE SILTATION RESULTS FROM THE CONSTRUCTION ACTIVITIES, THE ONSITE SUPERVISOR/INSPECTOR
- AND/OR THE LOCAL REGULATORY BODY RESERVE THE RIGHT TO REQUEST ADDITIONAL ESC MEASURES WHICH WOULD BE INSTALLED PRIOR TO FURTHER CONSTRUCTION ACTIVITIES.

## **DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT** 1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY

- OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAVINE OR STORM SEWER SYSTEM. 2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS,
- EXCESS OIL, AND GREASE. 3. NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR
- SURFACE WATER DRAINAGE. 4. A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ONSITE STAFF MUST BE TRAINED IN ITS USE.
- 5. THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE. ANY SEDIMENT SPILL FROM THE SITE SHOULD BE REPORTED TO MINISTRY OF ENVIRONMENT (SPILL ACTION CENTER) AT 1-800-268-6060.

# **WORK AREA ISOLATION**

RESOURCES.

- 1. ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
  2. CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT PERMITTED
- UNLESS APPROVED BY THE CONSERVATION AUTHORITY. ALL ACCESS TO WORK SITES SHALL BE FROM EITHER SIDES OF THE WATERCOURSE OR WETLAND. 3. THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 m FROM ANY WATERCOURSE OR WETLAND
- IN AN AREA WITH DENSE VEGETATIVE GROUNDCOVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUNDCOVER 4. FISH AND AMPHIBIANS MUST BE REMOVED FROM THE WORK AREA ONCE ISOLATED. FISH AND AMPHIBIAN SALVAGE

MUST BE COMPLETED BY A QUALIFIED TECHNICIAN WITH A LICENSE FROM THE ONTARIO MINISTRY OF NATURAL

1.0 08/15/2025 FIRST DETAILED DESIGN SUBMISSION TO CLIENT DATE REVISIONS DESIGNED BY: AS CHECKED BY: PV DRAWN BY: RS DATE: AUGUST 2025

DRAFT FOR **INTERNAL** DISCUSSION

**NOT FOR** 

 $M O R P H I X^{\mathsf{m}}$ 36 Main St N., P.O. Box 205

Campbellville, Ontario L0P 1B0

T: 416.920.0926 www.geomorphix.com


DEZEN REALTY DEVELOPMENT 7140 HURONTARIO STREET CITY OF MISSISSAUGA

FLETCHERS CREEK SWM OUTFALL DESIGN SUPPORT PLANFORM AND PROFILE

PROJECT No.: PN25102 DRAWING No.: GEO-1

SCALED FOR PLOT ON 'ARCH D'

SHEET 1 OF 2 SCALE: AS NOTED



SCIENTIFIC NAME	COMMON NAME	QTY	CONDITION
CORNUS STOLONIFERA	RED OSIER DOGWOOD	34	1 m, LIVE STAKE
SALIX BEBBIANA	BEBB'S WILLOW	34	1 m, LIVE STAKE
SALIX DISCOLOR	PUSSY WILLOW	34	1 m, LIVE STAKE
SALIX INTERIOR	SANDBAR WILLOW	34	1 m, LIVE STAKE
SALIX LUCIDA	SHINING WILLOW	34	1 m, LIVE STAKE


- QUANTITY TO BE DETERMINED BASED ON AREA OF DISTURBANCE TO BE RESTORED
- LIVE STAKES SHOULD BE FROM AT MINIMUM 2-YEAR OLD STOCK.
- 3. LIVE STAKES ARE TO BE INSTALLED AT A DENSITY OF 3 STAKES PER SQUARE METRE.
- 4. LIVE STAKES SHOULD BE PRE-SOAKED (SUBMERGED IN WATER) FOR AT LEAST 24 HOURS AFTER HARVESTING AND IMMEDIATELY BEFORE INSTALLATION.
- 5. LIVE STAKES SHOULD NOT BE STORED FOR A PERIOD LONGER THAN 2 DAYS, UNLESS THEY ARE BEING SOAKED.
- 6. THE CONTRACTOR SHALL PROTECT PLANT MATERIALS FROM DRYING FROM THE TIME OF
- HARVEST UNTIL INSTALLED. 7. LIVE STAKES ARE TO BE A MINIMUM OF 25 mm IN DIAMETER AND CUT TO A LENGTH OF 1000
- 8. CUT ANGLE AT THE BOTTOM OF THE STAKE AND FLAT ON THE TOP.
- 9. TRIM ALL SIDE BRANCHES WHILE TAKING CARE NOT TO DAMAGE THE BARK.
- 10. INSTALL STAKES WITH BUDS POINTING UPWARDS AND THICKER STEM IN THE BED.
- 11. LIVE STAKES SHOULD BE INSTALLED USING A LARGE RUBBER MALLET.
- 14. IN COMPACT SOIL A PILOT HOLE MUST BE USED TO LIMIT DAMAGE TO THE STAKES. PILOT
- HOLES SHOULD BE MAX. 25 mm DIAMETER. 15. IF USING A PILOT HOLE REPACK SOIL AROUND THE LIVE STAKE.
- 16. 80% OF THE STAKE IS TO BE BELOW SURFACE.
- 17. TAMP THE LIVE STAKE INTO THE GROUND AT RIGHT ANGLE TO THE SURFACE.
- 18. LIVE STAKES SHOULD STAND FIRM FROM THE SOIL FOLLOWING INSTALLATION. 19. ALL STAKES NOT PLANTED TO THE SPECIFICATIONS ABOVE WILL BE REPLACED AT THE

CONTRACTOR'S EXPENSE.

# LIVE STAKING

# **EROSION CONTROL BLANKET SPECIFICATIONS**

- 1. A BIODEGRADABLE EROSION CONTROL BLANKET (ECB) SHALL BE INSTALLED ON ALL DISTURBED NATURAL SURFACES FOLLOWING THE PLACEMENT OF TOPSOIL AND APPLICATION OF THE NATIVE SEED MIX.
- 2. THE ECB MUST BE CONSTRUCTED OF 100% WOVEN COCONUT FIBRE (E.G., COIR) OR STRAW MAT WITHIN A GEOJUTE NETTING (TOP AND BOTTOM) WITH BIODEGRADABLE THREAD. NON-BIODEGRADABLE MATERIAL INCLUDING POLYPROPELENE OR PLASTICS WITH A BIODEGRADABLE RATING ARE NOT ACCEPTABLE. THE MINIMUM WEIGHT OF THE ECB MUST BE 400 g/m<sup>2</sup> (12 oz./yd<sup>2</sup>).
- 3. TO INSTALL, THE ECB MUST BE UNROLLED DOWNSLOPE OR IN DIRECTION OF WATER FLOW. ADJACENT ECBS SHOULD OVERLAP A MINIMUM OF 150 mm ALONG THE EDGES. AT THE END OF EACH ROLL, FOLD BACK 100 mm TO 200 mm OF THE ECB. OVERLAP THIS 100 mm TO 200 mm OVER THE START OF THE NEXT ROLL. SECURE THE TWO LAYERS TO THE GROUND SECURELY.
- 4. BIODEGRADABLE OR TAPERED WOODEN STAKES SHALL BE USED TO SECURE THE BLANKET. STAKES SHALL BE INSTALLED AT THE SPACING RECOMMENDED BY THE ECB MANUFACTURER TO PREVENT SURFACE RUNOFF FROM ERODING THE UNDERLYING SOIL.



- 1. WATTLE AND SILTSOXX TO BE INSTALLED IN A 200 mm WIDE TRENCH AND STAKED
- 2. WATTLE, SILTSOXX AND GRADING INSTALLATION TO RESULT IN A LEVEL BERM WITHOUT BREAKS.

# WATTLE AND FILTREXX® SILTSOXX™ (OR EQUIVALENT) DETAIL

# **CVC 3 – LOWLAND RESTORATION MIX**

SCIENTIFIC NAME	COMMON NAME	PERCENTAGE
ANEMONE CANADENSIS	CANADA ANEMONE	1
BIDENS CERNUA	NODDING BEAGGARTICKS	1
CAREX VULPINOIDEA	FOX SEDGE	25
ELYMUS VIRGINICUS VAR. VIRGINICUS	VIRGINIA WILD RYE	25
EUTROCHIUM MACULATUM VAR. MACULATUM	SPOTTED JOE PYE WEED	1
JUNCUS EFFUSUS SUBSP. SOLUTUS	EASTERN SOFT RUSH	5
JUNCUS TENUIS	PATH RUSH	5
POA PALUSTRIS	FOWL BLUEGRASS	25
SCIRPUS ATROVIRENS	DARK GREEN BULRUSH	5
SYMPHYOTRICHUM NOVAE-ANGLIAE	NEW ENGLAND ASTER	1
SYMPHYOTRICHUM PUNICEUM	SWAMP ASTER	1
VERBENA HASTATA	BLUE VERVAIN	5
NOTES.		


- 1. APPLY SEED MIX AT A RATE OF 25 kg PER HECTARE.
- 2. SEEDING SHALL OVERLAP ADJACENT GROUND COVER BY 300 mm. 3. SIMULTANEOUSLY APPLY THE SPECIED NURSE CROP MIX AT A RATE OF 15 kg PER
- 4. WATER SOIL AFTER SEED APPLICATION.

# **CVC RESTORATION NURSE CROP MIX**

SCIENTIFIC NAME	COMMON NAME	PERCENTAGE
AVENA SATIVA	ANNUAL OATS	40
ELYMUS CANADENSIS	CANADA WILD RYE	15
HORDEUM VULGARE	BARLEY	45
NOTES		

# 1. APPLY SEED MIX AT A RATE OF 15 kg PER HECTARE.

- 2. SEEDING SHALL OVERLAP ADJACENT GROUND COVER BY 300 mm.
- 3. SIMULTANEOUSLY APPLY THE SPECIFIED NATIVE SEED MIX AT A RATE OF 25 kg PER HECTARE.
- 4. WATER SOIL AFTER SEED APPLICATION.
- 5. IF SEEDING IN FALL (OCTOBER-NOVEMBER), 100% WINTER WHEAT (TRITICUM AESTIVUM) SHOULD BE SUBSTITUTED FOR THE SPECIES LISTED ABOVE.



1. THE ACCOMPANYING CHANNEL REALIGNMENT TECHNICAL DESIGN BRIEF PREPARED BY GEO MORPHIX LTD. (2025) PROVIDES ADDITIONAL DESIGN DETAILS AND DIRECTION FOR IMPLEMENTATION AND IS TO BE REVIEWED IN

- CONJUNCTION WITH THIS DRAWING SET. 2. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING
- CONSTRUCTION FOR REFERENCE. 3. THE CONTRACTOR MUST NOTIFY THE DESIGNER AND CONTRACT ADMINISTRATOR OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE
- THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES.
   LAYOUT MUST BE REVIEWED AND APPROVED BY THE DESIGNER / DESIGNER REPRESENTATIVE, DESIGNATED
- ENGINEER, AND THE CONTRACT ADMINISTRATOR. 6. CONSTRUCTION OBSERVATION IS TO BE PERFORMED BY A CERTIFIED FLUVIAL GEOMORPHOLOGIST OR EXPERIENCED ENVIRONMENTAL INSPECTOR UNDER DIRECTION FROM THE DESIGNER.
- 7. ON-SITE SUPPORT FROM PROJECT ENGINEER (E.G., GEOTECHNICAL, HYDROGEOLOGICAL, AND/OR WATER RESOURCES ENGINEER) REQUIRED TO ASSESS AND ENSURE FAVOURABLE SURFICIAL AND SUBSURFACE CONDITIONS TO SUPPORT CHANNEL REALIGNMENT CONSTRUCTION.
- 8. BE ADVISED THAT THE LOCAL REGULATORY BODY MAY, AT ANY TIME, WITHDRAW THIS PERMISSION, IF, IN THE OPINION OF THE AUTHORITY, THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVAL DOES NOT EXEMPT THE PROPERTY OWNER/APPLICANT/AGENT FROM THE PROVISIONS OF ANY OTHER FEDERAL, PROVINCIAL OR MUNICIPAL STATUTES, REGULATIONS OR BY-LAWS, OR ANY RIGHTS UNDER COMMON LAW.

- WORKS SHALL BE COMPLETED DURING THE DESIGNATED IN-WATER WORKS WINDOW SET OUT BY MNR/DFO TREE CLEARING IS TO BE COMPLETED OUTSIDE THE BIRD NESTING SEASON (APRIL 1ST TO AUGUST 31ST) AND THE BAT ROOSTING WINDOW (APRIL 1ST TO SEPTEMBER 30TH) TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT AND THE PROVINCIAL ENDANGERED SPECIES ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST TO DETERMINE THE PRESENCE OF
- THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.

4. COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE. SITE AND MATERIAL MANAGEMENT

1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m AWAY

2. IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN

FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED STAGING/STORAGE

- OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN. STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
   STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS
- 5. MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE. ALL DISTURBED GROUND LEFT INACTIVE FOR MORE THAN 30 DAYS SHALL BE STABILIZED USING APPROPRIATE EROSION CONTROL MEASURES AND AN APPROPRIATE SEED
- MIX AS NOTED WITHIN THE FINAL APPROVED RESTORATION PLAN. ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
- 7. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED,
- UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.

  8. AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ONSITE FOR EMERGENCIES. ALL THE PLANS SHOULD
- HAVE NAME AND CONTACT INFO OF THE PERSON RESPONSIBLE FOR ESC MEASURES.

## EROSION AND SEDIMENT CONTROL

- 1. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS 2. FOLLOWING INSTALLATION OF THE PROPOSED ESC MEASURES, A QUALIFIED AGENT OF THE PROPONENT (E.G. CAN-CISEC CERTIFIED MONITOR) WILL CONDUCT REGULAR SITE VISITS TO MONITOR ALL WORKS, PARTICULARLY THE CONDITION OF THE ESC MEASURES, DEWATERING, AND IN- OR NEAR-WATER WORKS, SHOULD CONCERNS ARISE: THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, THE CONSERVATION AUTHORITY, AND ANY OTHER
- 3. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE
- 4. EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER FUNCTION. 5. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
- 6. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.
  7. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE SITE
- 8. THE PROJECT PROPONENT OR THEIR REPRESENTATIVE IS ULTIMATELY RESPONSIBLE FOR CONTROLLING SEDIMENT AND EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION.
- 9. IF EXCESSIVE SILTATION RESULTS FROM THE CONSTRUCTION ACTIVITIES, THE ONSITE SUPERVISOR/INSPECTOR AND/OR THE LOCAL REGULATORY BODY RESERVE THE RIGHT TO REQUEST ADDITIONAL ESC MEASURES WHICH
- WOULD BE INSTALLED PRIOR TO FURTHER CONSTRUCTION ACTIVITIES.

# DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT

- 1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAVINE OR STORM SEWER SYSTEM. 2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS,
- 3. NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER DRAINAGE.
- 4. A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ONSITE STAFF MUST BE TRAINED IN ITS USE
- 5. THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE. ANY SEDIMENT SPILL FROM THE SITE SHOULD BE REPORTED TO MINISTRY OF ENVIRONMENT (SPILL ACTION CENTER) AT 1-800-268-6060.

# WORK AREA ISOLATION

- 1. ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT PERMITTED UNLESS APPROVED BY THE CONSERVATION AUTHORITY. ALL ACCESS TO WORK SITES SHALL BE FROM EITHER SIDES OF THE WATERCOURSE OR WETLAND.
- 3. THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 m FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUNDCOVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUNDCOVER.
- 4. FISH AND AMPHIBIANS MUST BE REMOVED FROM THE WORK AREA ONCE ISOLATED. FISH AND AMPHIBIAN SALVAGE MUST BE COMPLETED BY A QUALIFIED TECHNICIAN WITH A LICENSE FROM THE ONTARIO MINISTRY OF NATURAL RESOURCES.

1.0	08/15/2025	AS	FIRST DETAILED DESIGN SUBMISSION TO CLIEN		
	DATE	BY			REVISIONS
DESIGNED BY: AS			CHECKED BY: PV		
DRAWN BY: RS			DATE: AUGUST 2025		
	DRAFT I	OR			CEO

INTERNAL DISCUSSION

 $M O R P H I X^{\mathsf{m}}$ 36 Main St N., P.O. Box 205

NOT FOR CONSTRUCTION

Campbellville, Ontario L0P 1B0 T: 416.920.0926 www.geomorphix.com

DEZEN REALTY DEVELOPMENT 7140 HURONTARIO STREET CITY OF MISSISSAUGA

FLETCHERS CREEK SWM OUTFALL DESIGN SUPPORT PLANFORM AND PROFILE

PROJECT No.: PN25102 DRAWING No.: DET-1 SHEET 2 OF 2 SCALE: AS NOTED

SCALED FOR PLOT ON 'ARCH D'