P:\P\60549_001\60549_001-C2.DWG

REGION OF PEEL NOTES

1. PUBLIC AND PRIVATE SERVICES, APPURTENANCES, MATERIALS AND CONSTRUCTION METHODS MUST COMPLY WITH THE MOST CURRENT REGION OF PEEL STANDARDS AND SPECIFICATIONS, THE LOCAL MUNICIPALITY'S REQUIREMENTS FOR THE ONTARIO BUILDING CODE AND ONTARIO PROVINCIAL STANDARDS. ALL WORKS SHALL ADHERE TO ALL APPLICABLE LEGISLATION, INCLUDING REGIONAL BY-LAWS.
2. WATERMAIN AND/OR WATER SERVICE MATERIALS 100MM (4") AND LARGER MUST BE PVC DR-18 CONSTRUCTED AS PER AWWA C900-16. SIZE 50MM (2") AND SMALLER MUST BE TYPE "K" SOFT COPPER CONSTRUCTED AS PER ASTM B88-49.
3. WATERMAIN AND/OR SERVICES ARE TO HAVE A MINIMUM COVER OF 1.7M (5'6") WITH A MINIMUM HORIZONTAL SPACING OF 1.2M (4') FROM THEMSELVES AND ALL OTHER UTILITIES.
4. PROVISIONS FOR FLUSHING WATER LINE PRIOR TO TESTING ETC. MUST BE PROVIDED WITH AT LEAST A 50MM (2") OUTLET ON 100MM (4") AND LARGER LINES. COPPER LINES ARE TO HAVE FLUSHING POINTS AT THE END, THE SAME SIZE AS THE LINE. THEY MUST ALSO BE HOSED OR PIPED TO ALLOW THE WATER TO DRAIN ONTO A PARKING LOT OR DOWN A DRAIN, ON FIRE LINES, FLUSHING OUTLET TO BE 100MM (4") DIAMETER MINIMUM ON A HYDRANT.
5. ALL CURB STOPS TO BE 3.0M (10') OFF THE FACE OF THE BUILDING UNLESS OTHERWISE NOTED.
6. HYDRANT AND VALVE SET TO REGION STANDARD 1-6-1, DIMENSION A AND B, 0.7M (2') AND 0.9M (3') AND TO HAVE PUMPER NOZZLE.
7. WATERMAINS TO BE INSTALLED TO GRADES AS SHOWN ON APPROVED SITE PLAN. COPY OF GRADE SHEET MUST BE SUPPLIED TO INSPECTOR PRIOR TO COMMENCEMENT OF WORK, WHERE REQUESTED BY INSPECTOR.
8. WATERMAINS MUST HAVE A MINIMUM VERTICAL CLEARANCE OF 0.3M (12") OVER/0.5M (20") UNDER SEWERS AND ALL OTHER UTILITIES WHEN CROSSING.
9. ALL PROPOSED WATER PIPING MUST BE ISOLATED FROM EXISTING LINES IN ORDER TO ALLOW INDEPENDENT PRESSURE TESTING AND CHLORINATING FROM EXISTING SYSTEMS.
10. ALL LIVE TAPPING AND OPERATION OF REGION WATER VALVES SHALL BE ARRANGED THROUGH THE REGIONAL INSPECTOR ASSIGNED OR BY CONTACTING THE OPERATIONS AND MAINTENANCE DIVISION.
11. LOCATION OF ALL EXISTING UTILITIES IN THE FIELD TO BE ESTABLISHED BY THE CONTRACTOR.
12. THE CONTRACTOR(S) SHALL BE SOLELY RESPONSIBLE FOR LOCATES, EXPOSING, SUPPORTING AND PROTECTING OF ALL UNDERGROUND AND OVERHEAD UTILITIES AND STRUCTURES EXISTING AT THE TIME OF CONSTRUCTION IN THE AREA OF THE WORK, WHETHER SHOWN ON THE PLANS OR NOT AND FOR ALL REPAIRS AND CONSEQUENCES RESULTING FROM DAMAGE TO THE SAME.
13. THE CONTRACTOR(S) SHALL BE SOLELY RESPONSIBLE TO GIVE 72 HOURS WRITTEN NOTICE TO THE UTILITIES PRIOR TO CROSSING SUCH UTILITIES, FOR THE PURPOSE OF INSPECTION BY THE CONCERNED UTILITY. THIS INSPECTION WILL BE FOR THE DURATION OF THE CONSTRUCTION, WITH THE CONTRACTOR RESPONSIBLE FOR ALL COSTS ARISING FROM SUCH INSPECTION.
14. ALL PROPOSED WATER PIPING MUST BE ISOLATED THROUGH A TEMPORARY CONNECTION THAT SHALL INCLUDE AN APPROPRIATE CROSS-CONNECTION CONTROL DEVICE, CONSISTENT WITH THE DEGREE OF HAZARD, FOR BACKFLOW PREVENTION OF THE ACTIVE DISTRIBUTION SYSTEM, CONFORMING TO REGION OF PEEL STANDARDS 1-7-7 OR 1-7-8.
15. ALL WATER METERS MUST BE INSTALLED IN HEATED AND ACCESSIBLE SPACE.

THE KING'S HIGHWAY N° 401

43r-23417

part 4 plan 43r-23554

part 1, plan 43r-23554

part 94 plan 43r-23554

part 8 plan 43r-23554

MATCHLINE, SEE CONTINUATION ON C2.2B

SEWER CROSSING CHART

NOTE:
1) Maintain minimum 0.5m vertical clearance between all watermains and sewers. Where watermain is deflected, ensure 2.0 m cover is achieved or watermain is insulated.
2) Maintain vertical clearance at all their crossings.
3) Existing and proposed sewer and watermain inverts are approximate only. Notify Design Engineer of any discre epancies.
4) Contractor is verify all existing inverts prior to product ordering. Notify Design Engineer of any discre epancies.

CROSSING #	SEWER TYPE	SEWER SIZE (mm ø)	CROSSING ELEVATION	NOTES
X1	STM	825	BOT=207.56	MAINTAIN MIN. 0.3m VERTICAL SEPARATION
	SAN	250	TOP=204.20	
X2	STM	675	BOT=207.70	MAINTAIN MIN. 0.3m VERTICAL SEPARATION
	SAN	250	TOP=204.46	
X3	STM	450	BOT=206.76	MAINTAIN MIN. 0.3m VERTICAL SEPARATION
	SAN	150	TOP=204.38	
X4	STM	675	BOT=207.75	MAINTAIN MIN. 0.3m VERTICAL SEPARATION
	SAN	450	TOP=207.44	
X5	WTM	300	BOT=209.90	MAINTAIN MIN. 0.3m VERTICAL SEPARATION
	STM	450	TOP=207.50	
X6	WTM	150	BOT=210.30	MAINTAIN MIN. 0.3m VERTICAL SEPARATION
	STM	450	TOP=208.03	
X7	STM	450	BOT=207.70	MAINTAIN MIN. 0.3m VERTICAL SEPARATION
	SAN	250	TOP=206.66	
X8	STM	375	BOT=209.39	MAINTAIN MIN. 0.3m VERTICAL SEPARATION
	STM	675	TOP=209.09	
X9	WTM	300	BOT=209.60	MAINTAIN MIN. 0.3m VERTICAL SEPARATION
	SAN	250	TOP=206.74	

NOTE:
REFER TO SITEPLAN/LANDSCAPE PLAN FOR ALL SURFACE TYPES AND DETAILS

NOTES TO CONTRACTOR:

1. INSPECTION
CONTRACTOR IS RESPONSIBLE FOR CONTACTING ENGINEER & CITY INSPECTION STAFF 48 HRS PRIOR TO COMMENCING WORK TO ARRANGE FOR INSPECTION & OFF-SITE WORKS. ENGINEER TO DETERMINE DEGREE OF INSPECTION AND TESTING REQUIRED FOR CERTIFICATION OF UNDERGROUND SERVICE INSTALLATION AS MANDATED BY ONTARIO BUILDING CODE DIVISION C, PART 1, SECTION 1.2.2, GENERAL REVIEW. FAILURE TO NOTIFY ENGINEER WILL RESULT IN EXTENSIVE POST CONSTRUCTION INSPECTION AT CONTRACTORS EXPENSE.
2. CONFIRMATION OF EXISTING INVERTS
72 HOURS PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR IS TO LOCATE, EXPOSE AND VERIFY INVERTS OF EXISTING SEWERS AT CONNECTION POINTS AND REPORT FINDINGS TO MTE. SHOULD THE CONTRACTOR PROCEED WITHOUT COMPLETING THESE LOCATES, EXTRA COSTS RESULTING FROM DELAYS AND STANDBY TIME WILL NOT BE CONSIDERED.


LEGEND OF EXISTING FEATURES

- SITE BOUNDARY
- EASEMENT
- EXISTING SANITARY SEWER
- EXISTING WATERMAIN
- EXISTING STORM SEWER
- EXISTING CURB
- EXISTING FENCE
- EXISTING EMBANKMENT (SLOPE AS NOTED)

LEGEND OF PROPOSED FEATURES

- EMBANKMENT (SLOPE AS NOTED)
- SANITARY SEWER
- STORM SEWER
- PERFORATED BIG 'O' SUBDRAIN (SEE DETAIL)
- WATERMAIN
- PROPOSED BUILDING
- OVERHEAD DOOR
- MAN DOOR
- FENCE
- CONCRETE CURB
- RETAINING WALL
- SHALLOW PIPE INSULATION (SEE DETAIL)
- FLOW CONTROL ROOF DRAIN ZURN MODEL Z105* SINGLE NOTCH *OR APPROVED EQUAL
- RIP RAP (SIZE & TYPE AS NOTED)
- LIGHT POLE (SEE SITE PLAN)
- WATER METER
- BACKFLOW PREVENTER
- SAW CUT c/w LAP JOINT (SEE DETAIL)
- PROPOSED TREE (SEE LANDSCAPE PLAN)

CITY OF MISSISAUGA



KEY PLAN N.T.S.

GEODETIC BENCHMARK ELEV. = 208.076m

ELEVATIONS ARE REFERRED TO THE CITY OF MISSISAUGA BENCHMARK No. 1045, LOCATED AT THE BASE OF A 750mmø CONCRETE TRAFFIC POLE AT THE SOUTH-WEST CORNER OF ARGENTIA ROAD AND PLAZA ENTRANCE (WALMART), HAVING A PUBLISHED ELEVATION OF 208.076 METRES.

SITE BENCHMARK ELEV. = m

SEE GEODETIC BENCHMARK

NOTE TO CONTRACTOR :

DO NOT SCALE DRAWINGS.

CONTRACTORS MUST CHECK AND VERIFY ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO THE ENGINEER BEFORE PROCEEDING WITH THE WORK.

ALL DRAWINGS REMAIN THE PROPERTY OF THE ENGINEER AND SHALL NOT BE REPRODUCED OR REUSED WITHOUT THE ENGINEER'S WRITTEN PERMISSION.

THE OWNER/ARCHITECT/CONTRACTOR IS ADVISED THAT M.T.E. CONSULTANTS INC. CANNOT CERTIFY ANY COMPONENT OF THE SITE WORKS NOT INSPECTED DURING CONSTRUCTION. IT IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO NOTIFY M.T.E. CONSULTANTS INC. PRIOR TO COMMENCEMENT OF CONSTRUCTION TO ARRANGE FOR INSPECTION.

No.	REVISION	BY	YYYY-MM-DD
16.	ISSUED FOR SPA RE-SUBMISSION	RDZ	2026-09-25
15.	ISSUED FOR SPA RE-SUBMISSION	RDZ	2026-09-10
14.	CONTRACT DOCUMENTS (100%) SUBMISSION	RDZ	2026-08-20
13.	CONTRACT DOCUMENTS (90%) SUBMISSION	RDZ	2026-07-22
12.	ISSUED FOR SPA RE-SUBMISSION	RDZ	2026-07-06
11.	CONTRACT DOCUMENTS (75%) SUBMISSION	RDZ	2026-06-30
10.	ADDENDUM #01 (EARLY WORKS)	RDZ	2026-06-29
9.	ISSUED FOR ZBA-RESUBMISSION	RDZ	2026-06-16
8.	CONTRACT DOCUMENTS (50%) SUBMISSION	RDZ	2026-05-29
7.	ISSUED FOR BUILDING PERMIT	RDZ	2026-05-12
6.	ISSUED FOR SPA RE-SUBMISSION	RDZ	2026-03-25
5.	ISSUED FOR SPA RE-SUBMISSION	RDZ	2026-03-04
4.	RE-ISSUED FOR GRADING PERMIT	RDZ	2026-02-06
3.	RE-ISSUED FOR GRADING PERMIT	RDZ	2025-10-28
2.	ISSUED FOR SPA	RDZ	2025-08-06
1.	ISSUED FOR GRADING PERMIT	RDZ	2025-06-30

MTE
Engineers, Scientists, Surveyors
905-639-2552

LICENSED PROFESSIONAL ENGINEER 2026-09-25 R.D.ZHOU 100567167 PROVINCE OF ONTARIO

NOT FOR CONSTRUCTION

CLIENT
PETROFF PARTNERSHIP ARCHITECTS
10 AVIVA WAY SUITE 400 MARKHAM

PROJECT
PROLOGIS MEADOWVALE DC4/DC5 & DATA CENTRE
3261/3265 ARGENTIA ROAD (DC5/DC4)
7700 TENTH LINE WEST (DATA CENTER) MISSISSAUGA

DRAWING
SITE SERVICING PLAN 1
SP 25-063 W9 (DATA CENTER)
SP 25-065 W9 (DC5/DC4)

Project Manager	R.ZHOU	Job No.	60549_001
Design By	NZR	Checked By	RDZ
Drawn By	AXG	Checked By	NZR
Surveyed By	Others	Drawing No.	C2.2A
Date	Jun.11/25		
Scale	1:400	Sheet 4 of 8	

September 25, 2026 - 12:25:25 PM - Plotted By: Alla Gulkin