




DOOR SCHEDULE		DOOR LEAF						DOOR FRAME FINISH		DOOR TYPE	QUANTITY	LOCKABLE	HEADING END INSULATION	PRE-INSULATING	SELF-CLOSING	DESCRIPTION
DOOR NO	TYPE	DOOR FRAME	WIDTH	HEIGHT	THICKNESS (mm)	MATERIAL	FINISH	MATERIAL	FINISH							
<u>D021</u>	INTERIOR	3"	32"	7'-10"	35	HOLLOW CORE	PAIN	VINYL	PRE FINISHED	SINGLE DOOR	3	✓	✓	✓	✓	PANEL TEXTURED PRE-HUNG SINGLE DOOR
<u>D022</u>	INTERIOR	3"	28"	7'-10"	35	HOLLOW CORE	PAIN	VINYL	PRE FINISHED	SINGLE DOOR	1	✓	✓	✓	✓	PANEL TEXTURED PRE-HUNG SINGLE DOOR
<u>D023</u>	EXTERIOR	10-4"	10-0"	8'-8"	35	HOLLOW CORE	PAIN	VINYL	PRE FINISHED	SLIDING DOOR	1	✓	✓	✓	✓	SLIDING GLASS DOOR

NOTE :	
ST1	PREFABRICATED STAIRS ARE SHOWN HERE FOR REFERENCE ONLY. STAIRS TO BE INSTALLED AS PER OWNERS CHOICE IN ACCORDANCE WITH MANUFACTURING SPECIFICATIONS. OWNER TO SUBMIT SHOP DRAWINGS FOR APPROVAL.



PROJECT NAME AND ADDRESS :
PROPOSED CUSTOM HOUSE WITH
UNFINISHED BASEMENT AT LOT-1,
44-45 LONGVIEW PLACE,
MISSISSAUGA ,ON



technoarchitects

MEP CONSULTANT :

DRAWN BY EM

APPROVED BY HB

1/4"=1'-0"	A1
SHEET NO A2.3	STAGE ZONING

00	R0
ISSUED DATE	2024-05-12

ISSUED DATE	2024-05-13
-------------	------------