**CPE Structural Consultants Limited**
49A Lesmill Road, Toronto, ON, M3B 2T8
T416.447.8555 • www.cpestructural.ca

#250120

October 19, 2026

1315 Bough Beeches Boulevard Limited
2700 Dufferin Street, Unit 50
Toronto ON
M6B 4J3

**Attn: Farrah Ward**

Re: 1315 Bough Beeches, Mississauga, ON- Truck Loading (SPA Submission)

The purpose of this letter is to respond to a request for confirmation whether the waste collection vehicles will be required to drive onto or over a supported structure to service the proposed building.

We can confirm that the intent is for waste collection vehicles to travel over portions of both existing and proposed underground parking structures.

CPE can confirm that the design of the new portion of the underground parking structure, including any trench drains or grating at the waste collection vehicle access route will be designed to support 35-tonne waste collection vehicles. These designs will be provided on the building permit submission drawings. In addition, portions of the existing parking garage under the waste collection vehicle access route for the proposed building will be checked for capacity to support 35-tonne waste collection vehicles to ensure that the new path of waste collection vehicles does not exceed the existing structural capacity. The details of new construction of both the new structure and checks of the existing garage to avoid exceeding existing structural capacity at the new waste collection vehicle access route will be included in the building permit submission drawings.

Should you require any additional information at this time, please do not hesitate to contact our office.

Yours very truly,
CPE Structural Consultants Limited

Chris Palin, PEng.

