


ESTABLISHED GRADE CALCULATION				
LENGTH NO.	START ELEV.	END ELEV.	LENGTH	AVERAGE ((el.1 + el.2)/2) x L
1	148.82	149.40	50.0 m	7459.23
2	149.40	149.40	6.9 m	1031.61
3	149.40	149.27	4.4 m	652.59
4	149.27	149.82	17.8 m	2662.65
5	149.82	149.73	24.1 m	3602.84
6	149.73	149.75	4.5 m	675.33
7	149.75	149.75	16.1 m	2408.73
8	149.75	149.71	3.1 m	469.40
9	149.71	149.34	16.6 m	2486.60
10	149.34	148.90	20.3 m	3030.86
11	148.90	148.82	3.8 m	570.88
TOTAL			167.7 m	25050.72
ESTABLISHED GRADE				149.40



CLIENT		
1315 Bough Beeches Boulevard Limited 2700 Dufferin Street, Unit 50 Toronto ON M6B 4J3		
COPYRIGHT		
This drawing has been prepared solely for the intended use, thus any reproduction or distribution for any purpose other than authorized by Arcadis is forbidden. Written dimensions shall have precedence over scaled dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and Arcadis shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted by Arcadis for general conformance before proceeding with fabrication.		
Arcadis Architects (Canada) Inc.		
ISSUES		
No.	DESCRIPTION	DATE
1	OPA/ZBA SUBMISSION	2026-03-13
KEY PLAN		
CONSULTANTS		
SEAL		
PROJECT		
1315 BOUGH BEECHES BOULEVARD		
PROJECT NO: 30280666		
DRAWN BY:		CHECKED BY:
PROJECT MGR:		APPROVED BY:
SHEET TITLE		SCALE
ESTABLISHED GRADE		1:200
SHEET NUMBER		DATE
A100c		2026-03-13
		ISSUE



SCALE CHECK
1/10mm